

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS AND MINING						FORM 3 AMENDED REPORT				
<b>APPLICATION FOR PERMIT TO DRILL</b>						1. WELL NAME and NUMBER Three Rivers Federal 35-34-720				
2. TYPE OF WORK DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>						3. FIELD OR WILDCAT WILDCAT				
4. TYPE OF WELL Oil Well Coalbed Methane Well: NO						5. UNIT or COMMUNITIZATION AGREEMENT NAME				
6. NAME OF OPERATOR AXIA ENERGY LLC						7. OPERATOR PHONE 720 746-5200				
8. ADDRESS OF OPERATOR 1430 Larimer Ste 400, Denver, CO, 80202						9. OPERATOR E-MAIL rsatre@axiaenergy.com				
10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE) UTU-88623			11. MINERAL OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>			12. SURFACE OWNERSHIP FEDERAL <input checked="" type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input type="checkbox"/> FEE <input type="checkbox"/>				
13. NAME OF SURFACE OWNER (if box 12 = 'fee')						14. SURFACE OWNER PHONE (if box 12 = 'fee')				
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')						16. SURFACE OWNER E-MAIL (if box 12 = 'fee')				
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')			18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS YES <input type="checkbox"/> (Submit Commingling Application) NO <input checked="" type="checkbox"/>			19. SLANT VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>				
20. LOCATION OF WELL	FOOTAGES		QTR-QTR	SECTION	TOWNSHIP	RANGE	MERIDIAN			
LOCATION AT SURFACE	1597 FSL 2498 FEL		NWSE	35	7.0 S	20.0 E	S			
Top of Uppermost Producing Zone	1584 FSL 2204 FWL		NESW	35	7.0 S	20.0 E	S			
At Total Depth	1584 FSL 2204 FWL		NESW	35	7.0 S	20.0 E	S			
21. COUNTY UINTAH			22. DISTANCE TO NEAREST LEASE LINE (Feet) 1597		23. NUMBER OF ACRES IN DRILLING UNIT 40					
			25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed) 16		26. PROPOSED DEPTH MD: 8990 TVD: 8917					
27. ELEVATION - GROUND LEVEL 4822			28. BOND NUMBER LPM9046683		29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 49-2262 - RNI at Green River					
<b>Hole, Casing, and Cement Information</b>										
String	Hole Size	Casing Size	Length	Weight	Grade & Thread	Max Mud Wt.	Cement	Sacks	Yield	Weight
SURF	11	8.625	0 - 900	32.0	J-55 LT&C	8.7	Premium Lite High Strength	70	2.97	11.5
							Class G	115	1.16	15.8
PROD	7.875	5.5	0 - 8990	17.0	N-80 LT&C	9.2	Premium Lite High Strength	570	2.31	12.0
<b>ATTACHMENTS</b>										
<b>VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES</b>										
<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER					<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN					
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)					<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER					
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)					<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP					
NAME Don Hamilton				TITLE Permitting Agent (Buys & Associates, Inc)				PHONE 435 719-2018		
SIGNATURE				DATE 07/26/2012				EMAIL starpoint@etv.net		
API NUMBER ASSIGNED 43047530060000				APPROVAL  Permit Manager						

## **DRILLING PLAN**

**Axia Energy, LLC**  
**Three Rivers Project**  
**Three Rivers Federal #35-34-720**  
**NESW Sec 35 T7S R20E**  
**Uintah County, Utah**

### 1. **ESTIMATED FORMATION TOPS**

FORMATION	TOP (TVD)	COMMENTS
Uinta	Surface	Gas & Degraded Oil; Possible Brackish H <sub>2</sub> O
Green River*	3,096'	Oil & Associated Gas
Lower Green River*	5,079'	Oil & Associated Gas
Wasatch*	6,917'	Oil & Associated Gas
TD	8,990' (MD) 8,917' (TVD)	

NOTE: Datum, Ground Level (GL) Elevation: 4,822'; Asterisks (\*) denotes target pay intervals

**A)** The Bureau of Land Management (BLM) will be notified within 24 hours of spudding the well. The State of Utah, Division of Oil, Gas and Mining will be notified within 24 hours of spudding the well.

### 2. **CASING PROGRAM**

CASING	HOLE SIZE	DEPTH SET (MD)	CSG SIZE	WGHT	GRD	THRD	CAPACITY (bbl/ft)
CONDUCTOR		50-75	13 3/8				
SURFACE	11	900 ±	8 5/8	32.0	J-55	LTC	0.0609
PRODUCTION	7 7/8	8,990'	5 1/2	17.0	N-80	LTC	0.0232

NOTE: All casing depth intervals are to surface unless otherwise noted.

#### ***Casing Specs***

SIZE (in)	ID (in)	DRIFT DIA (in)	COLLAPSE RESISTANCE (psi)	INTERNAL YIELD (psi)	TENSILE YIELD (lbs)	JOINT STRENGTH (lbs)
8 5/8	7.921	7.796	2,530	3,930	503,000	417,000
5 1/2	4.892	4.767	6,280	7,740	397,000	348,000

**A)** The Bureau of Land Management will be notified 24 hours prior to running casing, cementing, and BOPE testing

**B)** As per 43 CFR 3160, Onshore Oil and Gas Order No. 2, Drilling Operations, Part B.1 h:

- a) Prior to drilling out cement, all casing strings will be pressure tested to 0.22 psi/ft of casing length or 1500 psi, whichever is greater, but not to exceed 70% of minimum internal yield. Pressure decline must not be greater than 10% in 30 minutes.

### **FLOAT EQUIPMENT**

**SURFACE (8 5/8):**

Float Shoe, 1 JNT Casing, Float Collar  
Centralizers: 1<sup>st</sup> 4 Joints: every joint  
Remainder: every third joint

**PRODUCTION (5 1/2):**

Float Shoe, 1 JNT Casing, Float Collar  
Centralizers: 1<sup>st</sup> 4 Joints: every joint  
Remainder: every third joint 500' into surface casing

NOTE: 5 1/2" 17# N-80 or equivalent marker collar or casing joints will be placed at the top of the Green River and approximately 400' above the Wasatch.

### **3. CEMENT PROGRAM**

**CONDUCTOR (13 3/8):**

Ready Mix – Cement to surface

**SURFACE (8 5/8):**

Cement Top: Surface

Lead: 70 sks, Premium Lightweight Cmt w/ additives, 11.50 ppg, 2.97 cf/sk, 50% excess

Tail: 115 sks Class G Cement w/ additives, 15.80 ppg, 1.16 cf/sk, 50% excess

NOTE: The above volumes are based on a gauge-hole + 50% excess.

**PRODUCTION (5 1/2):**

Cement Top – 2,700'

570 sacks – Light Premium Cement w/ additives – 12.0 ppg, 2.31 ft<sup>3</sup>/sk – 20% excess

NOTE: The above volumes are based on gauge hole + 20% excess. Adjustments will be made and volumes will be caliper + 10%.

NOTE: The above volumes are based on a gauged-hole. Adjustments will be made based on caliper.

- A)** For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.
- B)** Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.
- C)** The Bureau of Land Management will be notified 24 hours prior to running casing and cementing.
- D)** As per 43 CFR 3160, Onshore Oil and Gas Order No.2, Drilling Operations, Part B:
  - a) All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe (minimum of 8 hours) prior to drilling out.
  - b) Prior to drilling out cement, casing will be pressure tested to 1500 psi. Pressure decline must not be greater than 10% (150 psi) in 30 minutes.

#### 4. **PRESSURE CONTROL EQUIPMENT**

- A) The Bureau of Land Management will be notified 24 hours prior to all BOPE pressure tests. The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
- C) As per 43 CFR 3160, Onshore Oil and Gas Order No. 2, Drilling Operations, Part A:
  - a) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
  - b) Choke Manifold:
    - i) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
    - ii) Two adjustable chokes will be used in the choke manifold.
    - iii) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
    - iv) Pressure gauges in the well control system will be designed for drilling fluid.
- D) BOPE Testing:
  - a) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
  - b) All BOP tests will be performed with a test plug in place.
  - c) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

INTERVAL	BOP EQUIPMENT
0 – 900 ±	11" Diverter with Rotating Head
900 ± – TD	3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

#### 5. **MUD PROGRAM**

- A) Mud test will be performed at least every 24 hours and after mudding up to determine density, viscosity, gel strength, filtration, and pH.
- B) Gas-detecting equipment will be installed and operated in the mud-return system from top of Green River Formation to TD.
  - a) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T's and anchors.

INTERVAL	MUD WGHT	VISC	FLUID LOSS	COMMENTS
SURF – 900 ±	8.4 – 8.7 ppg	32	NC	Spud Mud
900 ± – TD	8.6 – 9.2 ppg	40	NC	DAP/Gel

NOTE: Mud weight increases will be directed by hole conditions.

#### 6. **ABNORMAL CONDITIONS**

- A) No abnormal pressures or temperatures are anticipated.
  - a) Estimated bottom hole pressure at TD will be approximately 3,861 psi (normal pressure gradient: 0.433 psi/ft).
  - b) Estimated maximum surface pressure will be approximately 1,962 psi (estimated bottom hole minus pressure of partially evacuated hole (gradient: 0.220 psi/ft)).
- B) No hydrogen sulfide is anticipated.



<b>INTERVAL</b>	<b>CONDITION</b>
SURF – 900 ±	Lost Circulation Possible
900 ± – TD	Lost Circulation Possible

## **7. AUXILIARY EQUIPMENT**

- A)** Choke Manifold
- B)** Upper and lower kelly cock with handle available
- C)** Stabbing valve
- D)** Safety valve and subs to fit all string connections in use

## **8. SURVEY & LOGGING PROGRAMS**

- A)** Cores: None anticipated.
- B)** Testing: None anticipated.
- C)** Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D)** Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E)** Mud Logs: Computerized 2-person logging unit will catch and describe 10 foot samples from top of Green River Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).

## **9. HAZARDOUS MATERIALS**

In accordance with Superfund Amendments and Reauthorization Act of 1986 (SARA) Title III, no chemicals subject to reporting in an amount equal to or greater than 10,000 pounds will be used, produced, stored, transported, or disposed of annually in association with the drilling of this well. Furthermore, no extremely hazardous substances, as defined in 40 CFR 355, in threshold planning quantities (TPQ), will be used, produced, stored, transported, or disposed of in association with the drilling of this well.

**T7S, R20E, S.L.B.&M.****AXIA ENERGY**

Well location, THREE RIVERS FEDERAL #35-34-720, located as shown in the NW 1/4 SE 1/4 of Section 35, T7S, R20E, S.L.B.&M., Uintah County, Utah.  
BASIS OF ELEVATION


BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M. TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.

**LINE TABLE**

LINE	DIRECTION	LENGTH
L1	S88°32'44"W	611.19'



SCALE


**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH

**UINTAH ENGINEERING & LAND SURVEYING****85 SOUTH 200 EAST - VERNAL, UTAH 84078****(435) 789-1017**


SCALE 1" = 1000'	DATE SURVEYED: 03-27-12	DATE DRAWN: 03-30-12
PARTY B.H. A.S. R.L.	REFERENCES G.L.O. PLAT	
WEATHER COLD	FILE AXIA ENERGY	



NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°09'48.69" (40.163525)	LATITUDE = 40°09'48.84" (40.163567)
LONGITUDE = 109°38'15.15" (109.637542)	LONGITUDE = 109°38'07.28" (109.635356)
27 (TARGET BOTTOM HOLE)	NAD 27 (SURFACE LOCATION)
LATITUDE = 40°09'48.82" (40.163561)	LATITUDE = 40°09'48.97" (40.163603)
LONGITUDE = 109°38'12.65" (109.636847)	LONGITUDE = 109°38'04.78" (109.634661)

**RECEIVED: July 26, 2012**





**PROPOSED LOCATION:  
THREE RIVERS FEDERAL  
#35-34-720 & #35-44-720**

**LEGEND:**

● PROPOSED LOCATION

**AXIA ENERGY**

**THREE RIVERS FEDERAL #35-34-720 & #35-44-720  
SECTION 35, T7S, R20E, S.L.B.&M.  
NW 1/4 SE 1/4**



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813


**ACCESS ROAD  
MAP**

**04 26 12**  
MONTH DAY YEAR



SCALE: 1:100,000 DRAWN BY: A.T. REVISED: 00-00-00





**LEGEND:**

— EXISTING ROAD  
 - - - - - PROPOSED ACCESS ROAD

**AXIA ENERGY**

**THREE RIVERS FEDERAL #35-34-720 & #35-44-720**  
 SECTION 35, T7S, R20E, S.L.B.&M.  
 NW 1/4 SE 1/4



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813


**ACCESS ROAD  
 MAP**

**04 26 12**  
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: A.T. REVISED: 00-00-00

**B  
 TOPO**





**LEGEND:**

- |                   |                         |
|-------------------|-------------------------|
| ○ DISPOSAL WELLS  | ○ WATER WELLS           |
| ● PRODUCING WELLS | ● ABANDONED WELLS       |
| ● SHUT IN WELLS   | ● TEMPORARILY ABANDONED |



**Utah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**AXIA ENERGY**

**THREE RIVERS FEDERAL #35-34-720 & #35-44-720**  
 SECTION 35, T7S, R20E, S.L.B.&M.  
 NW 1/4 SE 1/4


**TOPOGRAPHIC**  
**MAP**

**04 26 12**  
 MONTH DAY YEAR

SCALE: 1" = 2000' DRAWN BY: A.T. REVISED: 00-00-00







**APPROXIMATE TOTAL PIPELINE DISTANCE = 191' +/-**

**LEGEND:**

- PROPOSED ACCESS ROAD
- - - - - PROPOSED PIPELINE
- - - - - PROPOSED PIPELINE (SERVICING OTHER WELLS)



**Uintah Engineering & Land Surveying**  
85 South 200 East Vernal, Utah 84078  
(435) 789-1017 \* FAX (435) 789-1813



**AXIA ENERGY**

**THREE RIVERS FEDERAL #35-34-720 & #35-44-720**  
**SECTION 35, T7S, R20E, S.L.B.&M.**  
**NW 1/4 SE 1/4**


**TOPOGRAPHIC**  
**MAP**

**04 26 12**  
MONTH DAY YEAR

SCALE: 1" = 1000' DRAWN BY: A.T. REVISED: 00-00-00

**D**  
**TOPO**





**APPROXIMATE TOTAL POWER LINE DISTANCE = 62' +/-**

**LEGEND:**

- PROPOSED ACCESS ROAD
- PROPOSED POWER LINE
- - - - - PROPOSED POWER LINE (SERVICING OTHER WELLS)



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



**AXIA ENERGY**

**THREE RIVERS FEDERAL #35-34-720 & #35-44-720**  
 SECTION 35, T7S, R20E, S.L.B.&M.  
 NW 1/4 SE 1/4

**TOPOGRAPHIC MAP**

**04 26 12**  
 MONTH DAY YEAR

SCALE: 1" = 1000'

DRAWN BY: A.T.

REVISED: 00-00-00

**E**  
**TOPO**





## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Company:</b>	Axia Energy	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site:</b>	SEC 35-T7S-R20E	<b>North Reference:</b>	True
<b>Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	DD		
<b>Design:</b>	Plan #1		

<b>Project</b>	Uintah County, UT		
<b>Map System:</b>	US State Plane 1983	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	North American Datum 1983		
<b>Map Zone:</b>	Utah Northern Zone		

Site		SEC 35-T7S-R20E			
Site Position:		Northing:	3,226,618.84 ft	Latitude:	40.169178
From:	Lat/Long	Easting:	2,161,378.00 ft	Longitude:	-109.636019
Position Uncertainty:	0.0 ft	Slot Radius:	13.200 in	Grid Convergence:	1.23 °

Well	Three Rivers Federal #35-34-720					
Well Position	+N/-S	0.0 ft	Northing:	3,224,578.93 ft	Latitude:	40.163567
	+E/-W	0.0 ft	Easting:	2,161,607.13 ft	Longitude:	-109.635356
Position Uncertainty		0.0 ft	Wellhead Elevation:	ft	Ground Level:	4,822.0 ft

<b>Wellbore</b>	DD				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination</b>	<b>Dip Angle</b>	<b>Field Strength</b>
			(°)	(°)	(nT)
	IGRF2010	6/14/2012	11.03	65.95	52,301

<b>Design</b>	Plan #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.0
<b>Vertical Section:</b>	<b>Depth From (TVD)</b>	<b>+N/-S</b>	<b>+E/-W</b>	<b>Direction</b>
	(ft)	(ft)	(ft)	(°)
	0.0	0.0	0.0	268.57

<b>Plan Sections</b>										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.0	0.00	0.00	0.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.00	0.00	0.00	0.00	
1,766.9	15.34	268.57	1,757.8	-2.6	-102.0	2.00	2.00	0.00	268.57	
3,306.2	15.34	268.57	3,242.2	-12.7	-509.0	0.00	0.00	0.00	0.00	
4,073.1	0.00	0.00	4,000.0	-15.3	-611.1	2.00	-2.00	0.00	180.00	
8,990.1	0.00	0.00	8,917.0	-15.3	-611.1	0.00	0.00	0.00	0.00	Three Rivers Federal

## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Company:</b>	Axia Energy	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site:</b>	SEC 35-T7S-R20E	<b>North Reference:</b>	True
<b>Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	DD		
<b>Design:</b>	Plan #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Comments / Formations
0.0	0.00	0.00	0.0	0.0	0.0	0.0	0.00	0.00	
100.0	0.00	0.00	100.0	0.0	0.0	0.0	0.00	0.00	
200.0	0.00	0.00	200.0	0.0	0.0	0.0	0.00	0.00	
300.0	0.00	0.00	300.0	0.0	0.0	0.0	0.00	0.00	
400.0	0.00	0.00	400.0	0.0	0.0	0.0	0.00	0.00	
500.0	0.00	0.00	500.0	0.0	0.0	0.0	0.00	0.00	
600.0	0.00	0.00	600.0	0.0	0.0	0.0	0.00	0.00	
700.0	0.00	0.00	700.0	0.0	0.0	0.0	0.00	0.00	
800.0	0.00	0.00	800.0	0.0	0.0	0.0	0.00	0.00	
900.0	0.00	0.00	900.0	0.0	0.0	0.0	0.00	0.00	
1,000.0	0.00	0.00	1,000.0	0.0	0.0	0.0	0.00	0.00	KOP @ 1000'
1,100.0	2.00	268.57	1,100.0	0.0	-1.7	1.7	2.00	2.00	
1,200.0	4.00	268.57	1,199.8	-0.2	-7.0	7.0	2.00	2.00	
1,300.0	6.00	268.57	1,299.5	-0.4	-15.7	15.7	2.00	2.00	
1,400.0	8.00	268.57	1,398.7	-0.7	-27.9	27.9	2.00	2.00	
1,500.0	10.00	268.57	1,497.5	-1.1	-43.5	43.5	2.00	2.00	
1,600.0	12.00	268.57	1,595.6	-1.6	-62.6	62.6	2.00	2.00	
1,700.0	14.00	268.57	1,693.1	-2.1	-85.1	85.1	2.00	2.00	
1,766.9	15.34	268.57	1,757.8	-2.6	-102.0	102.0	2.00	2.00	EOB; Inc=15.34°
1,800.0	15.34	268.57	1,789.7	-2.8	-110.8	110.8	0.00	0.00	
1,900.0	15.34	268.57	1,886.1	-3.4	-137.2	137.2	0.00	0.00	
2,000.0	15.34	268.57	1,982.6	-4.1	-163.6	163.7	0.00	0.00	
2,100.0	15.34	268.57	2,079.0	-4.8	-190.1	190.1	0.00	0.00	
2,200.0	15.34	268.57	2,175.4	-5.4	-216.5	216.6	0.00	0.00	
2,300.0	15.34	268.57	2,271.9	-6.1	-243.0	243.1	0.00	0.00	
2,400.0	15.34	268.57	2,368.3	-6.7	-269.4	269.5	0.00	0.00	
2,500.0	15.34	268.57	2,464.8	-7.4	-295.9	296.0	0.00	0.00	
2,600.0	15.34	268.57	2,561.2	-8.1	-322.3	322.4	0.00	0.00	
2,700.0	15.34	268.57	2,657.6	-8.7	-348.8	348.9	0.00	0.00	
2,800.0	15.34	268.57	2,754.1	-9.4	-375.2	375.3	0.00	0.00	
2,900.0	15.34	268.57	2,850.5	-10.0	-401.6	401.8	0.00	0.00	
3,000.0	15.34	268.57	2,946.9	-10.7	-428.1	428.2	0.00	0.00	
3,100.0	15.34	268.57	3,043.4	-11.4	-454.5	454.7	0.00	0.00	
3,154.6	15.34	268.57	3,096.0	-11.7	-469.0	469.1	0.00	0.00	Top Green River
3,200.0	15.34	268.57	3,139.8	-12.0	-481.0	481.1	0.00	0.00	
3,300.0	15.34	268.57	3,236.3	-12.7	-507.4	507.6	0.00	0.00	
3,306.2	15.34	268.57	3,242.2	-12.7	-509.0	509.2	0.00	0.00	Start Drop -2.00
3,400.0	13.46	268.57	3,333.1	-13.3	-532.4	532.5	2.00	-2.00	
3,472.7	12.01	268.57	3,404.0	-13.7	-548.4	548.6	2.00	-2.00	Top Birds Nest
3,500.0	11.46	268.57	3,430.7	-13.9	-553.9	554.1	2.00	-2.00	
3,600.0	9.46	268.57	3,529.1	-14.3	-572.1	572.3	2.00	-2.00	
3,700.0	7.46	268.57	3,628.0	-14.7	-586.8	587.0	2.00	-2.00	
3,800.0	5.46	268.57	3,727.3	-15.0	-598.1	598.2	2.00	-2.00	
3,900.0	3.46	268.57	3,827.0	-15.2	-605.8	606.0	2.00	-2.00	
3,941.0	2.64	268.57	3,868.0	-15.2	-608.0	608.2	2.00	-2.00	Base Birds Nest
4,000.0	1.46	268.57	3,926.9	-15.3	-610.1	610.3	2.00	-2.00	
4,073.1	0.00	0.00	4,000.0	-15.3	-611.1	611.2	2.00	-2.00	EOD; Inc=0°
4,100.0	0.00	0.00	4,026.9	-15.3	-611.1	611.2	0.00	0.00	
4,188.1	0.00	0.00	4,115.0	-15.3	-611.1	611.2	0.00	0.00	Temperature 120
4,200.0	0.00	0.00	4,126.9	-15.3	-611.1	611.2	0.00	0.00	
4,300.0	0.00	0.00	4,226.9	-15.3	-611.1	611.2	0.00	0.00	
4,400.0	0.00	0.00	4,326.9	-15.3	-611.1	611.2	0.00	0.00	

## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Company:</b>	Axia Energy	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site:</b>	SEC 35-T7S-R20E	<b>North Reference:</b>	True
<b>Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	DD		
<b>Design:</b>	Plan #1		

Planned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Comments / Formations
4,500.0	0.00	0.00	4,426.9	-15.3	-611.1	611.2	0.00	0.00	
4,600.0	0.00	0.00	4,526.9	-15.3	-611.1	611.2	0.00	0.00	
4,700.0	0.00	0.00	4,626.9	-15.3	-611.1	611.2	0.00	0.00	
4,800.0	0.00	0.00	4,726.9	-15.3	-611.1	611.2	0.00	0.00	
4,900.0	0.00	0.00	4,826.9	-15.3	-611.1	611.2	0.00	0.00	
5,000.0	0.00	0.00	4,926.9	-15.3	-611.1	611.2	0.00	0.00	
5,100.0	0.00	0.00	5,026.9	-15.3	-611.1	611.2	0.00	0.00	
5,152.1	0.00	0.00	5,079.0	-15.3	-611.1	611.2	0.00	0.00	Garden Gulch (MGR Marker)
5,200.0	0.00	0.00	5,126.9	-15.3	-611.1	611.2	0.00	0.00	
5,300.0	0.00	0.00	5,226.9	-15.3	-611.1	611.2	0.00	0.00	
5,400.0	0.00	0.00	5,326.9	-15.3	-611.1	611.2	0.00	0.00	
5,500.0	0.00	0.00	5,426.9	-15.3	-611.1	611.2	0.00	0.00	
5,600.0	0.00	0.00	5,526.9	-15.3	-611.1	611.2	0.00	0.00	
5,700.0	0.00	0.00	5,626.9	-15.3	-611.1	611.2	0.00	0.00	
5,800.0	0.00	0.00	5,726.9	-15.3	-611.1	611.2	0.00	0.00	
5,900.0	0.00	0.00	5,826.9	-15.3	-611.1	611.2	0.00	0.00	
6,000.0	0.00	0.00	5,926.9	-15.3	-611.1	611.2	0.00	0.00	
6,100.0	0.00	0.00	6,026.9	-15.3	-611.1	611.2	0.00	0.00	
6,200.0	0.00	0.00	6,126.9	-15.3	-611.1	611.2	0.00	0.00	
6,300.0	0.00	0.00	6,226.9	-15.3	-611.1	611.2	0.00	0.00	
6,400.0	0.00	0.00	6,326.9	-15.3	-611.1	611.2	0.00	0.00	
6,500.0	0.00	0.00	6,426.9	-15.3	-611.1	611.2	0.00	0.00	
6,600.0	0.00	0.00	6,526.9	-15.3	-611.1	611.2	0.00	0.00	
6,700.0	0.00	0.00	6,626.9	-15.3	-611.1	611.2	0.00	0.00	
6,800.0	0.00	0.00	6,726.9	-15.3	-611.1	611.2	0.00	0.00	
6,840.1	0.00	0.00	6,767.0	-15.3	-611.1	611.2	0.00	0.00	Top Uteland Butte (LGR Marker)
6,900.0	0.00	0.00	6,826.9	-15.3	-611.1	611.2	0.00	0.00	
6,990.1	0.00	0.00	6,917.0	-15.3	-611.1	611.2	0.00	0.00	Top Wasatch (Base Uteland)
7,000.0	0.00	0.00	6,926.9	-15.3	-611.1	611.2	0.00	0.00	
7,100.0	0.00	0.00	7,026.9	-15.3	-611.1	611.2	0.00	0.00	
7,200.0	0.00	0.00	7,126.9	-15.3	-611.1	611.2	0.00	0.00	
7,300.0	0.00	0.00	7,226.9	-15.3	-611.1	611.2	0.00	0.00	
7,400.0	0.00	0.00	7,326.9	-15.3	-611.1	611.2	0.00	0.00	
7,500.0	0.00	0.00	7,426.9	-15.3	-611.1	611.2	0.00	0.00	
7,600.0	0.00	0.00	7,526.9	-15.3	-611.1	611.2	0.00	0.00	
7,700.0	0.00	0.00	7,626.9	-15.3	-611.1	611.2	0.00	0.00	
7,800.0	0.00	0.00	7,726.9	-15.3	-611.1	611.2	0.00	0.00	
7,900.0	0.00	0.00	7,826.9	-15.3	-611.1	611.2	0.00	0.00	
8,000.0	0.00	0.00	7,926.9	-15.3	-611.1	611.2	0.00	0.00	
8,100.0	0.00	0.00	8,026.9	-15.3	-611.1	611.2	0.00	0.00	
8,200.0	0.00	0.00	8,126.9	-15.3	-611.1	611.2	0.00	0.00	
8,300.0	0.00	0.00	8,226.9	-15.3	-611.1	611.2	0.00	0.00	
8,400.0	0.00	0.00	8,326.9	-15.3	-611.1	611.2	0.00	0.00	
8,500.0	0.00	0.00	8,426.9	-15.3	-611.1	611.2	0.00	0.00	
8,600.0	0.00	0.00	8,526.9	-15.3	-611.1	611.2	0.00	0.00	
8,700.0	0.00	0.00	8,626.9	-15.3	-611.1	611.2	0.00	0.00	
8,800.0	0.00	0.00	8,726.9	-15.3	-611.1	611.2	0.00	0.00	
8,900.0	0.00	0.00	8,826.9	-15.3	-611.1	611.2	0.00	0.00	
8,990.1	0.00	0.00	8,917.0	-15.3	-611.1	611.2	0.00	0.00	TD at 8990.1 - Three Rivers Federal #35-34-720

## Planning Report

<b>Database:</b>	USA EDM 5000 Multi Users DB	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Company:</b>	Axia Energy	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Project:</b>	Uintah County, UT	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site:</b>	SEC 35-T7S-R20E	<b>North Reference:</b>	True
<b>Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Wellbore:</b>	DD		
<b>Design:</b>	Plan #1		

Targets									
Target Name									
- hit/miss target	Dip Angle	Dip Dir.	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
- Shape	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(ft)		
Three Rivers Federal #3	0.00	0.00	8,917.0	-15.3	-611.1	3,224,550.53	2,160,996.54	40.163525	-109.637542
- plan hits target center									
- Circle (radius 50.0)									

Formations						
Measured Depth	Vertical Depth	Name	Lithology	Dip	Dip Direction	
(ft)	(ft)			(°)	(°)	
3,154.6	3,096.0	Top Green River				
3,472.7	3,404.0	Top Birds Nest				
3,941.0	3,868.0	Base Birds Nest				
4,188.1	4,115.0	Temperature 120				
5,152.1	5,079.0	Garden Gulch (MGR Marker)				
6,840.1	6,767.0	Top Uteland Butte (LGR Marker)				
6,990.1	6,917.0	Top Wasatch (Base Uteland)				

Plan Annotations				
Measured Depth	Vertical Depth	Local Coordinates		Comment
(ft)	(ft)	+N/-S (ft)	+E/-W (ft)	
1,000.0	1,000.0	0.0	0.0	KOP @ 1000'
1,766.9	1,757.8	-2.6	-102.0	EOB; Inc=15.34°
3,306.2	3,242.2	-12.7	-509.0	Start Drop -2.00
4,073.1	4,000.0	-15.3	-611.1	EOD; Inc=0°
8,990.1	8,917.0	-15.3	-611.1	TD at 8990.1

# **Axia Energy**

**Uintah County, UT**

**SEC 35-T7S-R20E**

**Three Rivers Federal #35-34-720**

**DD**

**Plan #1**

## **Anticollision Report**

**14 June, 2012**

## Anticollision Report

<b>Company:</b>	Axia Energy	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Project:</b>	Uintah County, UT	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Reference Site:</b>	SEC 35-T7S-R20E	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site Error:</b>	0.0ft	<b>North Reference:</b>	True
<b>Reference Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	DD	<b>Database:</b>	USA EDM 5000 Multi Users DB
<b>Reference Design:</b>	Plan #1	<b>Offset TVD Reference:</b>	Offset Datum

Reference	Plan #1		
Filter type:	GLOBAL FILTER APPLIED: All wellpaths within 200'+ 100/1000 of reference		
Interpolation Method:	MD Interval 100.0ft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 1,099.0ft	Error Surface:	Elliptical Conic
Warning Levels Evaluated at:	2.00 Sigma		

Survey Tool Program		Date	6/14/2012		
From (ft)	To (ft)	Survey (Wellbore)	Tool Name	Description	
0.0	8,990.1	Plan #1 (DD)	MWD	Geolink MWD	

Summary						
Site Name	Reference Measured Depth (ft)	Offset Measured Depth (ft)	Distance Between Centres (ft)	Distance Between Ellipses (ft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
SEC 35-T7S-R20E						
Three Rivers Federal #35-44-720 - DD - Plan #1	1,000.0	1,000.0	16.5	13.0	4.798	CC
Three Rivers Federal #35-44-720 - DD - Plan #1	1,000.4	1,000.4	16.5	13.0	4.796	ES
Three Rivers Federal #35-44-720 - DD - Plan #1	1,100.0	1,099.8	17.1	13.3	4.524	SF

## Anticollision Report

<b>Company:</b>	Axia Energy	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Project:</b>	Uintah County, UT	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Reference Site:</b>	SEC 35-T7S-R20E	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site Error:</b>	0.0ft	<b>North Reference:</b>	True
<b>Reference Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	DD	<b>Database:</b>	USA EDM 5000 Multi Users DB
<b>Reference Design:</b>	Plan #1	<b>Offset TVD Reference:</b>	Offset Datum

Offset Design SEC 35-T7S-R20E - Three Rivers Federal #35-44-720 - DD - Plan #1														Offset Site Error:	0.0 ft
Survey Program: O-MWD														Offset Well Error:	0.0 ft
Reference		Offset		Semi Major Axis		Distance									
Measured Depth (ft)	Vertical Depth (ft)	Measured Depth (ft)	Vertical Depth (ft)	Reference (ft)	Offset (ft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (ft)	+E/-W (ft)	Between Centres (ft)	Between Ellipses (ft)	Total Uncertainty Axis	Separation Factor	Warning		
0.0	0.0	0.0	0.0	0.0	0.0	174.16	-16.4	1.7	16.5						
100.0	100.0	100.0	100.0	0.1	0.1	174.16	-16.4	1.7	16.5	16.2	0.29	56.208			
200.0	200.0	200.0	200.0	0.3	0.3	174.16	-16.4	1.7	16.5	15.8	0.64	25.660			
300.0	300.0	300.0	300.0	0.5	0.5	174.16	-16.4	1.7	16.5	15.5	0.99	16.625			
400.0	400.0	400.0	400.0	0.7	0.7	174.16	-16.4	1.7	16.5	15.1	1.34	12.296			
500.0	500.0	500.0	500.0	0.8	0.8	174.16	-16.4	1.7	16.5	14.8	1.69	9.755			
600.0	600.0	600.0	600.0	1.0	1.0	174.16	-16.4	1.7	16.5	14.4	2.04	8.085			
700.0	700.0	700.0	700.0	1.2	1.2	174.16	-16.4	1.7	16.5	14.1	2.39	6.903			
800.0	800.0	800.0	800.0	1.4	1.4	174.16	-16.4	1.7	16.5	13.7	2.74	6.022			
900.0	900.0	900.0	900.0	1.5	1.5	174.16	-16.4	1.7	16.5	13.4	3.09	5.341			
1,000.0	1,000.0	1,000.0	1,000.0	1.7	1.7	174.16	-16.4	1.7	16.5	13.0	3.43	4.798 CC			
1,000.4	1,000.4	1,000.4	1,000.4	1.7	1.7	-94.41	-16.4	1.7	16.5	13.0	3.44	4.796 ES			
1,100.0	1,100.0	1,099.8	1,099.8	1.9	1.9	-106.08	-16.4	3.4	17.1	13.3	3.79	4.524 SF			
1,200.0	1,199.8	1,198.9	1,198.8	2.1	2.1	-132.33	-16.3	8.6	22.4	18.3	4.14	5.423			
1,300.0	1,299.5	1,296.6	1,296.1	2.3	2.3	-152.41	-16.2	17.0	36.5	32.0	4.48	8.149			
1,400.0	1,398.7	1,393.8	1,392.7	2.5	2.5	-162.67	-16.0	27.5	57.7	52.9	4.80	12.020			
1,500.0	1,497.5	1,490.3	1,488.7	2.7	2.7	-167.85	-15.9	37.9	83.2	78.1	5.13	16.231			
1,600.0	1,595.6	1,585.8	1,583.6	3.1	2.9	-170.87	-15.8	48.2	112.3	106.9	5.44	20.647			
1,700.0	1,693.1	1,680.3	1,677.5	3.4	3.1	-172.80	-15.6	58.4	144.9	139.2	5.75	25.216			
1,800.0	1,789.7	1,773.6	1,770.3	3.8	3.3	-174.14	-15.5	68.4	180.7	174.6	6.06	29.831			
1,900.0	1,886.1	1,866.6	1,862.8	4.2	3.5	-175.09	-15.3	78.5	217.3	210.9	6.39	34.005			
2,000.0	1,982.6	1,959.6	1,955.2	4.7	3.8	-175.77	-15.2	88.5	253.9	247.1	6.72	37.771			
2,100.0	2,079.0	2,052.7	2,047.7	5.1	4.0	-176.28	-15.1	98.5	290.5	283.4	7.05	41.187			
2,200.0	2,175.4	2,145.7	2,140.2	5.6	4.2	-176.68	-14.9	108.6	327.1	319.8	7.38	44.298			
2,300.0	2,271.9	2,238.7	2,232.7	6.1	4.4	-176.99	-14.8	118.6	363.8	356.1	7.72	47.142			
2,400.0	2,368.3	2,331.7	2,325.2	6.6	4.7	-177.25	-14.6	128.6	400.5	392.4	8.05	49.754			
2,500.0	2,464.8	2,424.7	2,417.6	7.0	4.9	-177.47	-14.5	138.7	437.1	428.7	8.38	52.160			
2,600.0	2,561.2	2,517.8	2,510.1	7.5	5.1	-177.65	-14.4	148.7	473.8	465.1	8.71	54.383			
2,700.0	2,657.6	2,610.8	2,602.6	8.0	5.4	-177.80	-14.2	158.7	510.5	501.4	9.04	56.444			
2,800.0	2,754.1	2,703.8	2,695.1	8.5	5.6	-177.94	-14.1	168.8	547.2	537.8	9.38	58.359			
2,900.0	2,850.5	2,796.8	2,787.6	9.0	5.8	-178.06	-14.0	178.8	583.8	574.1	9.71	60.144			
3,000.0	2,946.9	2,889.9	2,880.0	9.5	6.0	-178.16	-13.8	188.8	620.5	610.5	10.04	61.812			
3,100.0	3,043.4	2,982.9	2,972.5	10.0	6.3	-178.25	-13.7	198.9	657.2	646.8	10.37	63.373			
3,200.0	3,139.8	3,075.9	3,065.0	10.5	6.5	-178.33	-13.5	208.9	693.9	683.2	10.70	64.838			
3,300.0	3,236.3	3,168.9	3,157.5	11.0	6.8	-178.41	-13.4	218.9	730.6	719.6	11.03	66.215			
3,400.0	3,333.1	3,262.5	3,250.5	11.4	7.0	-178.49	-13.3	229.0	765.9	754.4	11.42	67.085			
3,500.0	3,430.7	3,357.2	3,344.7	11.8	7.2	-178.56	-13.1	239.2	797.8	786.0	11.80	67.630			
3,600.0	3,529.1	3,453.0	3,439.9	12.2	7.5	-178.62	-13.0	249.6	826.5	814.3	12.17	67.900			
3,700.0	3,628.0	3,549.8	3,536.1	12.4	7.7	-178.66	-12.8	260.0	851.8	839.2	12.54	67.920			
3,800.0	3,727.3	3,647.3	3,633.1	12.7	8.0	-178.70	-12.7	270.5	873.7	860.8	12.90	67.712			
3,900.0	3,827.0	3,763.7	3,748.8	12.9	8.2	-178.73	-12.5	282.5	891.7	878.5	13.29	67.107			
4,000.0	3,926.9	3,908.5	3,893.3	13.0	8.5	-178.75	-12.4	291.5	902.3	888.6	13.71	65.789			
4,100.0	4,026.9	4,042.1	4,026.9	13.1	8.7	89.82	-12.4	293.5	904.6	890.5	14.12	64.080			
4,200.0	4,126.9	4,142.1	4,126.9	13.2	8.8	89.82	-12.4	293.5	904.6	890.1	14.47	62.529			
4,300.0	4,226.9	4,242.1	4,226.9	13.3	9.0	89.82	-12.4	293.5	904.6	889.8	14.82	61.053			
4,400.0	4,326.9	4,342.1	4,326.9	13.4	9.1	89.82	-12.4	293.5	904.6	889.4	15.17	59.644			
4,500.0	4,426.9	4,442.1	4,426.9	13.5	9.3	89.82	-12.4	293.5	904.6	889.1	15.52	58.299			
4,600.0	4,526.9	4,542.1	4,526.9	13.6	9.4	89.82	-12.4	293.5	904.6	888.7	15.87	57.014			
4,700.0	4,626.9	4,642.1	4,626.9	13.7	9.6	89.82	-12.4	293.5	904.6	888.4	16.22	55.784			
4,800.0	4,726.9	4,742.1	4,726.9	13.8	9.7	89.82	-12.4	293.5	904.6	888.0	16.57	54.606			
4,900.0	4,826.9	4,842.1	4,826.9	13.9	9.9	89.82	-12.4	293.5	904.6	887.7	16.92	53.477			
5,000.0	4,926.9	4,942.1	4,926.9	14.0	10.0	89.82	-12.4	293.5	904.6	887.3	17.26	52.394			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

## Anticollision Report

<b>Company:</b>	Axia Energy	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Project:</b>	Uintah County, UT	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Reference Site:</b>	SEC 35-T7S-R20E	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site Error:</b>	0.0ft	<b>North Reference:</b>	True
<b>Reference Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	DD	<b>Database:</b>	USA EDM 5000 Multi Users DB
<b>Reference Design:</b>	Plan #1	<b>Offset TVD Reference:</b>	Offset Datum

Offset Design SEC 35-T7S-R20E - Three Rivers Federal #35-44-720 - DD - Plan #1													Offset Site Error: 0.0 ft	
Survey Program: 0-MWD													Offset Well Error: 0.0 ft	
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth	Vertical	Measured Depth	Vertical	Reference	Offset	Highside	Offset Wellbore Centre		Between	Between	Total	Separation		
Depth (ft)	Depth (ft)	Depth (ft)	Depth (ft)	(ft)	(ft)	Toolface (°)	+N/-S (ft)	+E/-W (ft)	Centres (ft)	Ellipses (ft)	Uncertainty Axis	Factor		
5,100.0	5,026.9	5,042.1	5,026.9	14.1	10.2	89.82	-12.4	293.5	904.6	887.0	17.61	51.353		
5,200.0	5,126.9	5,142.1	5,126.9	14.2	10.3	89.82	-12.4	293.5	904.6	886.6	17.96	50.354		
5,300.0	5,226.9	5,242.1	5,226.9	14.3	10.5	89.82	-12.4	293.5	904.6	886.3	18.31	49.393		
5,400.0	5,326.9	5,342.1	5,326.9	14.4	10.6	89.82	-12.4	293.5	904.6	885.9	18.66	48.467		
5,500.0	5,426.9	5,442.1	5,426.9	14.6	10.8	89.82	-12.4	293.5	904.6	885.6	19.01	47.576		
5,600.0	5,526.9	5,542.1	5,526.9	14.7	10.9	89.82	-12.4	293.5	904.6	885.2	19.36	46.717		
5,700.0	5,626.9	5,642.1	5,626.9	14.8	11.1	89.82	-12.4	293.5	904.6	884.9	19.71	45.889		
5,800.0	5,726.9	5,742.1	5,726.9	14.9	11.2	89.82	-12.4	293.5	904.6	884.5	20.06	45.089		
5,900.0	5,826.9	5,842.1	5,826.9	15.0	11.4	89.82	-12.4	293.5	904.6	884.2	20.41	44.317		
6,000.0	5,926.9	5,942.1	5,926.9	15.1	11.5	89.82	-12.4	293.5	904.6	883.8	20.76	43.571		
6,100.0	6,026.9	6,042.1	6,026.9	15.3	11.7	89.82	-12.4	293.5	904.6	883.5	21.11	42.850		
6,200.0	6,126.9	6,142.1	6,126.9	15.4	11.9	89.82	-12.4	293.5	904.6	883.1	21.46	42.152		
6,300.0	6,226.9	6,242.1	6,226.9	15.5	12.0	89.82	-12.4	293.5	904.6	882.8	21.81	41.476		
6,400.0	6,326.9	6,342.1	6,326.9	15.6	12.2	89.82	-12.4	293.5	904.6	882.4	22.16	40.822		
6,500.0	6,426.9	6,442.1	6,426.9	15.8	12.3	89.82	-12.4	293.5	904.6	882.1	22.51	40.188		
6,600.0	6,526.9	6,542.1	6,526.9	15.9	12.5	89.82	-12.4	293.5	904.6	881.7	22.86	39.574		
6,700.0	6,626.9	6,642.1	6,626.9	16.0	12.7	89.82	-12.4	293.5	904.6	881.4	23.21	38.978		
6,800.0	6,726.9	6,742.1	6,726.9	16.1	12.8	89.82	-12.4	293.5	904.6	881.0	23.56	38.400		
6,900.0	6,826.9	6,842.1	6,826.9	16.3	13.0	89.82	-12.4	293.5	904.6	880.7	23.91	37.839		
7,000.0	6,926.9	6,942.1	6,926.9	16.4	13.1	89.82	-12.4	293.5	904.6	880.3	24.26	37.294		
7,100.0	7,026.9	7,042.1	7,026.9	16.5	13.3	89.82	-12.4	293.5	904.6	880.0	24.60	36.764		
7,200.0	7,126.9	7,142.1	7,126.9	16.7	13.5	89.82	-12.4	293.5	904.6	879.6	24.95	36.249		
7,300.0	7,226.9	7,242.1	7,226.9	16.8	13.6	89.82	-12.4	293.5	904.6	879.3	25.30	35.749		
7,400.0	7,326.9	7,342.1	7,326.9	16.9	13.8	89.82	-12.4	293.5	904.6	878.9	25.65	35.262		
7,500.0	7,426.9	7,442.1	7,426.9	17.1	13.9	89.82	-12.4	293.5	904.6	878.6	26.00	34.788		
7,600.0	7,526.9	7,542.1	7,526.9	17.2	14.1	89.82	-12.4	293.5	904.6	878.2	26.35	34.327		
7,700.0	7,626.9	7,642.1	7,626.9	17.3	14.3	89.82	-12.4	293.5	904.6	877.9	26.70	33.878		
7,800.0	7,726.9	7,742.1	7,726.9	17.5	14.4	89.82	-12.4	293.5	904.6	877.5	27.05	33.441		
7,900.0	7,826.9	7,842.1	7,826.9	17.6	14.6	89.82	-12.4	293.5	904.6	877.2	27.40	33.014		
8,000.0	7,926.9	7,942.1	7,926.9	17.7	14.8	89.82	-12.4	293.5	904.6	876.8	27.75	32.599		
8,100.0	8,026.9	8,042.1	8,026.9	17.9	14.9	89.82	-12.4	293.5	904.6	876.5	28.10	32.193		
8,200.0	8,126.9	8,142.1	8,126.9	18.0	15.1	89.82	-12.4	293.5	904.6	876.1	28.45	31.798		
8,300.0	8,226.9	8,242.1	8,226.9	18.1	15.2	89.82	-12.4	293.5	904.6	875.8	28.80	31.412		
8,400.0	8,326.9	8,342.1	8,326.9	18.3	15.4	89.82	-12.4	293.5	904.6	875.4	29.15	31.036		
8,500.0	8,426.9	8,442.1	8,426.9	18.4	15.6	89.82	-12.4	293.5	904.6	875.1	29.50	30.668		
8,600.0	8,526.9	8,542.1	8,526.9	18.6	15.7	89.82	-12.4	293.5	904.6	874.7	29.84	30.309		
8,700.0	8,626.9	8,642.1	8,626.9	18.7	15.9	89.82	-12.4	293.5	904.6	874.4	30.19	29.959		
8,800.0	8,726.9	8,742.1	8,726.9	18.8	16.1	89.82	-12.4	293.5	904.6	874.0	30.54	29.616		
8,900.0	8,826.9	8,842.1	8,826.9	19.0	16.2	89.82	-12.4	293.5	904.6	873.7	30.89	29.281		
8,990.1	8,917.0	8,932.2	8,917.0	19.1	16.4	89.82	-12.4	293.5	904.6	873.4	31.21	28.986		



## Anticollision Report

<b>Company:</b>	Axia Energy	<b>Local Co-ordinate Reference:</b>	Well Three Rivers Federal #35-34-720
<b>Project:</b>	Uintah County, UT	<b>TVD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Reference Site:</b>	SEC 35-T7S-R20E	<b>MD Reference:</b>	WELL @ 4838.0ft (Original Well Elev)
<b>Site Error:</b>	0.0ft	<b>North Reference:</b>	True
<b>Reference Well:</b>	Three Rivers Federal #35-34-720	<b>Survey Calculation Method:</b>	Minimum Curvature
<b>Well Error:</b>	0.0ft	<b>Output errors are at</b>	2.00 sigma
<b>Reference Wellbore</b>	DD	<b>Database:</b>	USA EDM 5000 Multi Users DB
<b>Reference Design:</b>	Plan #1	<b>Offset TVD Reference:</b>	Offset Datum

Reference Depths are relative to WELL @ 4838.0ft (Original Well Elev)


Offset Depths are relative to Offset Datum

Central Meridian is -111.500000 °

Coordinates are relative to: Three Rivers Federal #35-34-720

Coordinate System is US State Plane 1983, Utah Northern Zone

Grid Convergence at Surface is: 1.23°



# BOP Equipment

3000psi WP




EXHIBIT "F"



2580 Creekview Road  
Moab, Utah 84532  
435/719-2018

July 27, 2012

Mrs. Diana Mason  
State of Utah  
Division of Oil Gas and Mining  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801

RE: Request for Exception to Spacing – Axia Energy, LLC – **Three Rivers Federal 35-34-720**  
*Surface Location:* 1597' FSL & 2498' FEL, NW/4 SE/4, Section 35, T7S, R20E,  
*Target Location:* 1584' FSL & 2204' FWL, NE/4 SW/4, Section 35, T7S, R20E,  
SLB&M, Uintah County, Utah

Dear Diana:

Axia Energy, LLC respectfully submits this request for exception to spacing (R649-3-11) based on geology since the well is located less than 460 feet to the drilling unit boundary. Axia Energy, LLC is the only owner and operator within 460 feet of the surface and target location as well as all points along the intended well bore path and are not within 460 feet of any uncommitted tracts or a unit boundary.

Thank you very much for your timely consideration of this application. Please feel free to contact Jess A. Peonio of Axia Energy, LLC at 720-746-5212 or myself should you have any questions or need additional information.

Sincerely,

*Don Hamilton*

Don Hamilton  
Agent for Axia Energy, LLC

cc: Jess A. Peonio, Axia Energy, LLC

RECEIVED: July 26, 2012


## AXIA ENERGY

## LOCATION LAYOUT FOR

THREE RIVERS FEDERAL #35-34-720 & #35-44-720  
SECTION 35, T7S, R20E, S.L.B.&M.  
NW 1/4 SE 1/4

FIGURE #1

SCALE: 1" = 60'  
DATE: 03-30-12  
DRAWN BY: R.L.



Elev. Ungraded Ground At #35-34-720 Loc. Stake = 4822.5', UTAH ENGINEERING & LAND SURVEYING  
FINISHED GRADE ELEV. AT #35-34-720 LOC. STAKE = 4822.2' 85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

RECEIVED: July 26, 2012






## AXIA ENERGY

FIGURE #2

X-Section  
Scale  
1" = 100'

TYPICAL CROSS SECTIONS FOR  
THREE RIVERS FEDERAL #35-34-720 & #35-44-720  
SECTION 35, T7S, R20E, S.L.B.&M.  
NW 1/4 SE 1/4

DATE: 03-30-12  
DRAWN BY: R.L.



## NOTE:

Topsoil should not be  
Stripped Below Finished  
Grade on Substructure Area.

## APPROXIMATE ACREAGES

WELL SITE DISTURBANCE =  $\pm 2.943$  ACRES  
ACCESS ROAD DISTURBANCE =  $\pm 0.078$  ACRES  
TOTAL =  $\pm 3.021$  ACRES

\* NOTE:  
FILL QUANTITY INCLUDES  
5% FOR COMPACTION

## APPROXIMATE YARDAGES

(6") Topsoil Stripping = 2,140 Cu. Yds.  
Remaining Location = 10,280 Cu. Yds.  
TOTAL CUT = 12,420 CU. YDS.  
FILL = 2,030 CU. YDS.

EXCESS MATERIAL = 10,390 Cu. Yds.  
Topsoil & Pit Backfill = 4,990 Cu. Yds.  
(1/2 Pit Vol.)  
EXCESS UNBALANCE = 5,400 Cu. Yds.  
(After Interim Rehabilitation)

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

RECEIVED: July 26, 2012


## AXIA ENERGY

## TYPICAL RIG LAYOUT FOR


THREE RIVERS FEDERAL #35-34-720 & #35-44-720  
SECTION 35, T7S, R20E, S.L.B.&M.  
NW 1/4 SE 1/4

FIGURE #3

SCALE: 1" = 60'  
DATE: 03-30-12  
DRAWN BY: R.L.



NOTE:  
Flare Pit is to be  
located a min. of 100'  
from the Well Head.







## AXIA ENERGY

## INTERIM RECLAMATION PLAN FOR

THREE RIVERS FEDERAL #35-34-720 & #35-44-720  
SECTION 35, T7S, R20E, S.L.B.&M.  
NW 1/4 SE 1/4

FIGURE #4

SCALE: 1" = 60'  
DATE: 03-30-12  
DRAWN BY: R.L.



APPROXIMATE ACREAGES  
UN-RECLAIMED =  $\pm 0.890$  ACRES

Access Road




RECLAIMED AREA

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East \* Vernal, Utah 84078 \* (435) 789-1017

RECEIVED: July 26, 2012







## WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 7/26/2012

API NO. ASSIGNED: 43047530060000

WELL NAME: Three Rivers Federal 35-34-720

OPERATOR: AXIA ENERGY LLC (N3765)

PHONE NUMBER: 435 719-2018

CONTACT: Don Hamilton

PROPOSED LOCATION: NWSE 35 070S 200E

Permit Tech Review: ☒

SURFACE: 1597 FSL 2498 FEL

Engineering Review: ☐

BOTTOM: 1584 FSL 2204 FWL

Geology Review: ☒

COUNTY: UINTAH

LATITUDE: 40.16360

LONGITUDE: -109.63527

UTM SURF EASTINGS: 616216.00

NORTHINGS: 4446808.00

FIELD NAME: WILDCAT

LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU-88623

PROPOSED PRODUCING FORMATION(S): WASATCH

SURFACE OWNER: 1 - Federal

COALBED METHANE: NO

## RECEIVED AND/OR REVIEWED:

☒ PLAT☒ Bond: FEDERAL - LPM9046683☐ Potash☐ Oil Shale 190-5☐ Oil Shale 190-3☐ Oil Shale 190-13☒ Water Permit: 49-2262 - RNI at Green River☐ RDCC Review:☐ Fee Surface Agreement☐ Intent to Commingle

Commingle Approved

## LOCATION AND SITING:

☐ R649-2-3.

Unit:

☐ R649-3-2. General☒ R649-3-3. Exception☒ Drilling Unit

Board Cause No: R649-3-11

Effective Date:

Siting:

☒ R649-3-11. Directional Drill

Comments: Presite Completed

Stipulations: 1 - Exception Location - dmason  
4 - Federal Approval - dmason  
15 - Directional - dmason  
23 - Spacing - dmason

RECEIVED: August 02, 2012



GARY R. HERBERT  
*Governor*

GREGORY S. BELL  
*Lieutenant Governor*

# State of Utah

## DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

### Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

## Permit To Drill

\*\*\*\*\*

**Well Name:** Three Rivers Federal 35-34-720  
**API Well Number:** 43047530060000  
**Lease Number:** UTU-88623  
**Surface Owner:** FEDERAL  
**Approval Date:** 8/2/2012

### Issued to:

AXIA ENERGY LLC, 1430 Larimer Ste 400, Denver, CO 80202

### Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of R649-3-11. The expected producing formation or pool is the WASATCH Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

### Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

### Exception Location:

Appropriate information has been submitted to DOGM and administrative approval of the requested exception location is hereby granted.

### General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

### Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

This proposed well is located in an area for which drilling units (well spacing patterns) have not been established through an order of the Board of Oil, Gas and Mining (the "Board"). In order to avoid the possibility of waste or injury to correlative rights, the operator is requested, once the well has been drilled,

completed, and has produced, to analyze geological and engineering data generated therefrom, as well as any similar data from surrounding areas if available. As soon as is practicable after completion of its analysis, and if the analysis suggests an area larger than the quarter-quarter section upon which the well is located is being drained, the operator is requested to seek an appropriate order from the Board establishing drilling and spacing units in conformance with such analysis by filing a Request for Agency Action with the Board.

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

OR

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at <http://oilgas.ogm.utah.gov>

**Reporting Requirements:**

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) - due within 5 days of spudding the well
- Monthly Status Report (Form 9) - due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) - due prior to implementation
- Written Notice of Emergency Changes (Form 9) - due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) - due prior to implementation
- Report of Water Encountered (Form 7) - due within 30 days after completion
- Well Completion Report (Form 8) - due within 30 days after completion or plugging

**Approved By:**

A handwritten signature in black ink, appearing to read "John Rogers", written over a horizontal line.

For John Rogers  
Associate Director, Oil & Gas



RECEIVED

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

JUL 27 2012

FORM APPROVED  
OMB No. 1004-0136  
Expires July 31, 2010

BLM

## APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of Work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		<b>CONFIDENTIAL</b>	
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/> Single Zone <input checked="" type="checkbox"/> Multiple Zone			
2. Name of Operator AXIA ENERGY LLC		Contact: DON S HAMILTON E-Mail: starpoint@etv.net	
3a. Address 1430 LARIMER STREET SUITE #400 DENVER, CO 80202		3b. Phone No. (include area code) Ph: 435-719-2018 Fx: 435-719-2019	
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface NWSE 1597FSL 2498FEL 40.163567 N Lat, 109.635356 W Lon At proposed prod. zone NESW 1584FSL 2204FWL 40.163525 N Lat, 109.637542 W Lon		5. Lease Serial No. UTU88623	
14. Distance in miles and direction from nearest town or post office* 26.8 MILES SOUTHWEST OF VERNAL, UTAH		6. If Indian, Allottee or Tribe Name	
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 1597		7. If Unit or CA Agreement, Name and No.	
16. No. of Acres in Lease 557.80		8. Lease Name and Well No. THREE RIVERS FEDERAL 35-34-720	
17. Distance from proposed location to nearest well, drilling, completed, applied for, on this lease, ft. 16		9. API Well No. 43-047-53006	
18. Proposed Depth 8990 MD 8917 TVD		10. Field and Pool, or Exploratory UNDESIGNATED	
19. Elevations (Show whether DF, KB, RT, GL, etc.) 4822 GL		11. Sec., T., R., M., or Blk. and Survey or Area Sec 35 T7S R20E Mer SLB SME: BLM	
20. Approximate date work will start 10/01/2012		12. County or Parish UINTAH	
21. Estimated duration 60 DAYS		13. State UT	

## 24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO shall be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the authorized officer.

25. Signature (Electronic Submission)	Name (Printed/Typed) DON S HAMILTON Ph: 435-719-2018	Date 07/26/2012
Title PERMITTING AGENT		
Approved by (Signature) 	Name (Printed/Typed) Jerry Kenczka	Date FEB 22 2013
Title Assistant Field Manager Lands & Mineral Resources	Office VERNAL FIELD OFFICE	

Application approval does not warrant or certify the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.  
Conditions of approval, if any, are attached.

CONDITIONS OF APPROVAL ATTACHED

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

RECEIVED

Additional Operator Remarks (see next page)

Electronic Submission #144042 verified by the BLM Well Information System

For AXIA ENERGY LLC, sent to the Vernal

Committed to AFMSS for processing by LESLIE ROBINSON on 08/06/2012 (12LBR0865AE)

DIV. OF OIL, GAS &amp; MINING

NOTICE OF APPROVAL

\*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\* BLM REVISED \*\*



UNITED STATES DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT  
VERNAL FIELD OFFICE

170 South 500 East

VERNAL, UT 84078

(435) 781-4400



**CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL**

Company: Axia Energy, LLC.  
Well No: Three Rivers Federal 35-34-720  
API No: 43-047-53006

Location: NWSE, Sec. 35, T7S, R20E  
Lease No: UTU-88623  
Agreement:

**OFFICE NUMBER: (435) 781-4400**

**OFFICE FAX NUMBER: (435) 781-3420**

**A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR  
FIELD REPRESENTATIVE TO INSURE COMPLIANCE**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. **This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.**

**NOTIFICATION REQUIREMENTS**

Location Construction (Notify Environmental Scientist)	- Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	- Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	- Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to running casing and cementing all casing strings to: <a href="mailto:blm_ut_vn_opreport@blm.gov">blm ut vn opreport@blm.gov</a>
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	- Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	- Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

**SURFACE USE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horsepower must not emit more than 2 gms of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO<sub>x</sub> per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop work and contact the Authorized Officer (AO). A determination will be made by the AO as to what mitigation may be necessary for the discovered paleontologic material before construction can continue.
- All new and replacement internal combustion gas field engines of less than or equal to 300 design-rated horse power must not emit more than 2 grams of NO<sub>x</sub> per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower-hour.
- All new and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 grams of NO<sub>x</sub> per horsepower-hour.
- The following would be used as standard operating procedures: Green completion or controlled VOC emissions methods with 90% efficiency for Oil or Gas Atmospheric Storage Tanks, VOC Venting controls or flaring, Glycol Dehydration and Amine Unites, Well Completion, Re-Completion, Venting, and Planned Blowdown Emissions.
- All vehicles and equipment shall be cleaned either through power-washing, or other approved method, if the vehicles or equipment were previously operated outside the Uinta Basin, to prevent weed seed introduction.
- *Discovery Stipulation:* Reinitiating of section 7 consultation with the USFWS will be sought immediately if any loss of plants or occupied habitat for Uinta Basin hookless cactus is anticipated as a result of project activities.
- No drilling or construction from March 01 – August 31
- The best method to avoid entrainment is to pump from an off-channel location – one that does not connect to the river during high spring flows. An infiltration gallery constructed in a BLM and Service approved location is best.
- If the pump head is located in the river channel where larval fish are known to occur, the following measures apply:
  - do not situate the pump in a low-flow or no-flow area as these habitats tend to concentrate larval fishes;

- limit the amount of pumping, to the greatest extent possible, during that period of the year when larval fish may be present (April 1 to August 31); and
  - limit the amount of pumping, to the greatest extent possible, during the pre-dawn hours as larval drift studies indicate that this is a period of greatest daily activity.
- Screen all pump intakes with 3/32 inch mesh material.
  - Approach velocities for intake structures will follow the National Marine Fisheries Service's document "Fish Screening Criteria for Anadromous Salmonids". For projects with an in-stream intake that operate in stream reaches where larval fish may be present, the approach velocity will not exceed 0.33 feet per second (ft/s).
  - Report any fish impinged on the intake screen to the Service (801.975.3330) and the Utah Division of Wildlife Resources:
    - Northeastern Region
    - 318 North Vernal Ave, Vernal, UT 84078
    - Phone: (435) 781-9453



**DOWNHOLE PROGRAM  
CONDITIONS OF APPROVAL (COAs)**

**SITE SPECIFIC DOWNHOLE COAs:**

- Gamma Ray Log shall be run from Total Depth to Surface.
- CBL will be run from TD to TOC.
- Cement for the surface casing will be circulated to the surface.
- Cement for long-string shall be circulated 200' above surface casing shoe.
- Variances Granted
  - All variances approved as written in APD

**All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to.** The following items are emphasized:

**DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS**

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and **NOT** by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- **Cement baskets shall not be run on surface casing.**

- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM, Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- **Please submit an electronic copy of all other logs run on this well in CD (compact disc) format to the Vernal BLM Field Office. This submission will supersede the requirement for submittal of paper logs to the BLM.**
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.
- **OPERATING REQUIREMENT REMINDERS:**
  - All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
  - For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at [www.ONRR.gov](http://www.ONRR.gov).
  - Should the well be successfully completed for production, the BLM Vernal Field office must be notified when it is placed in a producing status. Such notification will be by written communication and must be received in this office by not later than the fifth business day following the date on which the well is placed on production. The notification shall provide, as a minimum, the following informational items:
    - Operator name, address, and telephone number.
    - Well name and number.
    - Well location (¼¼, Sec., Twn, Rng, and P.M.).
    - Date well was placed in a producing status (date of first production for which royalty will be

- paid).
- The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
  - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
  - Unit agreement and/or participating area name and number, if applicable.
  - Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
  - All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
  - Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid, and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.
  - All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
  - Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office Petroleum Engineers will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports shall be submitted to the BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall be identified as the point of sale or allocation for royalty purposes.
  - A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
  - Any additional construction, reconstruction, or alterations of facilities, including roads, gathering lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.

- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover equipment shall be removed from a well to be placed in a suspended status without prior approval of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior approval of the BLM Vernal Field Office shall be obtained and notification given before resumption of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in order that a representative may witness plugging operations. If a well is suspended or abandoned, all pits must be fenced immediately until they are backfilled. The "Subsequent Report of Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of the well bore, showing location of plugs, amount of cement in each, and amount of casing left in hole, and the current status of the surface restoration.



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-88623
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> AXIA ENERGY LLC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 1430 Larimer Ste 400 , Denver, CO, 80202		<b>8. WELL NAME and NUMBER:</b> THREE RIVERS FED 35-34-720
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1597 FSL 2498 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047530060000
<b>9. FIELD and POOL or WILDCAT:</b> WILDCAT		<b>COUNTY:</b> UINTAH
<b>STATE:</b> UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>11/15/2013</b>	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> DEEPEN <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PRODUCTION START OR RESUME <input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> WATER SHUTOFF <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> SI TA STATUS EXTENSION <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CONVERT WELL TYPE <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> PLUG BACK <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION <input type="checkbox"/> TEMPORARY ABANDON <input type="checkbox"/> WATER DISPOSAL <input checked="" type="checkbox"/> <b>APD EXTENSION</b> OTHER: <span style="border: 1px solid black; display: inline-block; width: 100px; height: 15px;"></span>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:			
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:			
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 Axia Energy LLC respectfully requests a one year extension of the state permit for the referenced well. This is the first extension that has been requested.

Approved by the  
Utah Division of  
Oil, Gas and Mining

Date: May 23, 2013

By:

<b>NAME (PLEASE PRINT)</b> Don Hamilton	<b>PHONE NUMBER</b> 435 719-2018	<b>TITLE</b> Permitting Agent (Buys & Associates, Inc)
<b>SIGNATURE</b> N/A	<b>DATE</b> 5/19/2013	



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

**Request for Permit Extension Validation Well Number 43047530060000**

API: 43047530060000

Well Name: THREE RIVERS FED 35-34-720

Location: 1597 FSL 2498 FEL QTR NWSE SEC 35 TWNP 070S RNG 200E MER S

Company Permit Issued to: AXIA ENERGY LLC

Date Original Permit Issued: 8/2/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

Signature: Don Hamilton

Date: 5/19/2013

Title: Permitting Agent (Buys & Associates, Inc) Representing: AXIA ENERGY LLC

**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

**Request to Transfer Application or Permit to Drill**

(This form should accompany a Sundry Notice, Form 9, requesting APD transfer)

<b>Well name:</b>	See Attached List
<b>API number:</b>	
<b>Location:</b>	Qtr-Qtr:                      Section:                      Township:                      Range:
<b>Company that filed original application:</b>	Don Hamilton - Star Point Enterprises for Axia Energy, LLC
<b>Date original permit was issued:</b>	
<b>Company that permit was issued to:</b>	Axia Energy, LLC

Check one	Desired Action:
	<b>Transfer pending (unapproved) Application for Permit to Drill to new operator</b>
	The undersigned as owner with legal rights to drill on the property, hereby verifies that the information as submitted in the pending Application for Permit to Drill, remains valid and does not require revision. The new owner of the application accepts and agrees to the information and procedures as stated in the application.
✓	<b>Transfer approved Application for Permit to Drill to new operator</b>
	The undersigned as owner with legal rights to drill on the property as permitted, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision.

Following is a checklist of some items related to the application, which should be verified.	Yes	No
If located on private land, has the ownership changed?		✓
If so, has the surface agreement been updated?		✓
Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location?		✓
Have there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well?		✓
Have there been any changes to the access route including ownership or right-of-way, which could affect the proposed location?		✓
Has the approved source of water for drilling changed?		✓
Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation?		✓
Is bonding still in place, which covers this proposed well? Bond No. _____		✓

Any desired or necessary changes to either a pending or approved Application for Permit to Drill that is being transferred, should be filed on a Sundry Notice, Form 9, or amended Application for Permit to Drill, Form 3, as appropriate, with necessary supporting information as required.

RECEIVED  
DEC 16 2013  
DIV. OF OIL, GAS & MINING

Name (please print) Mary Sharon Balakas Title Attorney in Fact  
Signature Mary Sharon Balakas Date 12/11/13  
Representing (company name) Ultra Resources

The person signing this form must have legal authority to represent the company or individual(s) to be listed as the new operator on the Application for Permit to Drill.

Division of Oil, Gas and Mining  
**OPERATOR CHANGE WORKSHEET (for state use only)**

**ROUTING**  
 CDW

**X - Change of Operator (Well Sold)**

Operator Name Change/Merger

The operator of the well(s) listed below has changed, effective:

**10/1/2013**

<b>FROM:</b> (Old Operator): N3765-Axia Energy, LLC 1430 Larimer Street, Suite 400 Denver, CO 80202  Phone: 1 (720) 746-5200	<b>TO:</b> ( New Operator): N4045-Ultra Resources, Inc. 304 Inverness Way South, Suite 295 Englewood, CO 80112  Phone: 1 (303) 645-9810
---	--

CA No.				Unit:	N/A			
WELL NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS
See Attached List								

**OPERATOR CHANGES DOCUMENTATION**

Enter date after each listed item is completed

- (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 12/16/2013
- (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 12/16/2013
- The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 1/14/2014
- a. Is the new operator registered in the State of Utah: \_\_\_\_\_ Business Number: 8861713-0143
- 5a. (R649-9-2)Waste Management Plan has been received on: N/A
- 5b. Inspections of LA PA state/fee well sites complete on: N/A
- 5c. Reports current for Production/Disposition & Sundries on: 1/14/2014
- Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM Not Yet BIA
- Federal and Indian Units:**  
The BLM or BIA has approved the successor of unit operator for wells listed on: N/A
- Federal and Indian Communization Agreements ("CA"):**  
The BLM or BIA has approved the operator for all wells listed within a CA on: N/A
- Underground Injection Control ("UIC")** Division has approved UIC Form 5 Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: N/A

**DATA ENTRY:**

- Changes entered in the **Oil and Gas Database** on: 1/14/2014
- Changes have been entered on the **Monthly Operator Change Spread Sheet** on: 1/14/2014
- Bond information entered in RBDMS on: 1/14/2014
- Fee/State wells attached to bond in RBDMS on: 1/14/2014
- Injection Projects to new operator in RBDMS on: N/A
- Receipt of Acceptance of Drilling Procedures for APD/New on: 1/14/2014
- Surface Agreement Sundry from **NEW** operator on Fee Surface wells received on: Yes

**BOND VERIFICATION:**

- Federal well(s) covered by Bond Number: 22046400
- Indian well(s) covered by Bond Number: 22046400
- 3a. (R649-3-1) The **NEW** operator of any state/fee well(s) listed covered by Bond Number 22046398
- 3b. The **FORMER** operator has requested a release of liability from their bond on: Not Yet

**LEASE INTEREST OWNER NOTIFICATION:**

- (R649-2-10) The **NEW** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: 1/14/2014

**COMMENTS:**




## Axia Energy, LLC (N3765) to Ultra Resources, Inc. (N4045) Effective 10/1/2013

Well Name	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Well Type	Well Status
THREE RIVERS 2-41-820	2	080S	200E	4304752686		State	OW	APD
THREE RIVERS 2-25-820	2	080S	200E	4304752690		State	OW	APD
THREE RIVERS 36-21-720	36	070S	200E	4304752698		State	OW	APD
THREE RIVERS 36-13-720	36	070S	200E	4304752699		State	OW	APD
THREE RIVERS FEDERAL 3-54-820	3	080S	200E	4304752860		Federal	OW	APD
THREE RIVERS FEDERAL 3-33-820	3	080S	200E	4304752864		Federal	OW	APD
THREE RIVERS FED 35-34-720	35	070S	200E	4304753006		Federal	OW	APD
THREE RIVERS FED 35-42-720	35	070S	200E	4304753007		Federal	OW	APD
THREE RIVERS FED 35-44-720	35	070S	200E	4304753008		Federal	OW	APD
Three Rivers 2-32-820	2	080S	200E	4304753274		State	OW	APD
Three Rivers 18-21-821	18	080S	210E	4304753276		Fee	OW	APD
Three Rivers 18-31-821	18	080S	210E	4304753277		Fee	OW	APD
Three Rivers 27-34-720	34	070S	200E	4304753278		Fee	OW	APD
Three Rivers 34-31T-720	34	070S	200E	4304753281		Fee	OW	APD
Three Rivers Federal 35-14-720	35	070S	200E	4304753553		Federal	OW	APD
Three Rivers Federal 35-13-720	35	070S	200E	4304753554		Federal	OW	APD
Three Rivers 7-34-821	7	080S	210E	4304753558		Fee	OW	APD
Three Rivers 7-23-821	7	080S	210E	4304753559		Fee	OW	APD
Three Rivers 7-21-821	7	080S	210E	4304753560		Fee	OW	APD
Three Rivers 7-22-821	7	080S	210E	4304753561		Fee	OW	APD
Three Rivers 7-12-821	7	080S	210E	4304753562		Fee	OW	APD
Three Rivers 18-22-821	18	080S	210E	4304753620		Fee	OW	APD
Three Rivers 18-32-821	18	080S	210E	4304753621		Fee	OW	APD
Three Rivers D	16	080S	200E	4304753702		State	WD	APD
Three Rivers Federal 4-41-820	4	080S	200E	4304753911		Federal	OW	APD
Three Rivers Federal 4-42-820	4	080S	200E	4304753913		Federal	OW	APD
Three Rivers Federal 3-12-820	4	080S	200E	4304753914		Federal	OW	APD
Three Rivers Federal 34-42-720	35	070S	200E	4304753915		Federal	OW	APD
Three Rivers Federal 34-43-720	35	070S	200E	4304753916		Federal	OW	APD
Three Rivers Federal 35-12-720	35	070S	200E	4304753917		Federal	OW	APD
Three Rivers Federal 35-43-720	35	070S	200E	4304753918		Federal	OW	APD
Three Rivers Federal 35-442-720	35	070S	200E	4304753919		Federal	OW	APD
Three Rivers Federal 35-21-720	35	070S	200E	4304753943		Federal	OW	APD
Three Rivers Federal 35-11-720	35	070S	200E	4304753944		Federal	OW	APD
Three Rivers 2-24-820	2	080S	200E	4304753945		State	OW	APD
Three Rivers 2-223-820	2	080S	200E	4304753946		State	OW	APD
Three Rivers 2-21-820	2	080S	200E	4304753947		State	OW	APD
Three Rivers 2-22-820	2	080S	200E	4304753948		State	OW	APD
Three Rivers 32-42-720	32	070S	200E	4304753949		Fee	OW	APD
Three Rivers Federal 3-13-820	3	080S	200E	4304753951		Federal	OW	APD
Three Rivers Federal 3-14-820	3	080S	200E	4304753952		Federal	OW	APD
Three Rivers Federal 3-23-820	3	080S	200E	4304753953		Federal	OW	APD
Three Rivers Federal 3-24-820	3	080S	200E	4304753954		Federal	OW	APD
Three Rivers 4-13-820	5	080S	200E	4304753956		Federal	OW	APD
Three Rivers Federal 5-43-820	5	080S	200E	4304753957		Federal	OW	APD
Three Rivers Federal 5-42-820	5	080S	200E	4304753958		Federal	OW	APD
Three Rivers Federal 5-11-820	5	080S	200E	4304754204		Federal	OW	APD
Three Rivers Federal 5-21-820	5	080S	200E	4304754205		Federal	OW	APD
Three Rivers Federal 8-31-820	8	080S	200E	4304754211		Federal	OW	APD
Three Rivers Federal 8-41-820	8	080S	200E	4304754212		Federal	OW	APD
Three Rivers Federal 3-34-820	3	080S	200E	4304754213		Federal	OW	APD
Three Rivers Federal 3-44-820	3	080S	200E	4304754214		Federal	OW	APD
THREE RIVERS 32-34-720	32	070S	200E	4304752735	19249	Fee	OW	DRL
THREE RIVERS FEDERAL 8-52-820	8	080S	200E	4304752770	19156	Federal	OW	DRL
THREE RIVERS 4-14-820	5	080S	200E	4304752863	19183	Fee	OW	DRL
THREE RIVERS FED 10-42-820	10	080S	200E	4304752949	19310	Federal	OW	DRL
THREE RIVERS FED 3-11-820	34	070S	200E	4304752950	19184	Federal	OW	DRL
Three Rivers 16-21-820	16	080S	200E	4304753229	19024	State	OW	DRL
Three Rivers 16-22-820	16	080S	200E	4304753230	18961	State	OW	DRL

## Axia Energy, LLC (N3765) to Ultra Resources, Inc. (N4045) Effective 10/1/2013

Three Rivers Federal 34-35-720	34	070S	200E	4304753282	19287	Federal	OW	DRL
Three Rivers Federal 34-25-720	34	070S	200E	4304753283	19288	Federal	OW	DRL
Three Rivers Federal 10-32-820	10	080S	200E	4304753415	19275	Federal	OW	DRL
Three Rivers Federal 10-31-820	10	080S	200E	4304753437	19276	Federal	OW	DRL
Three Rivers 16-34-820	16	080S	200E	4304753472	19278	State	OW	DRL
Three Rivers 16-44-820	16	080S	200E	4304753473	19268	State	OW	DRL
Three Rivers 16-11-820	16	080S	200E	4304753474	19262	State	OW	DRL
Three Rivers 16-12-820	16	080S	200E	4304753475	19263	State	OW	DRL
Three Rivers 16-32-820	16	080S	200E	4304753494	19185	State	OW	DRL
Three Rivers 16-31-820	16	080S	200E	4304753495	19269	State	OW	DRL
Three Rivers 16-33-820	16	080S	200E	4304753496	19161	State	OW	DRL
THREE RIVERS FED 10-30-820	10	080S	200E	4304753555	19169	Federal	OW	DRL
Three Rivers Federal 9-41-820	10	080S	200E	4304753556	19170	Federal	OW	DRL
Three Rivers Federal 33-13-720	33	070S	200E	4304753723	19222	Federal	OW	DRL
Three Rivers Federal 33-12-720	33	070S	200E	4304753724	19250	Federal	OW	DRL
Three Rivers 32-3333-720	32	070S	200E	4304753950	19251	Fee	OW	DRL
THREE RIVERS 36-11-720	36	070S	200E	4304751915	18355	State	OW	P
THREE RIVERS 2-11-820	2	080S	200E	4304751936	18354	State	OW	P
THREE RIVERS 34-31-720	34	070S	200E	4304752012	18326	Fee	OW	P
THREE RIVERS 16-42-820	16	080S	200E	4304752056	18682	State	OW	P
THREE RIVERS 16-43-820	16	080S	200E	4304752057	18683	State	OW	P
THREE RIVERS 16-41-820	16	080S	200E	4304752110	18356	State	OW	P
THREE RIVERS 2-51-820	2	080S	200E	4304752685	18941	State	OW	P
THREE RIVERS 2-13-820	2	080S	200E	4304752687	19014	State	OW	P
THREE RIVERS 2-23-820	2	080S	200E	4304752688	19015	State	OW	P
THREE RIVERS 2-15-820	2	080S	200E	4304752689	18770	State	OW	P
THREE RIVERS 36-31-720	36	070S	200E	4304752697	19086	State	OW	P
THREE RIVERS 32-25-720	32	070S	200E	4304752718	19033	Fee	OW	P
THREE RIVERS 36-23-720	36	070S	200E	4304752733	18769	State	OW	P
THREE RIVERS 32-33-720	32	070S	200E	4304752734	19016	Fee	OW	P
THREE RIVERS 32-15-720	32	070S	200E	4304752736	18767	Fee	OW	P
THREE RIVERS 32-35-720	32	070S	200E	4304752737	18766	Fee	OW	P
THREE RIVERS FEDERAL 8-53-820	8	080S	200E	4304752771	18992	Federal	OW	P
THREE RIVERS FEDERAL 3-53-820	3	080S	200E	4304752820	19104	Federal	OW	P
THREE RIVERS FEDERAL 3-32-820	3	080S	200E	4304752861	18942	Federal	OW	P
THREE RIVERS FEDERAL 5-56-820	5	080S	200E	4304752862	18993	Federal	OW	P
THREE RIVERS FED 4-31-820	4	080S	200E	4304752874	19023	Federal	OW	P
THREE RIVERS 4-21-820	4	080S	200E	4304752875	19048	Federal	OW	P
THREE RIVERS FED 34-23-720	34	070S	200E	4304752945	19049	Federal	OW	P
THREE RIVERS FED 34-33-720	34	070S	200E	4304752947	19050	Federal	OW	P
THREE RIVERS FED 10-41-820	10	080S	200E	4304752948	19137	Federal	OW	P
THREE RIVERS FED 34-15-720	34	070S	200E	4304752965	18960	Federal	OW	P
THREE RIVERS FED 35-32-720	35	070S	200E	4304753005	19138	Federal	OW	P
Three Rivers 16-23-820	16	080S	200E	4304753231	19037	State	OW	P
Three Rivers 16-24-820	16	080S	200E	4304753232	19038	State	OW	P
Three Rivers 2-33-820	2	080S	200E	4304753273	18943	State	OW	P
Three Rivers 4-33-820	4	080S	200E	4304753528	19167	Fee	OW	P
Three Rivers Federal 33-14-720	33	070S	200E	4304753551	19107	Federal	OW	P
Three Rivers Federal 4-32-820	4	080S	200E	4304753552	19168	Federal	OW	P
Three Rivers Federal 33-24-720	33	070S	200E	4304753557	19108	Federal	OW	P
Three Rivers 32-334-720	32	070S	200E	4304753710	19067	Fee	OW	P
Three Rivers 5-31-820	32	070S	200E	4304753711	19068	Fee	OW	P
Three Rivers Federal 33-11-720	32	070S	200E	4304753733	19109	Federal	OW	P
Three Rivers 32-32-720	32	070S	200E	4304753734	19087	Fee	OW	P
Three Rivers 32-333-720	32	070S	200E	4304753735	19088	Fee	OW	P



# Ultra Resources, Inc.

December 13, 2013

RECEIVED  
DEC 16 2013  
DIV. OF OIL, GAS & MINING

Division of Oil, Gas, and Mining  
1594 West North Temple  
Salt Lake City, UT 84116  
Attn: Rachel Medina

Re: Transfer of Operator  
Three Rivers Project Area  
Uintah County, Utah

Dear Ms. Medina:

Pursuant to Purchase and Sale Agreement dated effective October 1, 2013 Ultra Resources, Inc. ("Ultra") assumed the operations of Axia Energy, LLC ("Axia") in the Three Rivers Area, Uintah County, Utah.

Accordingly, Ultra is submitting the following documents for your review and approval:


- 1) Request to Transfer Application or Permit to Drill for New, APD Approved & Drilled Wells
- 2) Request to Transfer Application or Permit to Drill – APD Pending
- 3) Two Completed Sundry Notice and Reports on Wells Form 9 regarding Change of Operator executed by Ultra Resources, Inc. and Axia Energy, LLC
- 4) Statewide Surety Bond in the amount of \$120,000

As to all wells located on Fee Surface there are surface agreements in place. Ultra presently does not anticipate making any change in the drilling plans submitted by Axia.

Ultra has also submitted a Statewide Bond to the Bureau of Land Management. As soon as we receive the acknowledgement and approval by the BLM we will forward same to you for your files. A copy of our transfer letter and bond is attached for your reference.

Should you need any further information at this time, please call me direct at (303) 645-9865 or email [msbalakas@ultrapetroleum.com](mailto:msbalakas@ultrapetroleum.com).

Sincerely,

  
Mary Sharon Balakas, CPL  
Director of Land

cc: Cindy Turner, Axia Energy, LLC

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached Well List
2. NAME OF OPERATOR: Ultra Resources, Inc. N4045		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 304 Inverness Way South CITY Englewood STATE CO ZIP 80112		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: See Attached		8. WELL NAME and NUMBER: See Attached Well List
PHONE NUMBER: (303) 645-9810		9. API NUMBER:
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		10. FIELD AND POOL, OR WILDCAT:
COUNTY: Uintah		STATE: UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 10/1/2013	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EFFECTIVE DATE: October 1, 2013  
FROM:  
Axia Energy, LLC  
1430 Larimer Street  
Suite 400  
Denver, CO 80202  
Bond Number: Blanket Statewide UT State/Fee Bond LPM9046682  
TO:  
Ultra Resources, Inc.  
304 Inverness Way South  
Englewood, CO 80112  
Bond Number: DOGm-022046398  
BLM 022046400

Ultra Resources, Inc. will be responsible under the terms and conditions of the leases/wells for the operations conducted on the leased lands.

RECEIVED  
DEC 16 2013

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Mary Sharon Balakas TITLE Attorney in Fact  
SIGNATURE Mary Sharon Balakas DATE 12/11/13

APPROVED

(This space for State use only)

JAN 16 2013

DIV. OIL GAS & MINING

BY: Rachel Medina



ATTACHMENT TO FORM 9 CHANGE OF OPERATOR  
AXIA ENERGY TO ULTRA RESOURCES EFFECTIVE 10-01-2013

State Well Name List downloaded 12-10-13	Axia Well Name (for database sort and consistency)	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	State Well Status	Actual Status @ 12/12/13	Submitted	Date Apprvd DOGM
THREE RIVERS 2-11-820	Three Rivers 02-11-820	2	080S	200E	4304751936	18354	State	State	OW	P	P		
THREE RIVERS 2-13-820	Three Rivers 02-13-820	2	080S	200E	4304752687	19014	State	State	OW	DRL	P		08/27/12
THREE RIVERS 2-15-820	Three Rivers 02-15-820	2	080S	200E	4304752689	18770	State	State	OW	P	P		
Three Rivers 2-21-820	Three Rivers 02-21-820	2	080S	200E	4304753947		State	State	OW	APD	APRVD		10/15/13
Three Rivers 2-223-820	Three Rivers 02-223-820	2	080S	200E	4304753946		State	State	OW	APD	APRVD		10/15/13
Three Rivers 2-22-820	Three Rivers 02-22-820	2	080S	200E	4304753948		State	State	OW	APD	APRVD		10/15/13
THREE RIVERS 2-23-820	Three Rivers 02-23-820	2	080S	200E	4304752688	19015	State	State	OW	DRL	P		08/27/12
Three Rivers 2-24-820	Three Rivers 02-24-820	2	080S	200E	4304753945		State	State	OW	APD	APRVD		10/15/13
THREE RIVERS 2-25-820	Three Rivers 02-25-820	2	080S	200E	4304752690		State	State	OW	APD	APRVD		08/27/12
Three Rivers 2-32-820	Three Rivers 02-32-820	2	080S	200E	4304753274		State	State	OW	APD	APRVD		12/11/12
Three Rivers 2-33-820	Three Rivers 02-33-820	2	080S	200E	4304753273	18943	State	State	OW	P	P		
THREE RIVERS 2-41-820	Three Rivers 02-41-820	2	080S	200E	4304752686		State	State	OW	APD	APRVD		08/27/12
THREE RIVERS 2-51-820	Three Rivers 02-51-820	2	080S	200E	4304752685	18941	State	State	OW	P	P		
Three Rivers 4-13-820	Three Rivers 04-13-820	5	080S	200E	4304753956		Fee	Federal	OW	APD	PERPEND	08/19/13	
THREE RIVERS 4-14-820	Three Rivers 04-14-820	5	080S	200E	4304752863	19183	Fee	Federal	OW	DRL	P		
Three Rivers 4-33-820	Three Rivers 04-33-820	4	080S	200E	4304753528	19167	Fee	Fee	OW	DRL	P		
Three Rivers 5-31-820	Three Rivers 05-31-820	32	070S	200E	4304753711	19068	Fee	Fee	OW	DRL	P		
Three Rivers 7-12-821	Three Rivers 07-12-821	7	080S	210E	4304753562		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 7-21-821	Three Rivers 07-21-821	7	080S	210E	4304753560		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 7-22-821	Three Rivers 07-22-821	7	080S	210E	4304753561		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 7-23-821	Three Rivers 07-23-821	7	080S	210E	4304753559		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 7-34-821	Three Rivers 07-34-821	7	080S	210E	4304753558		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 16-11-820	Three Rivers 16-11-820	16	080S	200E	4304753474	19262	State	State	OW	DRL	SCS		03/12/13
Three Rivers 16-12-820	Three Rivers 16-12-820	16	080S	200E	4304753475	19263	State	State	OW	DRL	SCS		03/12/13
Three Rivers 16-21-820	Three Rivers 16-21-820	16	080S	200E	4304753229	19024	State	State	OW	DRL	P		12/11/12
Three Rivers 16-22-820	Three Rivers 16-22-820	16	080S	200E	4304753230	18961	State	State	OW	DRL	P		12/11/12
Three Rivers 16-23-820	Three Rivers 16-23-820	16	080S	200E	4304753231	19037	State	State	OW	DRL	P		12/11/12
Three Rivers 16-24-820	Three Rivers 16-24-820	16	080S	200E	4304753232	19038	State	State	OW	P	P		
Three Rivers 16-31-820	Three Rivers 16-31-820	16	080S	200E	4304753495		State	State	OW	APD	CCS		03/12/13
Three Rivers 16-32-820	Three Rivers 16-32-820	16	080S	200E	4304753494	19185	State	State	OW	DRL	WOC		03/12/13
Three Rivers 16-33-820	Three Rivers 16-33-820	16	080S	200E	4304753496	19161	State	State	OW	DRL	WOC		03/12/13
Three Rivers 16-34-820	Three Rivers 16-34-820	16	080S	200E	4304753472		State	State	OW	APD	CCS		03/12/13
THREE RIVERS 16-41-820	Three Rivers 16-41-820	16	080S	200E	4304752110	18356	State	State	OW	P	P		
THREE RIVERS 16-42-820	Three Rivers 16-42-820	16	080S	200E	4304752056	18682	State	State	OW	P	P		
THREE RIVERS 16-43-820	Three Rivers 16-43-820	16	080S	200E	4304752057	18683	State	State	OW	P	P		
Three Rivers 16-44-820	Three Rivers 16-44-820	16	080S	200E	4304753473		State	State	OW	APD	CCS		03/12/13
Three Rivers 18-21-821	Three Rivers 18-21-821	18	080S	210E	4304753276		Fee	Fee	OW	APD	PERPEND	12/17/12	
Three Rivers 18-22-821	Three Rivers 18-22-821	18	080S	210E	4304753620		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 18-31-821	Three Rivers 18-31-821	18	080S	210E	4304753277		Fee	Fee	OW	APD	PERPEND	12/19/12	
Three Rivers 18-32-821	Three Rivers 18-32-821	18	080S	210E	4304753621		Fee	Fee	OW	APD	PERPEND	04/15/13	
Three Rivers 27-34-720	Three Rivers 27-34-720	34	070S	200E	4304753278		Fee	Fee	OW	APD	PERPEND	12/19/12	
THREE RIVERS 32-15-720	Three Rivers 32-15-720	32	070S	200E	4304752736	18767	Fee	Fee	OW	P	P		
THREE RIVERS 32-25-720	Three Rivers 32-25-720	32	070S	200E	4304752718	19033	Fee	Fee	OW	P	P		
Three Rivers 32-32-720	Three Rivers 32-32-720	32	070S	200E	4304753734	19087	Fee	Fee	OW	DRL	P		06/12/13
Three Rivers 32-3333-720	Three Rivers 32-3333-720	32	070S	200E	4304753950	19251	Fee	Fee	OW	DRL	SCS		10/15/13
Three Rivers 32-333-720	Three Rivers 32-333-720	32	070S	200E	4304753735	19088	Fee	Fee	OW	DRL	P		06/12/13
Three Rivers 32-334-720	Three Rivers 32-334-720	32	070S	200E	4304753710	19067	Fee	Fee	OW	DRL	P		05/22/13
THREE RIVERS 32-33-720	Three Rivers 32-33-720	32	070S	200E	4304752734	19016	Fee	Fee	OW	DRL	P		08/29/12
THREE RIVERS 32-34-720	Three Rivers 32-34-720	32	070S	200E	4304752735	19249	Fee	Fee	OW	DRL	DRLG		08/29/12
THREE RIVERS 32-35-720	Three Rivers 32-35-720	32	070S	200E	4304752737	18766	Fee	Fee	OW	P	P		
Three Rivers 32-42-720	Three Rivers 32-42-720	32	070S	200E	4304753949		Fee	Fee	OW	APD	APRVD		10/15/13
THREE RIVERS 34-31-720	Three Rivers 34-31-720	34	070S	200E	4304752012	18326	Fee	Fee	OW	P	P		
Three Rivers 34-31T-720	Three Rivers 34-31T-720	34	070S	200E	4304753281		Fee	Fee	OW	APD	APRVD		12/11/12
THREE RIVERS 36-11-720	Three Rivers 36-11-720	36	070S	200E	4304751915	18355	State	State	OW	P	P		
THREE RIVERS 36-13-720	Three Rivers 36-13-720	36	070S	200E	4304752699		State	State	OW	APD	APRVD		08/29/12
THREE RIVERS 36-21-720	Three Rivers 36-21-720	36	070S	200E	4304752698		State	State	OW	APD	APRVD		08/29/12
THREE RIVERS 36-23-720	Three Rivers 36-23-720	36	070S	200E	4304752733	18769	State	State	OW	P	P		
THREE RIVERS 36-31-720	Three Rivers 36-31-720	36	070S	200E	4304752697	19086	State	State	OW	DRL	P		08/29/12
Three Rivers D	Three Rivers D	16	080S	200E	4304753702		State	State	WD	APD	APRVD		07/15/13
THREE RIVERS FED 3-11-820	Three Rivers Fed 03-11-820	34	070S	200E	4304752950	19184	Federal	Fee	OW	DRL	WOC		02/22/13
Three Rivers Federal 3-12-820	Three Rivers Fed 03-12-820	4	080S	200E	4304753914		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 3-13-820	Three Rivers Fed 03-13-820	3	080S	200E	4304753951		Federal	Federal	OW	APD	PERPEND	08/12/13	
Three Rivers Federal 3-14-820	Three Rivers Fed 03-14-820	3	080S	200E	4304753952		Federal	Federal	OW	APD	PERPEND	08/12/13	
Three Rivers Federal 3-23-820	Three Rivers Fed 03-23-820	3	080S	200E	4304753953		Federal	Federal	OW	APD	PERPEND	08/12/13	
Three Rivers Federal 3-24-820	Three Rivers Fed 03-24-820	3	080S	200E	4304753954		Federal	Federal	OW	APD	PERPEND	08/12/13	
THREE RIVERS FEDERAL 3-32-820	Three Rivers Fed 03-32-820	3	080S	200E	4304752861	18942	Federal	Federal	OW	P	P		
THREE RIVERS FEDERAL 3-33-820	Three Rivers Fed 03-33-820	3	080S	200E	4304752864		Federal	Federal	OW	APD	APRVD		12/24/12
THREE RIVERS FEDERAL 3-53-820	Three Rivers Fed 03-53-820	3	080S	200E	4304752820	19104	Federal	Federal	OW	DRL	P		12/24/12
THREE RIVERS FEDERAL 3-54-820	Three Rivers Fed 03-54-820	3	080S	200E	4304752860		Federal	Federal	OW	APD	APRVD		12/24/12

ATTACHMENT TO FORM 9 CHANGE OF OPERATOR  
AXIA ENERGY TO ULTRA RESOURCES EFFECTIVE 10-01-2013

State Well Name List downloaded 12-10-13	Axia Well Name (for database sort and consistency)	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	State Well Status	Actual Status @ 12/12/13	Submitted	Date Apprvd DOGM
THREE RIVERS 4-21-820	Three Rivers Fed 04-21-820	4	080S	200E	4304752875	19048	Federal	Fee	OW	DRL	P		02/22/13
THREE RIVERS FED 4-31-820	Three Rivers Fed 04-31-820	4	080S	200E	4304752874	19023	Federal	Fee	OW	DRL	P		02/22/13
Three Rivers Federal 4-32-820	Three Rivers Fed 04-32-820	4	080S	200E	4304753552	19168	Federal	Fee	OW	DRL	P		08/26/13
Three Rivers Federal 4-41-820	Three Rivers Fed 04-41-820	4	080S	200E	4304753911		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 4-42-820	Three Rivers Fed 04-42-820	4	080S	200E	4304753913		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 5-11-820	Three Rivers Fed 05-11-820	5	080S	200E	4304754204		Federal	Federal	OW	NEW	PERPEND	12/03/13	
Three Rivers Federal 5-21-820	Three Rivers Fed 05-21-820	5	080S	200E	4304754205		Federal	Federal	OW	NEW	PERPEND	12/03/13	
Three Rivers Federal 5-42-820	Three Rivers Fed 05-42-820	5	080S	200E	4304753958		Federal	Federal	OW	APD	PERPEND	08/19/13	
Three Rivers Federal 5-43-820	Three Rivers Fed 05-43-820	5	080S	200E	4304753957		Federal	Federal	OW	APD	PERPEND	08/19/13	
THREE RIVERS FEDERAL 5-56-820	Three Rivers Fed 05-56-820	5	080S	200E	4304752862	18993	Federal	Federal	OW	P	P		
THREE RIVERS FEDERAL 8-52-820	Three Rivers Fed 08-52-820	8	080S	200E	4304752770	19156	Federal	Federal	OW	DRL	P		02/22/13
THREE RIVERS FEDERAL 8-53-820	Three Rivers Fed 08-53-820	8	080S	200E	4304752771	18992	Federal	Federal	OW	P	P		
Three Rivers Federal 9-41-820	Three Rivers Fed 09-41-820	10	080S	200E	4304753556	19170	Federal	Federal	OW	DRL	P		08/20/13
THREE RIVERS FED 10-30-820	Three Rivers Fed 10-30-820	10	080S	200E	4304753555	19169	Federal	Federal	OW	DRL	P		08/20/13
Three Rivers Federal 10-31-820	Three Rivers Fed 10-31-820	10	080S	200E	4304753437		Federal	Federal	OW	APD	CCS		08/21/13
Three Rivers Federal 10-32-820	Three Rivers Fed 10-32-820	10	080S	200E	4304753415		Federal	Federal	OW	APD	CCS		08/21/13
THREE RIVERS FED 10-41-820	Three Rivers Fed 10-41-820	10	080S	200E	4304752948	19137	Federal	Federal	OW	DRL	P		02/22/13
THREE RIVERS FED 10-42-820	Three Rivers Fed 10-42-820	10	080S	200E	4304752949		Federal	Federal	OW	APD	APRVD		02/22/13
Three Rivers Federal 33-11-720	Three Rivers Fed 33-11-720	32	070S	200E	4304753733	19109	Federal	Fee	OW	DRL	P		07/17/13
Three Rivers Federal 33-12-720	Three Rivers Fed 33-12-720	33	070S	200E	4304753724	19250	Federal	Fee	OW	DRL	WOC		09/16/13
Three Rivers Federal 33-13-720	Three Rivers Fed 33-13-720	33	070S	200E	4304753723	19222	Federal	Fee	OW	DRL	WOC		09/16/13
Three Rivers Federal 33-14-720	Three Rivers Fed 33-14-720	33	070S	200E	4304753551	19107	Federal	Fee	OW	DRL	P		09/16/13
Three Rivers Federal 33-24-720	Three Rivers Fed 33-24-720	33	070S	200E	4304753557	19108	Federal	Fee	OW	DRL	P		07/09/13
THREE RIVERS FED 34-15-720	Three Rivers Fed 34-15-720	34	070S	200E	4304752965	18960	Federal	Fee	OW	P	P		
THREE RIVERS FED 34-23-720	Three Rivers Fed 34-23-720	34	070S	200E	4304752945	19049	Federal	Fee	OW	DRL	P		02/12/13
Three Rivers Federal 34-25-720	Three Rivers Fed 34-25-720	34	070S	200E	4304753283		Federal	Fee	OW	APD	APRVD		06/10/13
THREE RIVERS FED 34-33-720	Three Rivers Fed 34-33-720	34	070S	200E	4304752947	19050	Federal	Fee	OW	DRL	P		02/22/13
Three Rivers Federal 34-35-720	Three Rivers Fed 34-35-720	34	070S	200E	4304753282		Federal	Fee	OW	APD	APRVD		06/10/13
Three Rivers Federal 34-42-720	Three Rivers Fed 34-42-720	35	070S	200E	4304753915		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 34-43-720	Three Rivers Fed 34-43-720	35	070S	200E	4304753916		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 35-11-720	Three Rivers Fed 35-11-720	35	070S	200E	4304753944		Federal	Federal	OW	APD	PERPEND	07/25/13	
Three Rivers Federal 35-12-720	Three Rivers Fed 35-12-720	35	070S	200E	4304753917		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 35-13-720	Three Rivers Fed 35-13-720	35	070S	200E	4304753554		Federal	Federal	OW	APD	APRVD		08/20/13
Three Rivers Federal 35-14-720	Three Rivers Fed 35-14-720	35	070S	200E	4304753553		Federal	Federal	OW	APD	APRVD		08/22/13
Three Rivers Federal 35-21-720	Three Rivers Fed 35-21-720	35	070S	200E	4304753943		Federal	Federal	OW	APD	PERPEND	07/25/13	
THREE RIVERS FED 35-32-720	Three Rivers Fed 35-32-720	35	070S	200E	4304753005	19138	Federal	Federal	OW	DRL	APRVD		02/22/13
THREE RIVERS FED 35-34-720	Three Rivers Fed 35-34-720	35	070S	200E	4304753006		Federal	Federal	OW	APD	APRVD		02/22/13
THREE RIVERS FED 35-42-720	Three Rivers Fed 35-42-720	35	070S	200E	4304753007		Federal	Federal	OW	APD	APRVD		02/22/13
Three Rivers Federal 35-43-720	Three Rivers Fed 35-43-720	35	070S	200E	4304753918		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 35-44-720	Three Rivers Fed 35-44-720	35	070S	200E	4304753919		Federal	Federal	OW	APD	APRVD		08/01/13
THREE RIVERS FED 35-44-720	Three Rivers Fed 35-44-720	35	070S	200E	4304753008		Federal	Federal	OW	APD	APRVD		02/22/13
Three Rivers Fed 03-34-820	Three Rivers Fed 03-34-820	3	080S	200E			Federal			NA	SUB	12/10/13	
Three Rivers Fed 03-44-820	Three Rivers Fed 03-44-820	3	080S	200E			Federal			NA	SUB	12/10/13	
Three Rivers Fed 08-31-820	Three Rivers Fed 08-31-820	8	080S	200E			Federal			NA	SUB	12/07/13	
Three Rivers Fed 08-41-820	Three Rivers Fed 08-41-820	9	080S	200E			Federal			NA	SUB	12/07/13	

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: See Attached Well List
2. NAME OF OPERATOR: Axia Energy, LLC N3765		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1430 Larimer Street, Ste 400 CITY Denver STATE CO ZIP 80202		7. UNIT or CA AGREEMENT NAME:
4. LOCATION OF WELL FOOTAGES AT SURFACE: See Attached		8. WELL NAME and NUMBER: See Attached Well List
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:		9. API NUMBER:
COUNTY: Uintah		10. FIELD AND POOL, OR WILDCAT:
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: 10/1/2013	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input checked="" type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion:	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: _____
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

EFFECTIVE DATE: October 1, 2013  
FROM:  
Axia Energy, LLC  
1430 Larimer Street  
Suite 400  
Denver, CO 80202  
Bond Number: Blanket Statewide UT State/Fee Bond LPM9046682  
TO:  
Ultra Resources, Inc.  
304 Inverness Way South  
Englewood, CO 80112  
Bond Number: DOGm 022046298  
BLM 022046400

Ultra Resources, Inc. will be responsible under the terms and conditions of the leases/wells for the operations conducted on the leased lands.

RECEIVED

DEC 16 2013

DIV. OF OIL, GAS & MINING

NAME (PLEASE PRINT) Daniel G. Blanchard	TITLE President
SIGNATURE <i>D. G. Blanchard</i>	DATE 12/11/13

(This space for State use only)

APPROVED

JAN 16 2013

DIV. OIL GAS & MINING  
BY: *D. G. Blanchard*

ATTACHMENT TO FORM 9 CHANGE OF OPERATOR  
AXIA ENERGY TO ULTRA RESOURCES EFFECTIVE 10-01-2013

State Well Name List downloaded 12-10-13	Axia Well Name (for database sort and consistency)	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	State Well Status	Actual Status @ 12/12/13	Submitted	Date Apprvd DOGM
THREE RIVERS 2-11-820	Three Rivers 02-11-820	2	080S	200E	4304751936	18354	State	State	OW	P	P	1	
THREE RIVERS 2-13-820	Three Rivers 02-13-820	2	080S	200E	4304752687	19014	State	State	OW	DRL	P	2	08/27/12
THREE RIVERS 2-15-820	Three Rivers 02-15-820	2	080S	200E	4304752689	18770	State	State	OW	P	P	3	
Three Rivers 2-21-820	Three Rivers 02-21-820	2	080S	200E	4304753947		State	State	OW	APD	APRVD	4	10/15/13
Three Rivers 2-223-820	Three Rivers 02-223-820	2	080S	200E	4304753946		State	State	OW	APD	APRVD	5	10/15/13
Three Rivers 2-22-820	Three Rivers 02-22-820	2	080S	200E	4304753948		State	State	OW	APD	APRVD	6	10/15/13
THREE RIVERS 2-23-820	Three Rivers 02-23-820	2	080S	200E	4304752688	19015	State	State	OW	DRL	P	7	08/27/12
Three Rivers 2-24-820	Three Rivers 02-24-820	2	080S	200E	4304753945		State	State	OW	APD	APRVD	8	10/15/13
THREE RIVERS 2-25-820	Three Rivers 02-25-820	2	080S	200E	4304752690		State	State	OW	APD	APRVD	9	08/27/12
Three Rivers 2-32-820	Three Rivers 02-32-820	2	080S	200E	4304753274		State	State	OW	APD	APRVD	10	12/11/12
Three Rivers 2-33-820	Three Rivers 02-33-820	2	080S	200E	4304753273	18943	State	State	OW	P	P	1	
THREE RIVERS 2-41-820	Three Rivers 02-41-820	2	080S	200E	4304752686		State	State	OW	APD	APRVD	2	08/27/12
THREE RIVERS 2-51-820	Three Rivers 02-51-820	2	080S	200E	4304752685	18941	State	State	OW	P	P	3	
Three Rivers 4-13-820	Three Rivers 04-13-820	5	080S	200E	4304753956		Fee	Federal	OW	APD	PERPEND	08/19/13	
THREE RIVERS 4-14-820	Three Rivers 04-14-820	5	080S	200E	4304752863	19183	Fee	Federal	OW	DRL	P	5	
Three Rivers 4-33-820	Three Rivers 04-33-820	4	080S	200E	4304753528	19167	Fee	Fee	OW	DRL	P	6	
Three Rivers 5-31-820	Three Rivers 05-31-820	32	070S	200E	4304753711	19068	Fee	Fee	OW	DRL	P	7	
Three Rivers 7-12-821	Three Rivers 07-12-821	7	080S	210E	4304753562		Fee	Fee	OW	APD	PERPEND	04/15/13	8
Three Rivers 7-21-821	Three Rivers 07-21-821	7	080S	210E	4304753560		Fee	Fee	OW	APD	PERPEND	04/15/13	9
Three Rivers 7-22-821	Three Rivers 07-22-821	7	080S	210E	4304753561		Fee	Fee	OW	APD	PERPEND	04/15/13	20
Three Rivers 7-23-821	Three Rivers 07-23-821	7	080S	210E	4304753559		Fee	Fee	OW	APD	PERPEND	04/15/13	1
Three Rivers 7-34-821	Three Rivers 07-34-821	7	080S	210E	4304753558		Fee	Fee	OW	APD	PERPEND	04/15/13	2
Three Rivers 16-11-820	Three Rivers 16-11-820	16	080S	200E	4304753474	19262	State	State	OW	DRL	SCS	3	03/12/13
Three Rivers 16-12-820	Three Rivers 16-12-820	16	080S	200E	4304753475	19263	State	State	OW	DRL	SCS	4	03/12/13
Three Rivers 16-21-820	Three Rivers 16-21-820	16	080S	200E	4304753229	19024	State	State	OW	DRL	P	5	12/11/12
Three Rivers 16-22-820	Three Rivers 16-22-820	16	080S	200E	4304753230	18961	State	State	OW	DRL	P	6	12/11/12
Three Rivers 16-23-820	Three Rivers 16-23-820	16	080S	200E	4304753231	19037	State	State	OW	DRL	P	7	12/11/12
Three Rivers 16-24-820	Three Rivers 16-24-820	16	080S	200E	4304753232	19038	State	State	OW	P	P	8	
Three Rivers 16-31-820	Three Rivers 16-31-820	16	080S	200E	4304753495		State	State	OW	APD	CCS	9	03/12/13
Three Rivers 16-32-820	Three Rivers 16-32-820	16	080S	200E	4304753494	19185	State	State	OW	DRL	WOC	30	03/12/13
Three Rivers 16-33-820	Three Rivers 16-33-820	16	080S	200E	4304753496	19161	State	State	OW	DRL	WOC	1	03/12/13
Three Rivers 16-34-820	Three Rivers 16-34-820	16	080S	200E	4304753472		State	State	OW	APD	CCS	2	03/12/13
THREE RIVERS 16-41-820	Three Rivers 16-41-820	16	080S	200E	4304752110	18356	State	State	OW	P	P	3	
THREE RIVERS 16-42-820	Three Rivers 16-42-820	16	080S	200E	4304752056	18682	State	State	OW	P	P	4	
THREE RIVERS 16-43-820	Three Rivers 16-43-820	16	080S	200E	4304752057	18683	State	State	OW	P	P	5	
Three Rivers 16-44-820	Three Rivers 16-44-820	16	080S	200E	4304753473		State	State	OW	APD	CCS	6	03/12/13
Three Rivers 18-21-821	Three Rivers 18-21-821	18	080S	210E	4304753276		Fee	Fee	OW	APD	PERPEND	12/17/12	7
Three Rivers 18-22-821	Three Rivers 18-22-821	18	080S	210E	4304753260		Fee	Fee	OW	APD	PERPEND	04/15/13	8
Three Rivers 18-31-821	Three Rivers 18-31-821	18	080S	210E	4304753277		Fee	Fee	OW	APD	PERPEND	12/19/12	9
Three Rivers 18-32-821	Three Rivers 18-32-821	18	080S	210E	4304753261		Fee	Fee	OW	APD	PERPEND	04/15/13	40
Three Rivers 27-34-720	Three Rivers 27-34-720	34	070S	200E	4304753278		Fee	Fee	OW	APD	PERPEND	12/19/12	1
THREE RIVERS 32-15-720	Three Rivers 32-15-720	32	070S	200E	4304752736	18767	Fee	Fee	OW	P	P	2	
THREE RIVERS 32-25-720	Three Rivers 32-25-720	32	070S	200E	4304752718	19033	Fee	Fee	OW	P	P	3	
Three Rivers 32-32-720	Three Rivers 32-32-720	32	070S	200E	4304753734	19087	Fee	Fee	OW	DRL	P	4	06/12/13
Three Rivers 32-333-720	Three Rivers 32-333-720	32	070S	200E	4304753950	19251	Fee	Fee	OW	DRL	SCS	5	10/15/13
Three Rivers 32-333-720	Three Rivers 32-333-720	32	070S	200E	4304753735	19088	Fee	Fee	OW	DRL	P	6	06/12/13
Three Rivers 32-334-720	Three Rivers 32-334-720	32	070S	200E	4304753710	19067	Fee	Fee	OW	DRL	P	7	05/22/13
THREE RIVERS 32-33-720	Three Rivers 32-33-720	32	070S	200E	4304752734	19016	Fee	Fee	OW	DRL	P	8	08/29/12
THREE RIVERS 32-34-720	Three Rivers 32-34-720	32	070S	200E	4304752735	19249	Fee	Fee	OW	DRL	DRLG	9	08/29/12
THREE RIVERS 32-35-720	Three Rivers 32-35-720	32	070S	200E	4304752737	18766	Fee	Fee	OW	P	P	50	
Three Rivers 32-42-720	Three Rivers 32-42-720	32	070S	200E	4304753949		Fee	Fee	OW	APD	APRVD	1	10/15/13
THREE RIVERS 34-31-720	Three Rivers 34-31-720	34	070S	200E	4304752012	18326	Fee	Fee	OW	P	P	2	
Three Rivers 34-31T-720	Three Rivers 34-31T-720	34	070S	200E	4304753281		Fee	Fee	OW	APD	APRVD	3	12/11/12
THREE RIVERS 36-11-720	Three Rivers 36-11-720	36	070S	200E	4304751915	18355	State	State	OW	P	P	4	
THREE RIVERS 36-13-720	Three Rivers 36-13-720	36	070S	200E	4304752699		State	State	OW	APD	APRVD	5	08/29/12
THREE RIVERS 36-21-720	Three Rivers 36-21-720	36	070S	200E	4304752698		State	State	OW	APD	APRVD	6	08/29/12
THREE RIVERS 36-23-720	Three Rivers 36-23-720	36	070S	200E	4304752733	18769	State	State	OW	P	P	7	
THREE RIVERS 36-31-720	Three Rivers 36-31-720	36	070S	200E	4304752697	19089	State	State	OW	DRL	P	8	08/29/12
Three Rivers D	Three Rivers D	16	080S	200E	4304753702		State	State	WD	APD	APRVD	9	07/15/13
THREE RIVERS FED 3-11-820	Three Rivers Fed 03-11-820	34	070S	200E	4304752950	19184	Federal	Fee	OW	DRL	WOC	60	02/22/13
Three Rivers Federal 3-12-820	Three Rivers Fed 03-12-820	4	080S	200E	4304753914		Federal	Federal	OW	APD	APRVD	1	08/01/13
Three Rivers Federal 3-13-820	Three Rivers Fed 03-13-820	3	080S	200E	4304753951		Federal	Federal	OW	APD	PERPEND	08/12/13	2
Three Rivers Federal 3-14-820	Three Rivers Fed 03-14-820	3	080S	200E	4304753952		Federal	Federal	OW	APD	PERPEND	08/12/13	3
Three Rivers Federal 3-23-820	Three Rivers Fed 03-23-820	3	080S	200E	4304753953		Federal	Federal	OW	APD	PERPEND	08/12/13	4
Three Rivers Federal 3-24-820	Three Rivers Fed 03-24-820	3	080S	200E	4304753954		Federal	Federal	OW	APD	PERPEND	08/12/13	5
THREE RIVERS FEDERAL 3-32-820	Three Rivers Fed 03-32-820	3	080S	200E	4304752861	18942	Federal	Federal	OW	P	P	6	
THREE RIVERS FEDERAL 3-33-820	Three Rivers Fed 03-33-820	3	080S	200E	4304752864		Federal	Federal	OW	APD	APRVD	7	12/24/12
THREE RIVERS FEDERAL 3-53-820	Three Rivers Fed 03-53-820	3	080S	200E	4304752820	19104	Federal	Federal	OW	DRL	P	8	12/24/12
THREE RIVERS FEDERAL 3-54-820	Three Rivers Fed 03-54-820	3	080S	200E	4304752860		Federal	Federal	OW	APD	APRVD	9	12/24/12



ATTACHMENT TO FORM 9 CHANGE OF OPERATOR  
AXIA ENERGY TO ULTRA RESOURCES EFFECTIVE 10-01-2013

State Well Name List downloaded 12-10-13	Axia Well Name (for database sort and consistency)	Sec	TWN	RNG	API Number	Entity	Mineral Lease	Surface Lease	Well Type	State Well Status	Actual Status @ 12/12/13	Submitted	Date Apprvd DOGM
THREE RIVERS 4-21-820	Three Rivers Fed 04-21-820	4	080S	200E	4304752875	19048	Federal	Fee	OW	DRL	P	70	02/22/13
THREE RIVERS FED 4-31-820	Three Rivers Fed 04-31-820	4	080S	200E	4304752874	19023	Federal	Fee	OW	DRL	P	1	02/22/13
Three Rivers Federal 4-32-820	Three Rivers Fed 04-32-820	4	080S	200E	4304753552	19168	Federal	Fee	OW	DRL	P	2	08/26/13
Three Rivers Federal 4-41-820	Three Rivers Fed 04-41-820	4	080S	200E	4304753911		Federal	Federal	OW	APD	APRVD	3	08/01/13
Three Rivers Federal 4-42-820	Three Rivers Fed 04-42-820	4	080S	200E	4304753913		Federal	Federal	OW	APD	APRVD	4	08/01/13
Three Rivers Federal 5-11-820	Three Rivers Fed 05-11-820	5	080S	200E	4304754204		Federal	Federal	OW	NEW	PERPEND	12/03/13	5
Three Rivers Federal 5-21-820	Three Rivers Fed 05-21-820	5	080S	200E	4304754205		Federal	Federal	OW	NEW	PERPEND	12/03/13	6
Three Rivers Federal 5-42-820	Three Rivers Fed 05-42-820	5	080S	200E	4304753958		Federal	Federal	OW	APD	PERPEND	08/19/13	7
Three Rivers Federal 5-43-820	Three Rivers Fed 05-43-820	5	080S	200E	4304753957		Federal	Federal	OW	APD	PERPEND	08/19/13	8
THREE RIVERS FEDERAL 5-56-820	Three Rivers Fed 05-56-820	5	080S	200E	4304752862	18993	Federal	Federal	OW	P	P		
THREE RIVERS FEDERAL 8-52-820	Three Rivers Fed 08-52-820	8	080S	200E	4304752770	19156	Federal	Federal	OW	DRL	P	9	02/22/13
THREE RIVERS FEDERAL 8-53-820	Three Rivers Fed 08-53-820	8	080S	200E	4304752771	18992	Federal	Federal	OW	P	P		
Three Rivers Federal 9-41-820	Three Rivers Fed 09-41-820	10	080S	200E	4304753556	19170	Federal	Federal	OW	DRL	P		08/20/13
THREE RIVERS FED 10-30-820	Three Rivers Fed 10-30-820	10	080S	200E	4304753555	19169	Federal	Federal	OW	DRL	P		08/20/13
Three Rivers Federal 10-31-820	Three Rivers Fed 10-31-820	10	080S	200E	4304753437		Federal	Federal	OW	APD	CCS		08/21/13
Three Rivers Federal 10-32-820	Three Rivers Fed 10-32-820	10	080S	200E	4304753415		Federal	Federal	OW	APD	CCS		08/21/13
THREE RIVERS FED 10-41-820	Three Rivers Fed 10-41-820	10	080S	200E	4304752948	19137	Federal	Federal	OW	DRL	P		02/22/13
THREE RIVERS FED 10-42-820	Three Rivers Fed 10-42-820	10	080S	200E	4304752949		Federal	Federal	OW	APD	APRVD		02/22/13
Three Rivers Federal 33-11-720	Three Rivers Fed 33-11-720	32	070S	200E	4304753733	19109	Federal	Fee	OW	DRL	P		07/17/13
Three Rivers Federal 33-12-720	Three Rivers Fed 33-12-720	33	070S	200E	4304753724	19250	Federal	Fee	OW	DRL	WOC		09/16/13
Three Rivers Federal 33-13-720	Three Rivers Fed 33-13-720	33	070S	200E	4304753723	19222	Federal	Fee	OW	DRL	WOC		09/16/13
Three Rivers Federal 33-14-720	Three Rivers Fed 33-14-720	33	070S	200E	4304753551	19107	Federal	Fee	OW	DRL	P		09/16/13
Three Rivers Federal 33-24-720	Three Rivers Fed 33-24-720	33	070S	200E	4304753557	19108	Federal	Fee	OW	DRL	P		07/09/13
THREE RIVERS FED 34-15-720	Three Rivers Fed 34-15-720	34	070S	200E	4304752965	18960	Federal	Fee	OW	P	P		
THREE RIVERS FED 34-23-720	Three Rivers Fed 34-23-720	34	070S	200E	4304752945	19049	Federal	Fee	OW	DRL	P		02/12/13
Three Rivers Federal 34-25-720	Three Rivers Fed 34-25-720	34	070S	200E	4304753283		Federal	Fee	OW	APD	APRVD		06/10/13
THREE RIVERS FED 34-33-720	Three Rivers Fed 34-33-720	34	070S	200E	4304752947	19050	Federal	Fee	OW	DRL	P		02/22/13
Three Rivers Federal 34-35-720	Three Rivers Fed 34-35-720	34	070S	200E	4304753282		Federal	Fee	OW	APD	APRVD		06/10/13
Three Rivers Federal 34-42-720	Three Rivers Fed 34-42-720	35	070S	200E	4304753915		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 34-43-720	Three Rivers Fed 34-43-720	35	070S	200E	4304753916		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 35-11-720	Three Rivers Fed 35-11-720	35	070S	200E	4304753944		Federal	Federal	OW	APD	PERPEND	07/25/13	100
Three Rivers Federal 35-12-720	Three Rivers Fed 35-12-720	35	070S	200E	4304753917		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 35-13-720	Three Rivers Fed 35-13-720	35	070S	200E	4304753554		Federal	Federal	OW	APD	APRVD		08/20/13
Three Rivers Federal 35-14-720	Three Rivers Fed 35-14-720	35	070S	200E	4304753553		Federal	Federal	OW	APD	APRVD		08/22/13
Three Rivers Federal 35-21-720	Three Rivers Fed 35-21-720	35	070S	200E	4304753943		Federal	Federal	OW	APD	PERPEND	07/25/13	4
THREE RIVERS FED 35-32-720	Three Rivers Fed 35-32-720	35	070S	200E	4304753005	19138	Federal	Federal	OW	DRL	APRVD		02/22/13
THREE RIVERS FED 35-34-720	Three Rivers Fed 35-34-720	35	070S	200E	4304753006		Federal	Federal	OW	APD	APRVD		02/22/13
THREE RIVERS FED 35-42-720	Three Rivers Fed 35-42-720	35	070S	200E	4304753007		Federal	Federal	OW	APD	APRVD		02/22/13
Three Rivers Federal 35-43-720	Three Rivers Fed 35-43-720	35	070S	200E	4304753918		Federal	Federal	OW	APD	APRVD		08/01/13
Three Rivers Federal 35-442-720	Three Rivers Fed 35-442-720	35	070S	200E	4304753919		Federal	Federal	OW	APD	APRVD		08/01/13
THREE RIVERS FED 35-44-720	Three Rivers Fed 35-44-720	35	070S	200E	4304753008		Federal	Federal	OW	APD	APRVD	110	02/22/13
Three Rivers Fed 03-34-820	Three Rivers Fed 03-34-820	3	080S	200E			Federal		NA	SUB		12/10/13	1
Three Rivers Fed 03-44-820	Three Rivers Fed 03-44-820	3	080S	200E			Federal		NA	SUB		12/10/13	2
Three Rivers Fed 08-31-820	Three Rivers Fed 08-31-820	8	080S	200E			Federal		NA	SUB		12/07/13	3
Three Rivers Fed 08-41-820	Three Rivers Fed 08-41-820	9	080S	200E			Federal		NA	SUB		12/07/13	4

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-88623
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> ULTRA RESOURCES INC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 304 Inverness Way South #295, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> THREE RIVERS FED 35-34-720
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1597 FSL 2498 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047530060000
<b>PHONE NUMBER:</b> 303 645-9810 Ext		<b>9. FIELD and POOL or WILDCAT:</b> THREE RIVERS
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: <b>8/1/2014</b>	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"><input type="checkbox"/> ACIDIZE</div> <div style="width: 33%;"><input type="checkbox"/> ALTER CASING</div> <div style="width: 33%;"><input type="checkbox"/> CASING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TO PREVIOUS PLANS</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE TUBING</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL NAME</div> <div style="width: 33%;"><input type="checkbox"/> CHANGE WELL STATUS</div> <div style="width: 33%;"><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</div> <div style="width: 33%;"><input type="checkbox"/> CONVERT WELL TYPE</div> <div style="width: 33%;"><input type="checkbox"/> DEEPEN</div> <div style="width: 33%;"><input type="checkbox"/> FRACTURE TREAT</div> <div style="width: 33%;"><input type="checkbox"/> NEW CONSTRUCTION</div> <div style="width: 33%;"><input type="checkbox"/> OPERATOR CHANGE</div> <div style="width: 33%;"><input type="checkbox"/> PLUG AND ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> PLUG BACK</div> <div style="width: 33%;"><input type="checkbox"/> PRODUCTION START OR RESUME</div> <div style="width: 33%;"><input type="checkbox"/> RECLAMATION OF WELL SITE</div> <div style="width: 33%;"><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> REPERFORATE CURRENT FORMATION</div> <div style="width: 33%;"><input type="checkbox"/> SIDETRACK TO REPAIR WELL</div> <div style="width: 33%;"><input type="checkbox"/> TEMPORARY ABANDON</div> <div style="width: 33%;"><input type="checkbox"/> TUBING REPAIR</div> <div style="width: 33%;"><input type="checkbox"/> VENT OR FLARE</div> <div style="width: 33%;"><input type="checkbox"/> WATER DISPOSAL</div> <div style="width: 33%;"><input type="checkbox"/> WATER SHUTOFF</div> <div style="width: 33%;"><input type="checkbox"/> SI TA STATUS EXTENSION</div> <div style="width: 33%;"><input checked="" type="checkbox"/> APD EXTENSION</div> <div style="width: 33%;"><input type="checkbox"/> WILDCAT WELL DETERMINATION</div> <div style="width: 33%;"><input type="checkbox"/> OTHER</div> </div>
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	
<input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	
OTHER: <input style="width: 100%;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Ultra respectfully requests a one year extension on the state permit for the referenced well. This is the second extension that has been requested.

**Approved by the  
 Utah Division of  
 Oil, Gas and Mining**  
 July 02, 2014

**Date:** \_\_\_\_\_  
**By:**

<b>NAME (PLEASE PRINT)</b> Jenna Anderson	<b>PHONE NUMBER</b> 303 645-9804	<b>TITLE</b> Permitting Assistant
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/1/2014	



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Request for Permit Extension Validation Well Number 43047530060000**

**API:** 43047530060000

**Well Name:** THREE RIVERS FED 35-34-720

**Location:** 1597 FSL 2498 FEL QTR NWSE SEC 35 TWNP 070S RNG 200E MER S

**Company Permit Issued to:** ULTRA RESOURCES INC

**Date Original Permit Issued:** 8/2/2012

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

- If located on private land, has the ownership changed, if so, has the surface agreement been updated? ☒ Yes ☐ No
- Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? ☐ Yes ☒ No
- Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? ☐ Yes ☒ No
- Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? ☐ Yes ☒ No
- Has the approved source of water for drilling changed? ☐ Yes ☒ No
- Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? ☐ Yes ☒ No
- Is bonding still in place, which covers this proposed well? ☒ Yes ☐ No

**Signature:** Jenna Anderson

**Date:** 7/1/2014

**Title:** Permitting Specialist **Representing:** ULTRA RESOURCES INC

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>																														
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-88623																														
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>																														
<b>2. NAME OF OPERATOR:</b> ULTRA RESOURCES INC		<b>7. UNIT or CA AGREEMENT NAME:</b>																														
<b>3. ADDRESS OF OPERATOR:</b> 304 Inverness Way South #295, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> THREE RIVERS FED 35-34-720																														
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1597 FSL 2498 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047530060000																														
<b>PHONE NUMBER:</b> 303 645-9810 Ext		<b>9. FIELD and POOL or WILDCAT:</b> THREE RIVERS																														
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH																														
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>																																
<b>TYPE OF SUBMISSION</b>  <input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 7/24/2014  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<b>TYPE OF ACTION</b>  <table style="width: 100%;"> <tr> <td><input type="checkbox"/> ACIDIZE</td> <td><input type="checkbox"/> ALTER CASING</td> <td><input type="checkbox"/> CASING REPAIR</td> </tr> <tr> <td><input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS</td> <td><input type="checkbox"/> CHANGE TUBING</td> <td><input type="checkbox"/> CHANGE WELL NAME</td> </tr> <tr> <td><input type="checkbox"/> CHANGE WELL STATUS</td> <td><input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS</td> <td><input type="checkbox"/> CONVERT WELL TYPE</td> </tr> <tr> <td><input type="checkbox"/> DEEPEN</td> <td><input type="checkbox"/> FRACTURE TREAT</td> <td><input type="checkbox"/> NEW CONSTRUCTION</td> </tr> <tr> <td><input type="checkbox"/> OPERATOR CHANGE</td> <td><input type="checkbox"/> PLUG AND ABANDON</td> <td><input type="checkbox"/> PLUG BACK</td> </tr> <tr> <td><input type="checkbox"/> PRODUCTION START OR RESUME</td> <td><input type="checkbox"/> RECLAMATION OF WELL SITE</td> <td><input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION</td> </tr> <tr> <td><input type="checkbox"/> REPERFORATE CURRENT FORMATION</td> <td><input type="checkbox"/> SIDETRACK TO REPAIR WELL</td> <td><input type="checkbox"/> TEMPORARY ABANDON</td> </tr> <tr> <td><input type="checkbox"/> TUBING REPAIR</td> <td><input type="checkbox"/> VENT OR FLARE</td> <td><input type="checkbox"/> WATER DISPOSAL</td> </tr> <tr> <td><input type="checkbox"/> WATER SHUTOFF</td> <td><input type="checkbox"/> SI TA STATUS EXTENSION</td> <td><input type="checkbox"/> APD EXTENSION</td> </tr> <tr> <td><input type="checkbox"/> WILDCAT WELL DETERMINATION</td> <td><input type="checkbox"/> OTHER</td> <td>OTHER: <input style="width: 100px;" type="text"/></td> </tr> </table>		<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR																														
<input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME																														
<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE																														
<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION																														
<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK																														
<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION																														
<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON																														
<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL																														
<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION																														
<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>																														
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> This well was originally permitted by Axia. Ultra requests the following changes to fit our pad design and drilling program: (1) Change TD from 8,990 MD/8,917 TVD to 7,409 MD/7,280 TVD; (2) Change SHL & BHL per attached plat dated 6-19-14; (3) Update drilling plan and directional plan. Ultra's directional drilling letter is also attached.																																
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b>  <b>Date:</b> _____ <b>By:</b> <u>Derek Quist</u>																																
<b>NAME (PLEASE PRINT)</b> Jenna Anderson	<b>PHONE NUMBER</b> 303 645-9804	<b>TITLE</b> Permitting Assistant																														
<b>SIGNATURE</b> N/A	<b>DATE</b> 7/10/2014																															

**T7S, R20E, S.L.B.&M.**W 1/4 Cor. Sec. 26  
Brass Cap, 0.3'  
High, Steel Post1950 Brass Cap,  
0.5' High, Mound  
of Stones, N-S  
Fenceline1988 Brass Cap,  
Flush with Ground,  
Fence CornerS81°44'27"W  
1337.97' (Meas.)S83°23'23"E  
1337.16' (Meas.)S89°07'18"E  
1434.87' (Meas.)

S83°59'21"W - 2664.19' (Meas.)

NW Cor NE 1/4  
NE 1/4 Sec. 34  
1988 Brass Cap,  
0.1' High, South  
of FenceRe-Established  
Corner By Double  
Proportion Method  
(Not Set on Ground)Re-Established  
Corner By Grant  
Boundary Method  
(Not Set on Ground)**LEGEND:**

- └─ = 90° SYMBOL
- = PROPOSED WELLHEAD.
- = TARGET BOTTOM HOLE.
- ▲ = SECTION CORNERS  
LOCATED.
- △ = SECTION CORNERS  
RE-ESTABLISHED.  
(Not Set on Ground.)

N00°12'16"W - 2703.71' (Meas.)

1988 Brass Cap,  
0.2' Below Ground

Brass Cap

1950 Brass Cap,  
1.0' High**35**Target  
Bottom Hole

1980'

THREE RIVERS  
FED #35-34-720  
Elev. Ungraded  
Ground = 4822.9'

2492'

1988 Brass  
Cap, Flush  
W/Ground,  
Between  
N-S Fence  
& N-S Road1950 Brass Cap,  
0.7' High

N00°41'05"W - 2704.87' (Meas.)


1988 Brass  
Cap, 0.5' High  
E-W Fence1988 Brass  
Cap, 0.1'  
High, E-W  
Fence

S89°47'10"W - 2631.47' (Meas.)

S89°47'33"W - 2631.35' (Meas.)

**T7S**  
**T8S**N01°06'50"E  
1375.18' (Meas.)N01°07'16"E  
1375.19' (Meas.)N01°08'00"E  
1371.77' (Meas.)N01°07'40"E  
1371.00' (Meas.)**LINE TABLE**

LINE	DIRECTION	LENGTH
L1	N67°16'58"W	916.94'



NAD 83 (TARGET BOTTOM HOLE)	NAD 83 (SURFACE LOCATION)
LATITUDE = 40°09'52.56" (40.164600)	LATITUDE = 40°09'49.05" (40.163625)
LONGITUDE = 109°38'18.04" (109.638344)	LONGITUDE = 109°38'07.15" (109.635219)

**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD  
NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION  
AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY  
KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH 06-19-14

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION

**BASIS OF ELEVATION**

BENCH MARK (38EAM) LOCATED IN THE SW 1/4 OF SECTION 9, T7S, R20E, S.L.B.&M.  
TAKEN FROM THE PELICAN LAKE, QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE  
QUAD (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE  
INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4942 FEET.

**ULTRA RESOURCES, INC.**

**THREE RIVERS FED #35-34-720**  
**NW 1/4 SE 1/4, SECTION 35, T7S, R20E, S.L.B.&M.**  
**UINTAH COUNTY, UTAH**

SURVEYED BY: M.P., T.P.	SURVEY DATE: 04-30-14
DRAWN BY: C.C.	DATE DRAWN: 05-07-14
SCALE: 1" = 1000'	REVISION: 00-00-00

**WELL LOCATION PLAT**

**UELS, LLC**  
Corporate Office \* 85 South 200 East  
Vernal, UT 84078 \* (435) 789-1017



RECEIVED: Jul. 10, 2014



**ULTRA RESOURCES, INC.**

**MASTER**  
**8 - POINT DRILLING PROGRAM**

**Slim Hole Design**  
**8 5/8" Surface & 5 1/2" Production Casing Design**

**DATED: 07-10-14**

**Directional Wells located on Ultra leases in  
Three Rivers Project:**

**Three Rivers Fed 35-34-720**

**SHL: Sec 35 (NWSE) T7S R20E**

**Uintah, Utah**

**ONSHORE OIL & GAS ORDER NO. 1**  
**Approval of Operations on Onshore**  
**Federal and Indian Oil and Gas Leases**

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (CFR 43, Part 3160) and the approved Application for Permit to Drill. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations.

**1. Formation Tops**

The estimated tops of important geologic markers are as follows:

<u>Formation Top</u>	<u>Top (TVD)</u>	<u>Comments</u>
Uinta	Surface	
BMSW	2,641' MD / 2,600' TVD	
Green River	3,244' MD / 3,175' TVD	
Mahogany	4,607' MD / 4,480' TVD	
Garden Gulch	5,289' MD / 5,160' TVD	Oil & Associated Gas
Lower Green River*	5,469' MD / 5,340' TVD	Oil & Associated Gas
Wasatch	7,159' MD / 7,030' TVD	Oil & Associated Gas
TD	7,409' MD / 7,280' TVD	

**Asterisks (\*) denotes target pay intervals**

All shows of fresh water and minerals will be reported and protected. A sample will be taken of any water flows and a water analysis furnished to the BLM. Oil and gas shows will be adequately tested for commercial possibilities, reported and protected by casing and cement.

**2. BOP Equipment**

- A) The BOPE shall be closed whenever the well is unattended The Bureau of Land Management will be notified 24 hours prior to all BOPE pressure tests. The State of Utah, Division of Oil, Gas and Mining will be notified 24 hours prior to all BOPE pressure tests.
- B) The BOPE shall be closed whenever the well is unattended.
- C) As per 43 CFR 3160, Onshore Oil and Gas Order No. 2, Drilling Operations, Part A:
- 1) All BOPE connections subjected to well pressure will be flanged, welded, or clamped.
  - 2) Choke Manifold
  - 3) Tee blocks or targeted 'T's will be used and anchored to prevent slip and reduce vibration.
  - 4) Two adjustable chokes will be used in the choke manifold.
  - 5) All valves (except chokes) in kill line choke manifold and choke line will not restrict the flow.
  - 6) Pressure gauges in the well control system will be designed for drilling fluid.
- D) BOPE Testing:
- 1) BOPE shall be pressure tested when initially installed, whenever any seal subject to pressure testing is broken, or after repairs.
  - 2) All BOP tests will be performed with a test plug in place.
  - 3) BOP will be tested to full stack working pressure and annular preventer to 50% stack working pressure.

**INTERVAL**

0 - 1,000' MD / 1,000' TVD

1,000' MD / 1,000' TVD – 7,409' MD / 7,280' TVD

**BOP EQUIPMENT**

11" Diverter with Rotating Head

3,000# Ram Double BOP & Annular with Diverter & Rotating Head

NOTE: Drilling spool to accommodate choke and kill lines.

**3. Casing and Float Equipment Program****CASING:**

<b>Directional Well</b>	<b>Hole Size</b>	<b>OD</b>	<b>Depth MD/TVD</b>	<b>Wt.</b>	<b>Grade &amp; Connection</b>	<b>Cond.</b>
<b>Surface</b>	11"	8 5/8"	1,000' MD / 1,000' TVD	24.0 ppf	J-55, LTC	New
<b>Production</b>	7 7/8"	5 1/2"	7,409' MD / 7,280' TVD	17.0 ppf	J-55, LTC	New

**CASING SPECIFICATIONS:**

Directional Well	Casing OD	Casing ID / Drift ID	Collapse (psi)	Int. Yield (psi)	Ten. Yield (lb)	Jt. Strength (lb)
Surface	8 5/8"	8.097" / 7.972"	1,370	2,950	381,000	244,000
Production	5 1/2"	4.492" / 4.767"	4,910	5,320'	273,000	229,000

**FLOAT EQUIPMENT:**

SURFACE (8 5/8")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1<sup>st</sup> 4 Joints then every 4<sup>th</sup> joint to surface

PRODUCTION (5 1/2")

Float Shoe, 1 joint casing, float collar

Centralizers: 1 each 1<sup>st</sup> 4 Joints then every 3<sup>rd</sup> joint to 500' into surface casing**4. Cementing Programs****CONDUCTOR (13 3/8")**

Ready Mix – Cement to surface

**SURFACE (8 5/8")**

Surface – 500'

Cement Top - Surface

Lead: 80 sks, Premium Lightweight Cmt w/ additives, 11.5 ppg, 2,97 cf/sk 50% excess

500' – 1,000' MD / 1,000' TVD± Tail: 115 sks Glass G Cement w/ additives, 15.8 ppg, 1.16 cf/sx, 50% excess

Note: The above volumes are based on a gauge-hole + 50% excess.

**PRODUCTION (5 1/2")**

500' - 4,000' TVD ±

Cement Top – 500'

Lead: 225 sks – Econocem Cement w/ 0.25 lbm Poly-E-Flake, 1% Granulite TR 1/4, 5 lbm Kol-Seal; 11.0 ppg; 3.54 cf/sx; 15% excess

4,000' – 7,409' MD / 7,280' TVD Tail: 450 sks, Expandacem Cement w/ 0.25 lbm Poly-E-Flake, 1 lbm Granulite TR 1/4, 2 lbm Kol-Seal; 14.0 pp; 1.349 cf/sk; 15% excess

Note: Lead Cement will be brought to 4,000' which will give a minimum of 500' above Lower Green River.

- A) For Surface casing, if cement falls or does not circulate to surface, cement will be topped off.  
 B) Cement will not be placed down annulus with a 1" pipe unless BLM is contacted.  
 C) The Bureau of Land Management will be notified 24 hours prior to running casing and cementing.  
 D) As per 43 CFR 3160, Onshore Oil and Gas Order No.2, Drilling Operations, Part B:
- 1) All waiting on cement times shall be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe (minimum of 8 hours) prior to drilling out.
  - 2) Prior to drilling out cement, casing will be pressure tested to 1500 psi. Pressure decline must not be greater than 10% (150 psi) in 30 minutes.
  - 3) Progress reports, Form 3160-5 "Sundry Notices and Reports on Wells", shall be filed with the Field Manager within 30 days after the work is completed.
  - 4) Setting of each string of casing, size, grade, weight of casing set, hole size, setting depth, amounts and type of cement used, whether cement circulated or the top of the cement behind the casing, depth of cementing tools used, casing test method and results, and the date work was done. Show the spud date on the first reports submitted.
  - 5) Temperature or bond logs must be submitted for each well where the casing cement was not circulated to the surface.

- 6) A pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed after drilling 5-10 feet of new hole.

## 5. Mud Program

The proposed circulating mediums to be employed in drilling are as follows:

Interval	Mud Type	Viscosity	Fluid Loss	pH	Mud Wt. (ppg)
0 – 1,000' MD / 1,000' TVD	Water/Spud Mud	32	No Control (NC)	7.0 -8.2	<8.8
1,000' MD / 1,000' TVD - 7,409' MD / 7,280' TVD	DAP System	40 - 60	10 - 18	7.0-8.2	<10.0

- A) For Surface Sufficient quantities of mud materials will be maintained or readily accessible for the purpose of assuring well control during the course of drilling operations. A mud test shall be performed every 24 hours after mudding up to determine, as applicable: density, viscosity, gel strength, filtration, and pH.
- B) The mud monitoring equipment on location will be installed by top of Green River and will be able to monitor at a minimum the pit volume totalizer (PVT), stroke counter, and flow sensor
- C) Flare line discharge will be located no less than 100 feet from the wellhead using straight or targeted 'T' and anchors.

## 6. Evaluation Program - Testing, Logging, and Coring

- A) Cores: None anticipated.
- B) Testing: None anticipated.
- C) Directional Drilling: Directional tools will be used to locate the bottom hole per the attached directional plan +/-.
- D) Open Hole Logs: TD to surface casing: resistivity, neutron density, gamma ray and caliper.
- E) Mud Logs: None anticipated.
- F) Formation to TD; record and monitor gas shows and record drill times (normal mud logging duties).

## 7. Anticipated Pressures and H.S.

- A) The expected bottom hole pressure is 3,500 – 3,650 psig. Normal pressures are anticipated from surface to approximately TD. These pressures will be controlled by a blowout preventer stack, annular BOP, choke manifold, mud/gas separator, surface equipment and drilling mud. A supply of barite to weight the mud to a balancing specific gravity, if necessary, will be on location.
- B) Maximum expected surface pressure will be based on the frac gradient of the casing shoe. The design of the casing assumes that the MASP will be the fracture pressure at the shoe less a column of gas.
- C) No hydrogen sulfide gas is anticipated, however if H<sub>2</sub>S is encountered, the guidelines in Onshore Oil and Gas Order No. 6 will be complied with.

## 8. Other Information and Notification Requirements

- A) There shall be no deviation from the proposed drilling and/or workover program as approved. Any changes in operation must have prior approval from the *Utah Division of Oil, Gas and Mining*, and the BLM Vernal (when drilling on Federal leases).

- 1) Anticipated starting date will be upon approval. It is anticipated that completion operations will begin within 15 days after the well has been drilled.
  - 2) It is anticipated that the drilling and completion of this well will take approximately 90 days.
- B) Notification Requirements for ***Utah Division of Oil, Gas and Mining***:
- ***Within 24 hrs. of spud (Carol Daniels at 801/538-5284)***
  - ***24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)***
  - ***24 hrs. prior to cementing or testing casing (Dan Jarvis)***
  - ***Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)***
- C) Notification Requirements BLM Vernal ***when drilling on Federal leases as follows: (Cade T Taylor @ [cctaylor@blm.gov](mailto:cctaylor@blm.gov) and [Blm\\_ut\\_vn\\_opreport@blm.gov](mailto:Blm_ut_vn_opreport@blm.gov)***:
- ***Within 24 hrs. of spud (Carol Daniels at 801/538-5284)***
  - ***24 hrs. prior to testing BOP equipment (Dan Jarvis 801/538-5338 or 231-8956)***
  - ***24 hrs. prior to cementing or testing casing (Dan Jarvis)***
  - ***Within 24 hrs. of making any emergency changes to APD (Dustin Doucet 801/538-5281 or 733-0983)***
- D) Any changes in the program must be approved by the ***Utah Division of Oil, Gas and Mining*** and or the BLM Vernal Office. "Sundry Notices and Reports on Wells" (form 3160-5) must be filed for all changes of plans. Emergency approval may be obtained orally, but such approval does not waive the written report requirement.
- 1) Should the well be successfully completed for production, the BLM Pinedale Field Office must be notified when it is placed in a producing status. The notification shall provide, as a minimum, the following information items:
    - Operator name, address, and telephone number.
    - Well name and number.
    - Well location (1/4 1/4, Section, Township, Range and P.M.)
    - Date well was placed in a producing status (date of first production for which royalty will be paid).
    - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
    - The Federal or Indian lease prefix and number on which the well is located. As appropriate, the unit agreement name, number and participating area name. As appropriate, the communitization agreement number.





# ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers Fed 35-34-720 (1623' FSL &amp; 2492' FWL)

Field: UINTAH COUNTY

Well: Three Rivers Fed 35-34-720

Facility: Sec.35-T7S-R20E

Wellbore: Three Rivers Fed 35-34-720 PWB

## Targets



Name	MD (ft)	TVD (ft)	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Three Rivers Fed 35-34-720 Target On Plat 1987 FSL & 1980' FWL	5083.12	4954.00	355.20	-845.46	2105847.58	7234594.69	42°09'52.5007N	108°38'18.0427W

## Well Profile Data

Design Comment	MD (ft)	Inc (°)	Az (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	13.00	0.000	292.789	13.00	0.00	0.00	0.00	0.00
End of Tangent	1200.00	0.000	292.789	1200.00	0.00	0.00	0.00	0.00
End of Build (S)	2089.78	17.796	292.789	2075.55	53.09	-126.37	2.00	137.07
End of Tangent (S)	4193.34	17.796	292.789	4078.45	302.11	-719.08	0.00	779.97
End of Drop (S)	5083.12	0.000	292.789	4954.00	355.20	-845.46	2.00	917.04
End of Tangent	7409.12	0.000	292.789	7280.00	355.20	-845.46	0.00	917.04

## Location Information

Facility Name		Grid East (US ft)	Grid North (US ft)	Latitude	Longitude	
Sec.35-T7S-R20E		2105848.285	7233453.094	42°09'45.007N	108°38'18.043W	
Site	Local N (ft)	Local E (ft)	Grid East (US ft)	Grid North (US ft)	Latitude	Longitude
Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL)	355.20	-845.46	2105848.285	7233710.21	42°09'52.507N	108°38'18.043W
Rig on Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL) RT to Mud line (in Slot Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL))						
Mean Sea Level to Mud line (in Slot Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL))						
0.00						
Rig on Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL) RT to Mean Sea Level						
0.00						
Plot reference wellpath is Three Rivers Fed 35-34-720 PWB						
True vertical depths are referenced to Rig on Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL) (RT)			Grid System: NAD83 / Lambert UTM SP. Central Zone 49KSD, US Unit			
Measured depths are referenced to Rig on Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL) (RT)			North Reference: True north			
Rig on Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL) RT to Mean Sea Level: 4835.9 feet			Scale: True distance			
Mean Sea Level to Mud line (in Slot Three Rivers Fed 35-34-720 (1623' FSL & 2492' FWL)) 0 feet			Depth in air: feet			
Coordinates are in feet referenced to Slot			Quoted by Precision on 7/6/2024			





## Planned Wellpath Report

Three Rivers Fed 35-34-720 PWP

Page 1 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 PWB
Facility	Sec.35-T7S-R20E		

### REPORT SETUP INFORMATION

Projection System	NAD83 / Lambert Utah SP, Central Zone (4302), US feet	Software System	WellArchitect® 3.0.0
North Reference	True	User	EWilliams
Scale	0.999915	Report Generated	7/10/2014 at 3:05:24 PM
Convergence at slot	1.19° East	Database/Source file	WellArchitectDB/Three_Rivers_Fed_35-34-720_PWB.xml

### WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	309.74	2142.01	2161500.20	7233757.21	40°09'49.050"N	109°38'07.150"W
Facility Reference Pt			2159365.27	7233403.09	40°09'45.990"N	109°38'34.740"W
Field Reference Pt			2156630.96	7236613.42	40°10'18.270"N	109°39'09.100"W

### WELLPATH DATUM

Calculation method	Minimum curvature	Rig on Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL) (RT) to Facility Vertical Datum
Horizontal Reference Pt	Slot	Rig on Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL) (RT) to Mean Sea Level
Vertical Reference Pt	Rig on Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL) (RT)	Rig on Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL) (RT) to Mud Line at Slot (Three Rivers Fed 35-34-720 (1623' FSL
MD Reference Pt	Rig on Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL) (RT)	Section Origin
Field Vertical Reference	Mean Sea Level	Section Azimuth



## Planned Wellpath Report

Three Rivers Fed 35-34-720 PWP

Page 2 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 PWB
Facility	Sec.35-T7S-R20E		

### WELLPATH DATA (87 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	292.789	0.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
13.00	0.000	292.789	13.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
113.00†	0.000	292.789	113.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
120.00†	0.000	292.789	120.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	Base Gravel
213.00†	0.000	292.789	213.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
313.00†	0.000	292.789	313.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
413.00†	0.000	292.789	413.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
513.00†	0.000	292.789	513.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
613.00†	0.000	292.789	613.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
713.00†	0.000	292.789	713.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
813.00†	0.000	292.789	813.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
913.00†	0.000	292.789	913.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1013.00†	0.000	292.789	1013.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1113.00†	0.000	292.789	1113.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1200.00	0.000	292.789	1200.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1213.00†	0.260	292.789	1213.00	0.03	0.01	-0.03	40°09'49.050"N	109°38'07.150"W	2.00	
1313.00†	2.260	292.789	1312.97	2.23	0.86	-2.05	40°09'49.059"N	109°38'07.176"W	2.00	
1413.00†	4.260	292.789	1412.80	7.91	3.07	-7.30	40°09'49.080"N	109°38'07.244"W	2.00	
1513.00†	6.260	292.789	1512.38	17.08	6.62	-15.75	40°09'49.115"N	109°38'07.353"W	2.00	
1613.00†	8.260	292.789	1611.57	29.72	11.51	-27.40	40°09'49.164"N	109°38'07.503"W	2.00	
1713.00†	10.260	292.789	1710.26	45.81	17.74	-42.23	40°09'49.225"N	109°38'07.694"W	2.00	
1813.00†	12.260	292.789	1808.33	65.33	25.31	-60.23	40°09'49.300"N	109°38'07.926"W	2.00	
1913.00†	14.260	292.789	1905.66	88.27	34.19	-81.38	40°09'49.388"N	109°38'08.198"W	2.00	
2013.00†	16.260	292.789	2002.13	114.59	44.38	-105.64	40°09'49.489"N	109°38'08.511"W	2.00	
2089.78	17.796	292.789	2075.55	137.07	53.09	-126.37	40°09'49.575"N	109°38'08.778"W	2.00	
2113.00†	17.796	292.789	2097.65	144.17	55.84	-132.91	40°09'49.602"N	109°38'08.862"W	0.00	
2213.00†	17.796	292.789	2192.87	174.73	67.68	-161.09	40°09'49.719"N	109°38'09.225"W	0.00	
2313.00†	17.796	292.789	2288.08	205.29	79.52	-189.27	40°09'49.836"N	109°38'09.588"W	0.00	
2413.00†	17.796	292.789	2383.30	235.86	91.36	-217.44	40°09'49.953"N	109°38'09.951"W	0.00	
2513.00†	17.796	292.789	2478.51	266.42	103.19	-245.62	40°09'50.070"N	109°38'10.314"W	0.00	
2613.00†	17.796	292.789	2573.73	296.98	115.03	-273.80	40°09'50.187"N	109°38'10.677"W	0.00	
2640.59†	17.796	292.789	2600.00	305.41	118.30	-281.57	40°09'50.219"N	109°38'10.777"W	0.00	BMSW
2713.00†	17.796	292.789	2668.94	327.54	126.87	-301.97	40°09'50.304"N	109°38'11.040"W	0.00	
2813.00†	17.796	292.789	2764.16	358.10	138.71	-330.15	40°09'50.421"N	109°38'11.403"W	0.00	
2913.00†	17.796	292.789	2859.37	388.67	150.55	-358.33	40°09'50.538"N	109°38'11.765"W	0.00	
3013.00†	17.796	292.789	2954.59	419.23	162.38	-386.50	40°09'50.655"N	109°38'12.128"W	0.00	
3113.00†	17.796	292.789	3049.80	449.79	174.22	-414.68	40°09'50.772"N	109°38'12.491"W	0.00	
3213.00†	17.796	292.789	3145.02	480.35	186.06	-442.86	40°09'50.889"N	109°38'12.854"W	0.00	
3244.49†	17.796	292.789	3175.00	489.98	189.79	-451.73	40°09'50.925"N	109°38'12.969"W	0.00	Green River Top
3313.00†	17.796	292.789	3240.24	510.92	197.90	-471.03	40°09'51.006"N	109°38'13.217"W	0.00	
3413.00†	17.796	292.789	3335.45	541.48	209.73	-499.21	40°09'51.123"N	109°38'13.580"W	0.00	
3513.00†	17.796	292.789	3430.67	572.04	221.57	-527.39	40°09'51.240"N	109°38'13.943"W	0.00	
3613.00†	17.796	292.789	3525.88	602.60	233.41	-555.56	40°09'51.357"N	109°38'14.306"W	0.00	
3713.00†	17.796	292.789	3621.10	633.17	245.25	-583.74	40°09'51.473"N	109°38'14.669"W	0.00	
3813.00†	17.796	292.789	3716.31	663.73	257.09	-611.92	40°09'51.590"N	109°38'15.032"W	0.00	



## Planned Wellpath Report

Three Rivers Fed 35-34-720 PWP

Page 3 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 PWB
Facility	Sec.35-T7S-R20E		

### WELLPATH DATA (87 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
3913.00†	17.796	292.789	3811.53	694.29	268.92	-640.09	40°09'51.707"N	109°38'15.395"W	0.00	
4013.00†	17.796	292.789	3906.74	724.85	280.76	-668.27	40°09'51.824"N	109°38'15.758"W	0.00	
4113.00†	17.796	292.789	4001.96	755.42	292.60	-696.45	40°09'51.941"N	109°38'16.121"W	0.00	
4193.34	17.796	292.789	4078.45	779.97	302.11	-719.08	40°09'52.035"N	109°38'16.412"W	0.00	
4213.00†	17.402	292.789	4097.19	785.91	304.41	-724.56	40°09'52.058"N	109°38'16.483"W	2.00	
4313.00†	15.402	292.789	4193.12	814.15	315.35	-750.60	40°09'52.166"N	109°38'16.818"W	2.00	
4413.00†	13.402	292.789	4289.97	839.02	324.98	-773.53	40°09'52.261"N	109°38'17.113"W	2.00	
4513.00†	11.402	292.789	4387.63	860.50	333.30	-793.33	40°09'52.344"N	109°38'17.369"W	2.00	
4606.93†	9.524	292.789	4480.00	877.56	339.91	-809.05	40°09'52.409"N	109°38'17.571"W	2.00	Mahogany
4613.00†	9.402	292.789	4485.98	878.55	340.30	-809.97	40°09'52.413"N	109°38'17.583"W	2.00	
4713.00†	7.402	292.789	4584.90	893.17	345.96	-823.44	40°09'52.469"N	109°38'17.756"W	2.00	
4813.00†	5.402	292.789	4684.28	904.32	350.27	-833.72	40°09'52.511"N	109°38'17.889"W	2.00	
4913.00†	3.402	292.789	4783.98	911.99	353.25	-840.80	40°09'52.541"N	109°38'17.980"W	2.00	
5013.00†	1.402	292.789	4883.88	916.18	354.87	-844.67	40°09'52.557"N	109°38'18.030"W	2.00	
5083.12	0.000	292.789	4954.00†	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	2.00	
5113.00†	0.000	292.789	4983.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5213.00†	0.000	292.789	5083.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5289.12†	0.000	292.789	5160.00	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	Garden Gulch
5313.00†	0.000	292.789	5183.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5413.00†	0.000	292.789	5283.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5469.12†	0.000	292.789	5340.00	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	Lower Green River
5513.00†	0.000	292.789	5383.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5613.00†	0.000	292.789	5483.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5713.00†	0.000	292.789	5583.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5813.00†	0.000	292.789	5683.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
5913.00†	0.000	292.789	5783.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6013.00†	0.000	292.789	5883.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6113.00†	0.000	292.789	5983.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6213.00†	0.000	292.789	6083.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6313.00†	0.000	292.789	6183.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6413.00†	0.000	292.789	6283.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6513.00†	0.000	292.789	6383.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6613.00†	0.000	292.789	6483.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6713.00†	0.000	292.789	6583.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6813.00†	0.000	292.789	6683.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
6913.00†	0.000	292.789	6783.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
7013.00†	0.000	292.789	6883.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
7113.00†	0.000	292.789	6983.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
7159.12†	0.000	292.789	7030.00	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	Wasatch
7213.00†	0.000	292.789	7083.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
7313.00†	0.000	292.789	7183.88	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	
7409.12	0.000	292.789	7280.00	917.04	355.20	-845.46	40°09'52.560"N	109°38'18.040"W	0.00	TD



## Planned Wellpath Report

Three Rivers Fed 35-34-720 PWP

Page 4 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 PWB
Facility	Sec.35-T7S-R20E		

### HOLE & CASING SECTIONS - Ref Wellbore: Three Rivers Fed 35-34-720 PWB Ref Wellpath: Three Rivers Fed 35-34-720 PWP

String/Diameter	Start MD [ft]	End MD [ft]	Interval [ft]	Start TVD [ft]	End TVD [ft]	Start N/S [ft]	Start E/W [ft]	End N/S [ft]	End E/W [ft]
16in Conductor	13.00	120.00	107.00	13.00	120.00	0.00	0.00	0.00	0.00
12.25in Open Hole	120.00	1000.00	880.00	120.00	1000.00	0.00	0.00	0.00	0.00
8.625in Casing Surface	13.00	1000.00	987.00	13.00	1000.00	0.00	0.00	0.00	0.00
7.875in Open Hole	1000.00	7409.12	6409.12	1000.00	7280.00	0.00	0.00	355.20	-845.46
5.5in Casing Production	13.00	7409.12	7396.12	13.00	7280.00	0.00	0.00	355.20	-845.46

### TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) Three Rivers Fed 35-34-720 Target On Plat 1980' FSL & 1980' FWL	5083.12	4954.00	355.20	-845.46	2160647.59	7234094.68	40°09'52.560"N	109°38'18.040"W	point





## Planned Wellpath Report

Three Rivers Fed 35-34-720 PWP

Page 5 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 PWB
Facility	Sec.35-T7S-R20E		

### WELLPATH COMMENTS

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Comment
120.00	0.000	292.789	120.00	Base Gravel
2640.59	17.796	292.789	2600.00	BMSW
3244.49	17.796	292.789	3175.00	Green River Top
4606.93	9.524	292.789	4480.00	Mahogany
5289.12	0.000	292.789	5160.00	Garden Gulch
5469.12	0.000	292.789	5340.00	Lower Green River
7159.12	0.000	292.789	7030.00	Wasatch
7409.12	0.000	292.789	7280.00	TD



# Ultra Resources, Inc.

---

July 10, 2014

Mr. Dustin Doucet  
Utah Division of Oil, Gas & Mining  
1594 West North Temple  
Salt Lake City, Utah 84116

RE: Directional Drilling – Docket No. 2013-030 / Cause No. 270-02

**Three Rivers Fed 35-34-720**

Surface Location: 1623' FSL & 2492' FEL, NWSE, Sec. 35, T7S, R20E

Target Location: 1980' FSL & 1980' FWL, NESW, Sec. 35, T7S, R20E

SLB&M, Uintah County, Utah

Mr. Doucet:

Ultra Resources, Inc. ("Ultra") respectfully submits the below specifics concerning the proposed directional drilling of the subject well:

- Ultra is the sole owner of 100% of the leasehold rights within 460' around proposed bottom hole location and point of penetration of productive interval.
- The directional drilling of the well is proposed to limit surface disturbance within the project and affected surface owners.

Therefore, based on the above stated information, Ultra requests the permit be granted pursuant to Cause No. 270-02.

Thank you in advance for your consideration. Please feel free to contact me at 303-645-9810 if you have any questions or comments.

Sincerely,

Debbie Ghani  
Sr. Permitting Specialist

/dg

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-88623
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> ULTRA RESOURCES INC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 304 Inverness Way South #295 , Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> THREE RIVERS FED 35-34-720
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1623 FSL 2492 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047530060000
<b>PHONE NUMBER:</b> 303 645-9810 Ext		<b>9. FIELD and POOL or WILDCAT:</b> THREE RIVERS
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> ALTER CASING	
<input checked="" type="checkbox"/> SPUD REPORT Date of Spud: 8/22/2014	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input type="checkbox"/> OTHER	
	OTHER: <input style="width: 100px;" type="text"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  ra Resources will be moving ProPetro to spud the Three Rivers Fed 35-34-720 (API #43-047-53006) on 8/22/2014.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> August 22, 2014		
<b>NAME (PLEASE PRINT)</b> Jenna Anderson	<b>PHONE NUMBER</b> 303 645-9804	<b>TITLE</b> Permitting Assistant
<b>SIGNATURE</b> N/A	<b>DATE</b> 8/22/2014	

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
		5. LEASE DESIGNATION AND SERIAL NUMBER: UTU-88623
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
		7. UNIT or CA AGREEMENT NAME:
1. TYPE OF WELL Oil Well		8. WELL NAME and NUMBER: THREE RIVERS FED 35-34-720
2. NAME OF OPERATOR: ULTRA RESOURCES INC		9. API NUMBER: 43047530060000
3. ADDRESS OF OPERATOR: 304 Inverness Way South #295, Englewood, CO, 80112		9. FIELD and POOL or WILDCAT: THREE RIVERS
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1623 FSL 2492 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		COUNTY: UINTAH
		STATE: UTAH

11.

CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION  OTHER: <input style="width: 100px;" type="text"/>
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:			
<input type="checkbox"/> SPUD REPORT Date of Spud:			
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 11/7/2014			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Monthly status report of drilling and completion attached.

**Accepted by the**  
**Utah Division of**  
**Oil, Gas and Mining**  
**FOR RECORD ONLY**  
 November 12, 2014

NAME (PLEASE PRINT) Jenna Anderson	PHONE NUMBER 303 645-9804	TITLE Permitting Assistant
SIGNATURE N/A		DATE 11/7/2014

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 09/02/2014

WELL NAME

THREE RIVERS FED 35-34-720

AFE#

140979

SPUD DATE

09/02/2014

WELL SITE CONSULTANT

JARED MEJORADO

PHONE#

435-219-4933

CONTRACTOR

Other

TD AT REPORT

1,030'

FOOTAGE

911'

PRATE

CUM. DRLG. HRS

DRLG DAYS SINCE SPUD

0

ANTICIPATED TD

7,176'

PRESENT OPS

Drilling at 1,030'

GEOLOGIC SECT.

DAILY MUD LOSS

SURF:

DH:

CUM. MUD LOSS

SURF:

DH:

MUD COMPANY:

MUD ENGINEER:

LAST BOP TEST

NEXT CASING SIZE

8 5/8

NEXT CASING DEPTH

1,003

SSE

SSED

TIME BREAKDOWN

RIG UP / TEAR DOWN 2.00

DETAILS

Start	End	Hrs	
05:30	07:30	02:00	MOVE RIG ON LOCATION & RIG UP

AFE Days vs Depth:

AFE Cost Vs Depth:

DWOP Days vs Depth:

# LL/BP Received Today:

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,500.0	1,500.0		0.0	1,500.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:		Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg		
Conductor		08/22/2014	16	ARJ-55	45	147				

RECENT BITS:		MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
BIT	SIZE									

BIT OPERATIONS:		RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
BIT	WOB										

RECENT MUD MOTORS:		MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
#	SIZE									

MUD MOTOR OPERATIONS:		REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
#	WOB								

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	

SURFACE PUMP/BHA INFORMATION										
Pump 1 Liner		Stroke Len		SPM		PSI		GPM		SPR
Pump 2 Liner		Stroke Len		SPM		PSI		GPM		SPR
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR
BHA Makeup								Length		Hours on BHA
Up Weight	0	Dn Weight	0	RT Weight	0			Torque	0	Hours on Motor

DAILY COSTS			DAILY	CUM	AFE				DAILY	CUM	AFE
8100..100: Permits & Fees				14,117	4,500	8100..105: Insurance					2,000
8100..110: Staking & Surveying					1,500	8100..120: Surface Damages & R					
8100..200: Location Roads					50,000	8100..210: Reclamation					
8100..220: Secondary Reclamati						8100..230: Pit Solidification					5,000
8100..300: Water Well						8100..310: Water/Water Dispos		1,413		7,500	
8100..320: Mud & Chemicals					45,000	8100..325: Oil Base Mud Diesel					
8100..400: Drilling Rig					127,000	8100..402: Drilling Rig Cleani					
8100..405: Rig Fuel					40,000	8100..410: Mob/Demob					17,000
8100..420: Bits & Reamers					15,500	8100..500: Roustabout Services					7,000
8100..510: Testing/Inspection/					5,000	8100..520: Trucking & Hauling		735		10,000	
8100..530: Equipment Rental					25,000	8100..531: Down Hole Motor Ren					1,500
8100..532: Solids Control Equi					7,000	8100..535: Directional Drillin					76,000
8100..540: Fishing						8100..600: Surface Casing/Inte		17,086		20,000	
8100..605: Cementing Work					25,000	8100..610: P & A					
8100..700: Logging - Openhole					15,000	8100..705: Logging - Mud					
8100..800: Supervision/Consult					25,000	8100..810: Engineering/Evaluat					
8100..900: Contingencies				236		8100..950: Administrative O/H					
8100..999: Non Operated IDC						8200..510: Testing/Inspection/					2,000
8200..520: Trucking & Hauling					7,000	8200..530: Equipment Rental					37,500
8200..605: Cementing Work					25,000	8210..600: Production Casing					94,000
8210..620: Wellhead/Casing Hea					20,000	Total Cost		33,586		717,000	



ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 09/03/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979	SPUD DATE	09/02/2014
WELL SITE CONSULTANT	JARED MEJORADO			PHONE#	435-219-4933	CONTRACTOR	Other
TD AT REPORT	(no data)	FOOTAGE		PRATE		CUM. DRLG. HRS	17.5
ANTICIPATED TD	7,176'	PRESENT OPS		(nothing recorded)		GEOLOGIC SECT.	
DAILY MUD LOSS	SURF:		DH:		CUM. MUD LOSS	SURF:	
MUD COMPANY:				MUD ENGINEER:			DH:
LAST BOP TEST	NEXT CASING SIZE			NEXT CASING DEPTH		SSE	SSED

TIME BREAKDOWN							
	CASING & CEMENT	2.00		COND MUD & CIRCULATE	0.50		DRILLING
	RIG UP / TEAR DOWN	2.50		TRIPPING	2.00		17.50

DETAILS				
Start	End	Hrs		
05:30	07:30	02:00	MOVE RIG ON LOCATION & RIG UP	
07:30	01:00	17:30	DRILL FROM 119' TO 1030' (T.D.)	
01:00	01:30	00:30	CIRCULATE HOLE CLEAN	
01:30	03:30	02:00	TRIP OUT OF HOLE F/ 1030' T/ 0'	
03:30	04:30	01:00	RUN 23JTS 8 5/8 24# J-55 CASING - SHOE SET @ 1003' FLOAT COLLAR @ 958' - THREADLOCKED SHOE, SHOE JT & FLOAT COLLAR - CENTRALIZERS RAN ON FIRST 4 JOINTS & THEN EVERY FOURTH JOINT TO SURFACE	
			CEMENT	
04:30	05:30	01:00	RIG DOWN & MOVE ON LOCATION TO NEXT WELL	
05:30	06:00	00:30		

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

CASING EQUIPMENT  
23JTS 8 5/8 24# J-55 CSG W/ SHOE + SHOE JT & FLOAT COLLAR ALL THREADLOCKED - CENTRALIZE FIRST 4 JOINTS THEN EVERY FOURTH TO SURFACE

CEMENT JOB SUMMARY  
PRESSURE TEST LINES TO 3000PSI - PUMP 20BBLS FRESH WATER - PUMP 25BBLS WATER+GEL - PUMP 138.2BBLS 15.8 CEMENT 1.15 YIELD (675 SXS)5 GAL/SX MIX WATER - DISPLACE 61BBLS FRESH WATER - LAND PLUG W/ 400PSI+500 OVER FOR 1MIN - FLOATS HELD - BLEED BACK 1BBL TO TRUCK - GOOD RETURNS THROUGHOUT JOB - 35BBLS CEMENT TO SURFACE.

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:											
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		

SURFACE PUMP/BHA INFORMATION											
Pump 1 Liner	Stroke Len	SPM	PSI	GPM	SPR	Slow PSI					
Pump 2 Liner	Stroke Len	SPM	PSI	GPM	SPR	Slow PSI					
Pump 32 Liner	Stroke Len	SPM	PSI	GPM	SPR	Slow PSI					
BHA Makeup				Length		Hours on BHA	0				
Up Weight	0	Dn Weight	0	RT Weight	0	Hours on Motor					

DAILY COSTS	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads	32,524	32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	1,628	3,041	7,500
8100..320: Mud & Chemicals			45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	29,760	29,760	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/			5,000	8100..520: Trucking & Hauling		735	10,000
8100..530: Equipment Rental			25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi			7,000	8100..535: Directional Drillin			76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work	18,931	18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult			25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	9,038	9,274		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	91,881	125,467	717,000

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-88623
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> ULTRA RESOURCES INC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 304 Inverness Way South #295, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> THREE RIVERS FED 35-34-720
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1623 FSL 2492 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047530060000
<b>PHONE NUMBER:</b> 303 645-9809 Ext		<b>9. FIELD and POOL or WILDCAT:</b> THREE RIVERS
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> CHANGE WELL NAME	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> CONVERT WELL TYPE	
<input checked="" type="checkbox"/> DRILLING REPORT Report Date: 12/12/2014	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> NEW CONSTRUCTION	
	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> PLUG BACK	
	<input type="checkbox"/> PRODUCTION START OR RESUME	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	<input type="checkbox"/> TEMPORARY ABANDON	
	<input type="checkbox"/> TUBING REPAIR	<input type="checkbox"/> VENT OR FLARE	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> WATER SHUTOFF	<input type="checkbox"/> SI TA STATUS EXTENSION	<input type="checkbox"/> APD EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	<input type="checkbox"/> OTHER	OTHER: <input style="width: 100px;" type="text"/>	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 Monthly status report of drilling and completion attached.

Accepted by the  
 Utah Division of  
 Oil, Gas and Mining  
**FOR RECORD ONLY**  
 December 17, 2014

<b>NAME (PLEASE PRINT)</b> Jenna Anderson	<b>PHONE NUMBER</b> 303 645-9804	<b>TITLE</b> Permitting Assistant
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/12/2014	

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/09/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979		SPUD DATE	11/10/2014		
WELL SITE CONSULTANT	JOHN FREITAS/ KING BROWN			PHONE#	713-948-9196		CONTRACTOR	Ensign 122		
TD AT REPORT	0'	FOOTAGE	0'	PRATE			CUM. DRLG. HRS	17.5	DRLG DAYS SINCE SPUD	0
ANTICIPATED TD	7,176'		PRESENT OPS	Directional Drilling at 0'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:		DH:		CUM. MUD LOSS		SURF:		DH:	
MUD COMPANY:				MUD ENGINEER:						
LAST BOP TEST				NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	7,156	SSE		SSED

TIME BREAKDOWN

DETAILS		
Start	End	Hrs
05:55	05:55	00:00
SAFETY MEETING DAYS:PPE, SWA. SAFETY MEETING NIGHTS: PPE,SWA. REGULATORY VISITS: NONE. INCIDENTS: NONE. SAFETY DRILLS: NONE REGULATORY NOTICES: NOTICE TO STATE AND BLM TO TEST BOP. DAYLIGHT: 5 CREW MEMBERS NIGHTS: 5 CREW MEMEBERS		

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE

Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel		3,010.0		3,010.0	1,500.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours					
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:											
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R		

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		

MUD MOTOR OPERATIONS:										
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP		

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,000	GPM	440	SPR	43	Slow PSI	0
Pump 2 Liner	6.5	Stroke Len	9.0	SPM		PSI		GPM		SPR		Slow PSI	—
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR		Slow PSI	—
BHA Makeup		STEARABLE						Length	886.9			Hours on BHA	0
Up Weight	17,000	Dn Weight	0	RT Weight	0			Torque	0			Hours on Motor	0

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		JJ3957	SMITH MDI616
2	MUD MOTOR	6.500	0.000	28.09		6113	1.5 DEG FBH 7/8 4.8STG. .33REV
3	NON MAG MONEL	6.063	2.875	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.313	2.813	3.80		GSB0401	4.5 XH P x B
5	NON MAG FLEX MONEL	6.000	2.750	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.750	29.45		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.750	548.65		RIG	4.5 XH P x B
8	DRILLING JARS	6.375	2.250	32.00		42259G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
9	6JTS HWDP	4.500	2.750	182.79		RIG	4.5 XH P x B

DAILY COSTS	DAILY	CUM	A/E		DAILY	CUM	A/E
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Dispos		3,041	7,500
8100..320: Mud & Chemicals			45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,425	49,185	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob			17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/			5,000	8100..520: Trucking & Hauling		735	10,000
8100..530: Equipment Rental	3,311	3,311	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	425	7,000	8100..535: Directional Drillin	5,000	5,000	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	4,800	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies		9,274		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	32,961	158,428	717,000

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/10/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979	SPUD DATE	11/10/2014	
WELL SITE CONSULTANT	JOHN FREITAS/KINGBROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122	
TD AT REPORT	1,043'	FOOTAGE	0'	PRATE	CUM. DRLG. HRS	17.5	DRLG DAYS SINCE SPUD	0
ANTICIPATED TD	7,176'	PRESENT OPS	Drilling Cement at 1,043'			GEOLOGIC SECT.		
DAILY MUD LOSS	SURF:	DH:	CUM. MUD LOSS			SURF:	DH:	
MUD COMPANY:	ANCHOR			MUD ENGINEER:			DAN KASTEL	
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		7,156	SSE	SSED

TIME BREAKDOWN			
NIPPLE UP B.O.P.	2.00	PRESSURE TEST B.O.P.	5.50
RIG UP / TEAR DOWN	3.00	TRIPPING	1.00
WORK BHA	2.50		
		RIG MOVE	8.00
		WASH & REAM	2.00

DETAILS			
Start	End	Hrs	
06:00	14:00	08:00	ROAD MOVE RIG TO THE TR FED 35-34-720.
14:00	17:00	03:00	RIG UP ON LOCATION, RIG, GENERATORS, MUD PUMPS, ALL ELECTRIC LINES, ALL HYDROLIC LINES, PREPAIR PITS FOR MUD IN STORAGE,BUILD FLAIR.
17:00	19:00	02:00	NIPPLE UP, HYDROLIC LINES, FAST CONNECT STACK,FLOW LINE, MUD BUSTER LINE.
19:00	00:30	05:30	RIG UP TESTER (WALKER TESTING) TEST BOP - PIPE RAMS, BLIND RAMS, CHOKE LINE & CHOKE VALVES, FOSV, INSIDE BOP, KILL LINE AND VALVES, CHOKE LINE, CHOKE MANIFOLD & VALVES, HCR & MANUAL VALVE ALL @ 10 MIN 250 PSI LOW 10 MIN 3000 PSI HIGH - ANNULAR @ 10 MIN 1500 PSI HIGH 10 MIN 250 PSI LOW - CASING @ 30 MIN 1500 PSI - ACCUMULATOR FUNCTION TEST, RIG DOWN TESTER.
			WINTERIZE CHOKE
00:30	03:00	02:30	LOAD, STRAP, P/U AND ORIENT BHA.
03:00	04:00	01:00	RIH AND TAG CEMENT @ 868'.
04:00	06:00	02:00	CLEAN OUT CEMENT F/868' T/1043'.90 SPM, 315 GPM, 988 SPP, 10K WOB, 40 RPM.
05:55	05:55	00:00	SAFETY MEETING DAYS:PPE, SWA. RIG UP AND NIPPLE UP.
			SAFETY MEETING NIGHTS: PPE,SWA.TEST BOPE AND P/U BHA.
			REGULATORY VISITS: NONE.
			INCIDENTS: NONE.
			SAFETY DRILLS: NONE
			REGULATORY NOTICES: NONE.
			DAYLIGHT: 5 CREW MEMBERS
			NIGHTS: 4 CREW MEMEBERS

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	350.0			2,660.0	1,850.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours	3.00				3.00
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12	0.663	1,043		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/146	445	1,800	2.12	0.00	0		0.00	0	

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6296	7/8	1,043		11/10/2014			

MUD MOTOR OPERATIONS:									
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
1	25	0.33	2.00	0	0.00	2.00	0	0.00	

SURVEYS									
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
11/10/2014	3,604	17.9	293.83	3,514	617.0	271.22	-554.15	0.6	MWD Survey Tool
11/10/2014	3,513	17.5	292.73	3,428	589.3	260.29	-528.74	0.6	MWD Survey Tool
11/10/2014	3,423	17.0	293.54	3,342	562.6	249.80	-504.19	0.8	MWD Survey Tool

MUD PROPERTIES											
Type	LSND	Mud Wt	9.0	Alk.	3.0	Sand %	0.0	XS Lime lb/bbl			
Temp.	60	Gels 10sec	5	Cl ppm	1,700	Solids %	7.0	Salt bbls			
Visc	37	Gels 10min	8	Ca ppm	10	LGS %	4.0	LCM ppb			
PV	9	pH	9.0	pF	1.0	Oil %		API WL cc	10.4		
YP	9	Filter Cake/32	1	Mf	6.0	Water %	93.0	HTHP WL cc			
O/W Ratio		ES		WPS							
Comments:	MEGA CIDE-2, TRAILER-1, ENGINEERING-1.										

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION													
Pump 1 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>125</u>	PSI	<u>1,710</u>	GPM	<u>440</u>	SPR	<u>43</u>	Slow PSI	<u>0</u>
Pump 2 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>      </u>	PSI	<u>      </u>	GPM	<u>      </u>	SPR	<u>      </u>	Slow PSI	<u>      </u>
Pump 32 Liner	<u>      </u>	Stroke Len	<u>      </u>	SPM	<u>      </u>	PSI	<u>      </u>	GPM	<u>      </u>	SPR	<u>      </u>	Slow PSI	<u>      </u>
BHA Makeup	STEARABLE												
Up Weight	<u>0</u>	Dn Weight	<u>0</u>	RT Weight	<u>0</u>			Length	<u>885.6</u>			Hours on BHA	<u>0</u>
								Torque	<u>0</u>			Hours on Motor	<u>0</u>

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		26803	ULTERRA U616S 6X12
2	MUD MOTOR	6.500	0.000	26.72		6296	1.5 DEG FBH 7/8 4.8STG. .33REV
3	NON MAG MONEL	6.063	2.875	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.313	2.813	3.80		GSB0401	4.5 XH P x B
5	NON MAG FLEX MONEL	6.000	2.750	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.750	29.45		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.750	548.65		RIG	4.5 XH P x B
8	DRILLING JARS	6.375	2.250	32.00		71620G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
9	6JTS HWDP	4.500	2.750	182.79		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	2,466	5,507	7,500
8100..320: Mud & Chemicals	1,097	1,097	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,515	68,700	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob	2,607	2,607	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/	2,900	2,900	5,000	8100..520: Trucking & Hauling	2,670	3,405	10,000
8100..530: Equipment Rental	3,290	6,601	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	850	7,000	8100..535: Directional Drillin	11,395	16,395	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	9,600	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	5,628	14,902		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing			94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	56,793	215,221	717,000



ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/11/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979	SPUD DATE	11/10/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122		
TD AT REPORT	3,980'	FOOTAGE	2,937'	PRATE	130.5	CUM. DRLG. HRS	40.0	DRLG DAYS SINCE SPUD	1
ANTICIPATED TD	7,176'	PRESENT OPS	Directional Drilling at 3,980'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	DH:		CUM. MUD LOSS	SURF:	DH:			
MUD COMPANY:	ANCHOR			MUD ENGINEER:	DAN KASTEL				
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	7,156	SSE	0	SSED	0

TIME BREAKDOWN									
DIRECTIONAL DRILLING	22.50	OTHER	1.00	RIG SERVICE	0.50				

DETAILS				
Start	End	Hrs		
06:00	13:00	07:00	DIRECTIONAL DRILLING FROM 1043' TO 2198' (1155') 165 FT/HR GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=1850 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.4+, VIS 43	
13:00	13:30	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, ROUGHNECK, PILLAR BLOCKS, AND CATWALK - CHECK OIL LEVEL IN ALL PUMPS AND MOTORS	
13:30	18:00	04:30	DIRECTIONAL DRILLING FROM 2198' TO 3014' (816') 181 FT/HR GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=1850 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.4+, VIS 43	
18:00	00:00	06:00	DIRECTIONAL DRILLING FROM 3014' TO 3606' (592') 98.6 FT/HR GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=1850 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.4+, VIS 43	
00:00	01:00	01:00	DOWN LINK MWD AND SERVICE RIG. CHECK FOR LEAKS ON TOP DRIVE AND PIPE HANDLER.	
01:00	06:00	05:00	DIRECTIONAL DRILLING FROM 3606' TO 3980' (374')62 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43	
05:55	05:55	00:00	NO SIGNIFIANT MUD LOSS. SAFETY MEETING DAYS:PPE, SWA. TEAM WORK. SAFETY MEETING NIGHTS: PPE,SWA. DRILLING AND HOUSE KEEPING. REGULATORY VISITS: BLM. INCIDENTS: NONE. SAFETY DRILLS: BOPE DRILL DAYS AND NIGHTS. REGULATORY NOTICES: NONE. DAYLIGHT: 5 CREW MEMEBERS NIGHTS: 4 CREW MEMEBERS	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE						
Fluid	Used	Received	Transferred	On Hand	Cum.Used	
Fuel	1,470.0			1,190.0	3,320.0	
Gas						
Fresh Well Water						
Nano Water						
Frac Water						
Reserve Pit Water						
Boiler Hours	8.00				11.00	
Air Heater Hours						
Urea				0.0		
Urea Sys 1 Hrs						
Urea Sys 2 Hrs						
Urea Sys 3 Hrs						

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12/12	0.663	1,043		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/146	445	1,800	2.12	22.50	2,937	130.53	22.50	2,937	130.53

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6296	7/8	1,043		11/10/2014			

MUD MOTOR OPERATIONS:										
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP		
1	28	0.33	22.50	2,937	130.53	24.50	2,937	119.88		

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	
11/11/2014	4,781	7.6	303.92	4,657	891.2	381.48	-805.40	1.1	MWD Survey Tool	
11/11/2014	4,691	8.4	308.24	4,567	878.9	374.09	-795.29	1.1	MWD Survey Tool	
11/11/2014	4,600	9.0	302.73	4,477	865.3	366.12	-784.08	2.0	MWD Survey Tool	

MUD PROPERTIES													
Type	LSND	Mud Wt	9.5	Alk.	4.0	Sand %	0.0	XS Lime lb/bbl					
Temp.	90	Gels 10sec	4	Cl ppm	1,800	Solids %	6.0	Salt bbls					
Visc	45	Gels 10min	10	Ca ppm	10	LGS %	4.0	LCM ppb					
PV	12	pH	11.2	pF	1.0	Oil %		API WL cc	10.0				
YP	6	Filter Cake/32	2	Mf	2.0	Water %	94.0	HTHP WL cc					
O/W Ratio		ES		WPS									
Comments:	ANCO-BAR 40,DRILL PAC HV 3,HI-YIELD GEL 35,MICA 40,PHPA 3,FLOWZAN 2,SODIUM BICARB 4,WALNUT 15,PALLETS AND SHRINK WRAP 6,TRAILER-1, ENGINEERING-1.												

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION													
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,000	GPM	440	SPR	43	Slow PSI	0
Pump 2 Liner	6.5	Stroke Len	9.0	SPM		PSI		GPM		SPR	43	Slow PSI	307
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR		Slow PSI	
BHA Makeup	STEARABLE												
Up Weight	105,000	Dn Weight	82,000	RT Weight	93,000			Length	885.6			Hours on BHA	23
								Torque	6,500			Hours on Motor	23

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		26803	ULTERRA U616S 6X12
2	MUD MOTOR	6.500	0.000	26.72		6296	1.5 DEG FBH 7/8 4.8STG. .33REV
3	NON MAG MONEL	6.063	2.875	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.313	2.813	3.80		GSB0401	4.5 XH P x B
5	NON MAG FLEX MONEL	6.000	2.750	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.750	29.45		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.750	548.65		RIG	4.5 XH P x B
8	DRILLING JARS	6.375	2.250	32.00		71620G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
9	6JTS HWDP	4.500	2.750	182.79		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		5,507	7,500
8100..320: Mud & Chemicals	4,448	5,545	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,665	88,365	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel			40,000	8100..410: Mob/Demob		2,607	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling		3,405	10,000
8100..530: Equipment Rental	3,260	9,861	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	1,275	7,000	8100..535: Directional Drillin	8,150	24,545	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	14,400	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	4,482	19,384		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing	103,637	103,637	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	148,867	364,088	717,000

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/12/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979		SPUD DATE	11/10/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196		CONTRACTOR	Ensign 122		
TD AT REPORT	5,175'	FOOTAGE	1,195'	PRATE	50.9	CUM. DRLG. HRS	63.5	DRLG DAYS SINCE SPUD	2	
ANTICIPATED TD	7,176'	PRESENT OPS	Directional Drilling at 5,175'			GEOLOGIC SECT.				
DAILY MUD LOSS	SURF:	DH:	100	CUM. MUD LOSS	SURF:	DH:	100			
MUD COMPANY:	ANCHOR			MUD ENGINEER:		DAN KASTEL				
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		7,156	SSE	0	SSED	0

TIME BREAKDOWN		
DIRECTIONAL DRILLING	23.50	RIG SERVICE 0.50

DETAILS				
Start	End	Hrs		
06:00	14:00	08:00	DIRECTIONAL DRILLING FROM 3980' TO 4508' (528')66 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43.	
14:00	14:30	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, ROUGHNECK, PILLAR BLOCKS, AND CATWALK - CHECK OIL LEVEL IN ALL PUMPS AND MOTORS	
14:30	18:00	03:30	DIRECTIONAL DRILLING FROM 4508' TO 4695' (187')62 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43	
18:00	00:00	06:00	WE HAVE LOSS A TOTAL OF 100 BBLs AS OD 17:00 HRS. DIRECTIONAL DRILLING FROM 4695' to 4881' (186')62 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43	
00:00	06:00	06:00	NO SIGNIFIANT MUD LOSS. DIRECTIONAL DRILLING FROM 4881' TO 5175' (294')49 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43	
05:55	05:55	00:00	NO SIGNIFIANT MUD LOSS. SAFETY MEETING DAYS:PPE, SWA. DAILY ROUTINE. SAFETY MEETING NIGHTS: PPE,SWA. STAYING ALERT REGULATORY VISITS: NONE INCIDENTS: NONE. SAFETY DRILLS:NONE REGULATORY NOTICES: NONE. DAYLIGHT: 5 CREW MEMBERS NIGHTS: 5CREW MEMEBERS	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,880.0	3,000.0		2,310.0	5,200.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours	10.00				21.00
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12/12	0.663	1,043		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/146	445	1,800	2.12	23.50	1,195	50.85	46.00	4,132	89.83

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6296	7/8	1,043		11/10/2014			

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
1	28	0.33	23.50	1,195	50.85	48.00	4,132	86.08			

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		
11/12/2014	6,049	2.5	170.75	5,922	923.0	372.02	-845.28	3.9	MWD Survey Tool		
11/12/2014	6,041	2.2	169.43	5,914	923.2	372.34	-845.34	0.5	MWD Survey Tool		
11/12/2014	5,959	2.3	180.05	5,832	924.8	375.54	-845.63	0.3	MWD Survey Tool		

MUD PROPERTIES											
Type	LSND	Mud Wt	9.5	Alk.	4.0	Sand %	0.0	XS Lime lb/bbl			
Temp.	115	Gels 10sec	2	Cl ppm	2,000	Solids %	7.0	Salt bbls			
Visc	42	Gels 10min	7	Ca ppm	10	LGS %	5.0	LCM ppb			
PV	15	pH	9.9	pF	2.0	Oil %		API WL cc	6.4		
YP	6	Filter Cake/32	1	Mf	4.5	Water %	93.0	HTHP WL cc			
O/W Ratio		ES		WPS							
Comments:	ANCO-BAR 20,DRILL PAC HV 3,POLY SWELL-2,SALT-2,HI-YIELD GEL 8,LIGNITE-4MICA 18,LIME-14,PHPA 4,SAW DUST-40,FLOWZAN 5,SODIUM BICARB 0,WALNUT 22,MEGA CIDE-3, PACK LV-1PALLETs AND SHRINK WRAP 0,TRAILER-1, ENGINEERING-1.										

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,000	GPM	440	SPR	43	Slow PSI	0
Pump 2 Liner	6.5	Stroke Len	9.0	SPM	_____	PSI	_____	GPM	_____	SPR	43	Slow PSI	372
Pump 32 Liner	_____	Stroke Len	_____	SPM	_____	PSI	_____	GPM	_____	SPR	_____	Slow PSI	_____
BHA Makeup STEARABLE										Length 885.6			Hours on BHA 46
Up Weight 125,000 Dn Weight 97,000 RT Weight 110,000										Torque 9,500			Hours on Motor 46

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		26803	ULTERRA U616S 6X12
2	MUD MOTOR	6.500	0.000	26.72		6296	1.5 DEG FBH 7/8 4.8STG. .33REV
3	NON MAG MONEL	6.063	2.875	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.313	2.813	3.80		GSB0401	4.5 XH P x B
5	NON MAG FLEX MONEL	6.000	2.750	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.750	29.45		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.750	548.65		RIG	4.5 XH P x B
8	DRILLING JARS	6.375	2.250	32.00		71620G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
9	6JTS HWDP	4.500	2.750	182.79		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamat				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Dispos	525	6,032	7,500
8100..320: Mud & Chemicals	5,992	11,537	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,725	108,090	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel	9,633	9,633	40,000	8100..410: Mob/Demob		2,607	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling		3,405	10,000
8100..530: Equipment Rental	3,260	13,121	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	1,700	7,000	8100..535: Directional Drillin	8,150	32,695	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	19,200	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	5,950	25,334		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing	1,578	105,215	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	60,038	424,126	717,000

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/13/2014

WELL NAME	THREE RIVERS FED 35-34-720				AFE#	140979		SPUD DATE	11/10/2014	
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN				PHONE#	713-948-9196		CONTRACTOR	Ensign 122	
TD AT REPORT	6,400'	FOOTAGE	1,225'	PRATE	52.1	CUM. DRLG. HRS	87.0	DRLG DAYS SINCE SPUD	3	
ANTICIPATED TD	7,176'	PRESENT OPS	Directional Drilling at 6,400'				GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	DH:	120	CUM. MUD LOSS	SURF:			DH:	220	
MUD COMPANY:	ANCHOR				MUD ENGINEER:			DAN KASTEL		
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	7,156	SSE	0	SSD	0	

TIME BREAKDOWN		
DIRECTIONAL DRILLING	23.50	RIG SERVICE 0.50

DETAILS				
Start	End	Hrs		
06:00	13:00	07:00	DIRECTIONAL DRILLING FROM 5175' TO 5550'(375')53 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43.	
13:00	13:30	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, ROUGHNECK, PILLAR BLOCKS, AND CATWALK - CHECK OIL LEVEL IN ALL PUMPS AND MOTORS	
13:30	18:00	04:30	DIRECTIONAL DRILLING FROM 5550' TO 5850' (300')66.6 ft/hr. GPM=440, TOP DRIVE RPM=60, MOTOR RPM=145, TOTAL RPM=205, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-15K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43	
18:00	00:00	06:00	WE HAVE LOST 220 BBLS AS OF 17:00 HRS TOTAL, WE ARE ADDING SAWDUST AND MICA AS A LSM. DIRECTIONAL DRILLING FROM 5850'TO 6119' (269')48.8 ft/hr. GPM=440, TOP DRIVE RPM=45, MOTOR RPM=145, TOTAL RPM=250, OFF BOTTOM PRESSURE=2000 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 44	
00:00	06:00	06:00	NO SIGNIFIANT MUD LOSS. DIRECTIONAL DRILLING FROM 6119'TO 6400' (281')46.8 ft/hr. GPM=440, TOP DRIVE RPM=30-45, MOTOR RPM=145, TOTAL RPM=250, OFF BOTTOM PRESSURE=2044 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43	
05:55	05:55	00:00	NO SIGNIFIANT MUD LOSS. SAFETY MEETING DAYS:PPE, SWA. WORKING IN COLD WEATHER. SAFETY MEETING NIGHTS: PPE,SWA. TEAM WORK, MIXING CHEMICALS. REGULATORY VISITS: NONE INCIDENTS: NONE. SAFETY DRILLS:NONE REGULATORY NOTICES: NONE. DAYLIGHT: 5 CREW MEMBERS NIGHTS: 5 CREW MEMEBERS	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,880.0	3,000.0		3,430.0	7,080.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours	12.00				33.00
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12	0.663	1,043		-----	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/146	445	2,301	2.17	23.50	1,225	52.13	69.50	5,357	77.08

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
1	6.500	HUNTING	ARROW	6296	7/8	1,043		11/10/2014			

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
1	28	0.33	23.50	1,225	52.13	71.50	5,357	74.92			

SURVEYS											
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type		
11/13/2014	6,683	2.3	170.04	6,555	907.2	345.30	-840.62	0.3	MWD Survey Tool		
11/13/2014	6,593	2.5	174.76	6,465	909.3	349.05	-841.11	0.3	MWD Survey Tool		
11/13/2014	6,502	2.3	169.43	6,374	911.4	352.84	-841.63	0.3	MWD Survey Tool		

MUD PROPERTIES											
Type	LSND	Mud Wt	9.6	Alk.	4.4	Sand %	0.0	XS Lime lb/bbl			
Temp.	110	Gels 10sec	3	Cl ppm	1,750	Solids %	7.0	Salt bbls			
Visc	44	Gels 10min	9	Ca ppm	20	LGS %	5.0	LCM ppb			
PV	16	pH	10.5	pF	1.5	Oil %		API WL cc	5.2		
YP	10	Filter Cake/32	1	Mf	4.4	Water %	93.0	HTHP WL cc			
O/W Ratio		ES		WPS							
Comments:	ANCO-BAR 52,DRILL PAC HV 6,CEDAR FIBER 2,SALT 3,HI-YIELD GEL 35,LIGNITE 4,MICA 14,LIME 10,PHPA 3,SAWDUST 185,FLOWZAN 6,SOLTEX 2,WALNUT 38,MEGA-CIDE 3,PAC LV 4,TRAILER-1, ENGINEERING-1.										

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION													
Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,000	GPM	440	SPR	43	Slow PSI	388
Pump 2 Liner	6.5	Stroke Len	9.0	SPM		PSI		GPM		SPR	43	Slow PSI	372
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR		Slow PSI	
BHA Makeup	STEARABLE							Length	885.6			Hours on BHA	70
Up Weight	145,000	Dn Weight	97,000	RT Weight	120,000			Torque	9,500			Hours on Motor	70

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		26803	ULTERRA U616S 6X12
2	MUD MOTOR	6.500	0.000	26.72		6296	1.5 DEG FBH 7/8 4.8STG. .33REV
3	NON MAG MONEL	6.063	2.875	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.313	2.813	3.80		GSB0401	4.5 XH P x B
5	NON MAG FLEX MONEL	6.000	2.750	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.750	29.45		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.750	548.65		RIG	4.5 XH P x B
8	DRILLING JARS	6.375	2.250	32.00		71620G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
9	6JTS HWDP	4.500	2.750	182.79		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	210	6,242	7,500
8100..320: Mud & Chemicals	7,653	19,190	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	19,785	127,875	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel	9,470	19,103	40,000	8100..410: Mob/Demob		2,607	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling		3,405	10,000
8100..530: Equipment Rental	3,260	16,381	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	2,125	7,000	8100..535: Directional Drillin	8,150	40,845	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	24,000	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	5,873	31,207		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing		105,215	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	59,626	483,752	717,000



ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/14/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979		SPUD DATE	11/10/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196		CONTRACTOR	Ensign 122		
TD AT REPORT	6,818'	FOOTAGE	418'	PRATE	27.9	CUM. DRLG. HRS	102.0	DRLG DAYS SINCE SPUD	4	
ANTICIPATED TD	7,176'	PRESENT OPS			Rig Repair at 6,818'		GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	0	DH:	0	CUM. MUD LOSS	SURF:	0	DH:	220	
MUD COMPANY:	ANCHOR			MUD ENGINEER:			SEAN LEHNEN			
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		7,135	SSE	0	SSED	0

TIME BREAKDOWN					
DIRECTIONAL DRILLING	15.00	RIG REPAIRS	2.50	RIG SERVICE	0.50
TRIPPING	6.00				

DETAILS			
Start	End	Hrs	
06:00	13:00	07:00	DIRECTIONAL DRILLING FROM 6400'TO 6637' (237')33.85 ft/hr. GPM=440, TOP DRIVE RPM=30-45, MOTOR RPM=145, TOTAL RPM=250, OFF BOTTOM PRESSURE=2044 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43 NO MUD LOSS.
13:00	13:30	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, ROUGHNECK, PILLAR BLOCKS, AND CATWALK - CHECK OIL LEVEL IN ALL PUMPS AND MOTORS
13:30	18:00	04:30	DIRECTIONAL DRILLING FROM 6637'TO 6766' (129')28.6 ft/hr. GPM=440, TOP DRIVE RPM=30-45, MOTOR RPM=145, TOTAL RPM=250, OFF BOTTOM PRESSURE=2044 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 43 NO MUD LOSS.
18:00	21:30	03:30	DIRECTIONAL DRILLING FROM 6766'TO 6821' (55')15.7 ft/hr. GPM=440, TOP DRIVE RPM=30-45, MOTOR RPM=145, TOTAL RPM=250, OFF BOTTOM PRESSURE=2044 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 44,LOST 40 BBL.
21:30	00:00	02:30	POOH F/ BIT AND MOTOR.
00:00	03:30	03:30	POOH F/ BIT AND MOTOR.
03:30	06:00	02:30	REPAIR IRON ROUGHNECK.
05:55	05:55	00:00	SAFETY MEETING DAYS:PPE, SWA. MAINTAINENCE. SAFETY MEETING NIGHTS: PPE,SWA. TRIPPING. REGULATORY VISITS: NONE INCIDENTS: NONE. SAFETY DRILLS:NONE REGULATORY NOTICES: NONE. DAYLIGHT: 5 CREW MEMBERS NIGHTS: 5 CREW MEMEBERS

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	2,100.0			1,330.0	9,180.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours	24.00				57.00
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:									
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12/12	0.663	1,043	6,818	2-2-BT-M-X-X-CT-BC

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
1		60/146	445	2,301	2.17	15.00	418	27.87	84.50	5,775	68.34

RECENT MUD MOTORS:									
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT
2	6.500	HUNTING	ARROW	6275	7/8 3	6,818		11/14/2014	
1	6.500	HUNTING	ARROW	6296	7/8	1,043	6,818	11/10/2014	11/14/2014

MUD MOTOR OPERATIONS:								
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
2	25	0.20	0.00	0		0.00	0	
1	28	0.33	15.00	418	27.87	86.50	5,775	66.76

SURVEYS									
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
11/13/2014	6,683	2.3	170.04	6,555	907.2	345.30	-840.62	0.3	MWD Survey Tool
11/13/2014	6,593	2.5	174.76	6,465	909.3	349.05	-841.11	0.3	MWD Survey Tool
11/13/2014	6,502	2.3	169.43	6,374	911.4	352.84	-841.63	0.3	MWD Survey Tool

MUD PROPERTIES									
Type	LSND	Mud Wt	9.6	Alk.	1.0	Sand %	0.0	XS Lime lb/bbl	
Temp.	115	Gels 10sec	3	Cl ppm	1,700	Solids %	8.0	Salt bbls	
Visc	46	Gels 10min	8	Ca ppm	40	LGS %	7.0	LCM ppb	
PV	11	pH	10.0	pF	0.6	Oil %		API WL cc	6.2
YP	9	Filter Cake/32	1	Mf	3.2	Water %	92.0	HTHP WL cc	
O/W Ratio		ES		WPS					
Comments:	ALUM STEARATE 1,ANCO BAR 32,DRILL PAC HV 2,SALT 2,HIGH YIELD GEL 8,LIGNITE 4,MICA 15,LIME 7,PHPA 2,SAWDUST 175,SOLTEX 38,WALNUT 68,PAC LV 5,TRAILER-1, ENGINEERING-1.								

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>125</u>	PSI	<u>2,000</u>	GPM	<u>440</u>	SPR	<u>43</u>	Slow PSI	<u>388</u>
Pump 2 Liner	<u>6.5</u>	Stroke Len	<u>9.0</u>	SPM	<u>      </u>	PSI	<u>      </u>	GPM	<u>      </u>	SPR	<u>43</u>	Slow PSI	<u>372</u>
Pump 32 Liner	<u>      </u>	Stroke Len	<u>      </u>	SPM	<u>      </u>	PSI	<u>      </u>	GPM	<u>      </u>	SPR	<u>      </u>	Slow PSI	<u>      </u>
BHA Makeup STEARABLE										Length			<u>885.6</u>
Up Weight <u>145,000</u> Dn Weight <u>97,000</u> RT Weight <u>120,000</u>										Torque			<u>9,500</u>
										Hours on BHA			<u>70</u>
										Hours on Motor			<u>70</u>

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		26803	ULTERRA U616S 6X12
2	MUD MOTOR	6.500	0.000	26.72		6296	1.5 DEG FBH 7/8 4.8STG.
							.33REV
3	NON MAG MONEL	6.063	2.875	31.53		ATM64-513	4.5 XH P x B
4	EM GAP SUB	6.313	2.813	3.80		GSB0401	4.5 XH P x B
5	NON MAG FLEX MONEL	6.000	2.750	29.61		9041	4.5 XH P x B
6	DRILL COLLAR	6.500	2.750	29.45		RIG	4.5 XH P x B
7	18JTS HWDP	4.500	2.750	548.65		RIG	4.5 XH P x B
8	DRILLING JARS	6.375	2.250	32.00		71620G	4.5 XH P x B(SMITH)HE JARS
							(RUN 2)
9	6JTS HWDP	4.500	2.750	182.79		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamat				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Dispos	405	6,647	7,500
8100..320: Mud & Chemicals	8,744	27,934	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	20,145	148,020	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel		19,103	40,000	8100..410: Mob/Demob	20,000	22,607	17,000
8100..420: Bits & Reamers			15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling	872	4,277	10,000
8100..530: Equipment Rental	3,260	19,641	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	2,550	7,000	8100..535: Directional Drillin	8,150	48,995	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	28,800	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	7,349	38,556		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing		105,215	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	74,150	557,902	717,000

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/15/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979		SPUD DATE	11/10/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196		CONTRACTOR	Ensign 122		
TD AT REPORT	7,150'	FOOTAGE	332'	PRATE	27.7	CUM. DRLG. HRS	114.0	DRLG DAYS SINCE SPUD	5	
ANTICIPATED TD	7,176'	PRESENT OPS		Circulate at 7,150'		GEOLOGIC SECT.				
DAILY MUD LOSS	SURF:	0	DH:	150	CUM. MUD LOSS	SURF:	0	DH:	370	
MUD COMPANY:	ANCHOR			MUD ENGINEER:		SEAN LEHNEN				
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		7,135	SSE	0	SSED	0

TIME BREAKDOWN					
COND MUD & CIRCULATE	1.00	DRILLING	12.00	TRIPPING	11.00

DETAILS				
Start	End	Hrs		
06:00	07:30	01:30	POOH, LAYDOWN MWD,MONELS, MUD MOTOR AND DRILL BIT.FUNCTION TEST BLIND RAMS AND PIPE RAMS.	
			NOTE:	
			THE BIT AND BHA HAD A LOT OF CLAY AROUND IT. THE BIT HAD TO BE CLEANED WITH A CHISEL.	
07:30	08:30	01:00	CLEAN FLOOR, STRAP NEW BHA.	
08:30	11:00	02:30	TRIP INTO 1250', CIRC AND REAM TO 1300, WE SAW A LOT OF SHALE ACROSS THE SHAKERS, HAD TO VIS UP FROM A 46 TO A 55 VIS TO HELP HOLD THE SHALE BACK.	
			CIRC AND BUILD VIS UP TO A 55 VIS, CIRC HOLE.	
11:00	12:00	01:00	TRIP IN THE HOLE.WE ARE STILL SEEING SOME SHALE WHEN WE CIRC THE HOLE.	
12:00	18:00	06:00	DRILLING FROM 6818'TO 6890' (72')28.8 ft/hr.	
18:00	20:30	02:30	GPM=440, TOP DRIVE RPM=30-45, MOTOR RPM=145, TOTAL RPM=250, OFF BOTTOM PRESSURE=2044 PSI, DIFF PRESSURE=200-500 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 55,LOST 150 BBL. BY-PASS SHAKERS AND MIX LCM 7%	
			DRILLING FROM 6890'TO 7012' (122') 34.8 ft/hr.	
20:30	00:00	03:30	GPM=350, TOP DRIVE RPM=30-45, MOTOR RPM=70, TOTAL RPM=250, OFF BOTTOM PRESSURE=1200 PSI, DIFF PRESSURE=100-200 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.5+, VIS 55, BY-PASS SHAKERS AND MIX LCM 7%	
			DRILLING FROM 7012' TO 7150'(TD) (138') 23 ft/hr.	
00:00	06:00	06:00	GPM=350, TOP DRIVE RPM=30-45, MOTOR RPM=70, TOTAL RPM=250, OFF BOTTOM PRESSURE=1200 PSI, DIFF PRESSURE=100-200 PSI, WOB=10-30K, TQ=7,500 FT/LBS, MUD WT 9.8, VIS 60,STILL BY-PASS SHAKERS AND LCM IS 7%	
			SAFETY MEETING DAYS:PPE, SWA. TRIPPING AND PINCH POINTS.	
05:55	05:55	00:00	SAFETY MEETING NIGHTS: PPE,SWA. TRIPPIING, FIRST DAY BACK FOCUS.	
			REGULATORY VISITS: NONE	
			INCIDENTS: NONE.	
			SAFETY DRILLS:NONE	
			REGULATORY NOTICES: INTENT TO RUN PRODUCTION CASING TO BLM AND STATE.	
			DAYLIGHT: 5 CREW MEMBERS	
			NIGHTS: 5 CREW MEMEBERS	

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE						
Fluid	Used	Received	Transferred	On Hand	Cum.Used	
Fuel	1,320.0	3,000.0		3,010.0	10,500.0	
Gas						
Fresh Well Water						
Nano Water						
Frac Water						
Reserve Pit Water						
Boiler Hours	24.00				81.00	
Air Heater Hours						
Urea				0.0		
Urea Sys 1 Hrs						
Urea Sys 2 Hrs						
Urea Sys 3 Hrs						

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:										
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R	
3	7.875		INSERT		20/20/20	0.920	7,150	7,150	-----	
2	7.875	SMITH	MDI616	JH6360	12/12/12/12/12/12	0.663	6,818	7,150	0-0-BT-M-X-X-CT-TD	
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12/12	0.663	1,043	6,818	2-2-BT-M-X-X-CT-BC	

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
3		70	445	1,519		2.00	0	0.00	2.00	0	0.00
2		40/88	440	2,300	2.14	12.00	332	27.67	12.00	332	27.67
1		60/146	445	2,301	2.17	15.00	418	27.87	84.50	5,775	68.34

RECENT MUD MOTORS:										
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT	
2	6.500	HUNTING	ARROW	6275	7/8 3	6,818	7,150	11/14/2014	11/15/2014	
1	6.500	HUNTING	ARROW	6296	7/8	1,043	6,818	11/10/2014	11/14/2014	

MUD MOTOR OPERATIONS:									
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP	
2	25	0.20	12.00	332	27.67	12.00	332	27.67	
1	28	0.33	15.00	418	27.87	86.50	5,775	66.76	

SURVEYS										
Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type	
11/15/2014	7,150	2.4	174.94	7,022	897.2	325.99	-838.75	0.0	Projected Survey Station	
11/15/2014	6,818	2.4	174.94	6,690	904.2	339.78	-839.97	0.0	Projected Survey Station	
11/15/2014	6,774	2.4	174.94	6,646	905.2	341.61	-840.14	0.2	MWD Survey Tool	

MUD PROPERTIES

Type	LSND	Mud Wt	9.7	Alk.	1.0	Sand %	0.0	XS Lime lb/bbl	
Temp.	96	Gels 10sec	7	Cl ppm	1,700	Solids %	8.0	Salt bbls	
Visc	54	Gels 10min	15	Ca ppm	50	LGS %	7.0	LCM ppb	
PV	17	pH	10.0	pF	0.0	Oil %		API WL cc	6.8
YP	15	Filter Cake/32	1	Mf	2.0	Water %	92.0	HTHP WL cc	
O/W Ratio		ES		WPS					
Comments:	ANCO BAR 40,SALT 3,HI YIELD GEL 52,LIGNITE 1,MICA 2,LIME 6,PHPA 1,SAWDUST 75,FLOWZAN 1,WALNUT 3,MEGA CIDE 3,PAC LV 2,TRAILER-1, ENGINEERING-1.								

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,450	GPM	444	SPR	43	Slow PSI	465
Pump 2 Liner	6.5	Stroke Len	9.0	SPM		PSI		GPM		SPR		Slow PSI	—
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR	60	Slow PSI	
BHA Makeup	STRAIT HOLE MOTOR								Length	885.5		Hours on BHA	96
Up Weight	140,000	Dn Weight	85,000	RT Weight	105,000			Torque	11,500			Hours on Motor	12

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00		JH6360	MDSI616
2	MUD MOTOR	6.500	0.000	31.26		6275	0 DEG FBH 7/8 3.0STG. .20REV
3	DRILL COLLARS	6.500	2.750	89.82		RIG	4.5 XH P x B
4	18JTS HWDP	4.500	2.750	548.77		RIG	4.5 XH P x B
5	DRILLING JARS	6.375	2.250	32.00		42259G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
6	6JTS HWDP	4.500	2.750	182.64		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	420	7,067	7,500
8100..320: Mud & Chemicals	3,480	31,414	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	20,145	168,165	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel	9,302	28,405	40,000	8100..410: Mob/Demob		22,607	17,000
8100..420: Bits & Reamers	14,438	14,438	15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling	495	4,772	10,000
8100..530: Equipment Rental	3,260	22,901	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	2,975	7,000	8100..535: Directional Drillin	4,500	53,495	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	33,600	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	6,740	45,296		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing		105,215	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	68,005	625,907	717,000

ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/16/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979	SPUD DATE	11/10/2014		
WELL SITE CONSULTANT	JOHN FREITAS/KING BROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122		
TD AT REPORT	7,150'	FOOTAGE	0'	PRATE	CUM. DRLG. HRS	114.0	DRLG DAYS SINCE SPUD	6	
ANTICIPATED TD	7,176'	PRESENT OPS	Logging at 7,150'			GEOLOGIC SECT.			
DAILY MUD LOSS	SURF:	0	DH:	230	CUM. MUD LOSS	SURF:	0	DH:	600
MUD COMPANY:	ANCHOR			MUD ENGINEER:				SEAN LEHNEN	
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH		7,136	SSE	SSED	

TIME BREAKDOWN							
COND MUD & CIRCULATE	3.00	TRIPPING	16.50	WASH & REAM	1.00		
WIRELINE	2.50	WORK BHA	1.00				

DETAILS			
Start	End	Hrs	
06:00	07:00	01:00	CIRC HOLE CLEAN, STILL BYPASSED.
07:00	08:00	01:00	CIRC OVER ONE SHAKER SCREEN, WE ARE NOT SEEING ANY OF THE SHALE ACROSS THE SHAKER.
08:00	13:00	05:00	PULL OUT OF THE HOLE, WE DIDN'T SEE ANY TIGHT SPOT AT 1300' UP TO THE SHOE, LAY DOWN BHA.
13:00	14:30	01:30	PJSM WITH HALLIBURTON, RIG UP LOGGERS, RUN IN THE HOLE TO 1316' AND OPENED THE CALIPER, PULLED UP TO 1220' AND WAS UNABLE TO COME UP ANY MORE, WE WHERE NOT ABLE TO GO DOWN, PULLED WITH 12,500 LINE TENSTION, PULLED FREE AND POOH AND LAYED DOWN LOGGING TOOLS.
14:30	15:30	01:00	PICK UP BHA.
15:30	18:00	02:30	RIH, WASHED BRIDGE F/1276' T/1350'.
18:00	21:00	03:00	CONT RIH T/7110',TAGGED FILL.
21:00	22:00	01:00	WASH AND REAM F/7110' T/7150'. OBSERVED LARGE SLOUGHING SHALE OVER SHAKERS.
22:00	23:00	01:00	PUMP HIGH VIS SWEEP TO SURFACE. LOST 63 BBLs WHILE CIRCULATING. ADDED FRESH LCM TO STABILIZE LOSSES. (40 SACKS SAW DUST)
23:00	00:00	01:00	POOH F/ LOGS. PUMP AND ROTATE F/7150 T/6300'.
00:00	02:30	02:30	POOH T/ 2000' AND SPOT VIGH VIS PILL (60 VIS- 30 BBL)
02:30	05:00	02:30	POOH AND L/D BHA. FUNCTION PIPE AND BLIND RAMS.
05:00	06:00	01:00	SAFETY MEETING AND R/U WIRELINE CREW.
05:55	05:55	00:00	SAFETY MEETING DAYS:PPE, SWA. TRIPPING AND PINCH POINTS.
			SAFETY MEETING NIGHTS: PPE,SWA. TRIPPIING.
			REGULATORY VISITS: NONE
			INCIDENTS: NONE.
			SAFETY DRILLS:BOPE DRILL DAYS AND NIGHTS.
			REGULATORY NOTICES: NONE.
			DAYLIGHT: 5 CREW MEMBERS
			NIGHTS: 5 CREW MEMEBERS

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE					
Fluid	Used	Received	Transferred	On Hand	Cum.Used
Fuel	1,230.0			1,780.0	11,730.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours	24.00				105.00
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

CASING EQUIPMENT  
RUN SHOE, FLOAT, 47 JOINTS OF 5.5" 17# N-80, MARKER N-80, 20 JOINTS OF 5.5" 17# J-55, MARKER J-55, RUN 115 JOINTS OF 5.5" 17# J-55, PUP JOINT, MANDRELL, LANDING JOINT, CASING SET AT 7135.31.CIRC AT 2000', CIRC AT 6000' BOTH CIRCULATIONS ARE TO GET THE THICK MUD THAT WE SPOTED FOR THE LOGGERS OUT OF THE HOLE BEFORE THE CEMENT JOB.45 CENTRALIZERS

CEMENT JOB SUMMARY  
SAFETY MEETING, LOAD PLUG, AND TIE-IN LINES. TEST LINES T/5000 PSI. THAW MUD LINE IN TANK FARM, MIX AND PUMP TUNED SPACER(50 BBLs). MIX AND PUMP 235 SACKS LEAD CEMENT W/1 LBM GRANULITE,.25 LBM POLY FLAKE,5LBM KOL SEAL @11.0 PPG(146 BBL). MIX AND PUMP 490 SACKS TAIL CEMENT W/2LBM KOL-SEAL,1LBM GRANULITE TR, .25 LBM POLY-FLAKE @14 PPG(118 BBL). DROP PLUG AND DISPLACE W/165 BBL FRESH WATER. BUMPED PLUG W/1560 PSI PRESSURE T/2080 PSI 5 MIN. BLEED BACK 1.5 BBLs FLOATS HELD. 35 BBL CEMENT TO SURFACE. R/D AND RELEASE.

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Production	11/16/2014	5 1/2	N-80	17	7,135		
Production	11/16/2014	5 1/2	J-55	17	5,081		
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:									
BIT	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
3	7.875		INSERT		20/20/20	0.920	7,150	7,150	-----
2	7.875	SMITH	MDI616	JH6360	12/12/12/12/12	0.663	6,818	7,150	0-0-BT-M-X-X-CT-TD
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12	0.663	1,043	6,818	2-2-BT-M-X-X-CT-BC

BIT OPERATIONS:											
BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
3		70	445	1,519		2.00	0	0.00	2.00	0	0.00
2		40/88	440	2,300	2.14	12.00	332	27.67	12.00	332	27.67
1		60/146	445	2,301	2.17	15.00	418	27.87	84.50	5,775	68.34

RECENT MUD MOTORS:											
#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT		
2	6.500	HUNTING	ARROW	6275	7/8 3	6,818	7,150	11/14/2014	11/15/2014		
1	6.500	HUNTING	ARROW	6296	7/8	1,043	6,818	11/10/2014	11/14/2014		

MUD MOTOR OPERATIONS:											
#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP			
2	25	0.20	12.00	332	27.67	12.00	332	27.67			
1	28	0.33	15.00	418	27.87	86.50	5,775	66.76			

SURVEYS

Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
11/15/2014	7,150	2.4	174.94	7,022	897.2	325.99	-838.75	0.0	Projected Survey Station
11/15/2014	6,818	2.4	174.94	6,690	904.2	339.78	-839.97	0.0	Projected Survey Station
11/15/2014	6,774	2.4	174.94	6,646	905.2	341.61	-840.14	0.2	MWD Survey Tool

MUD PROPERTIES

Type	LSND	Mud Wt	9.9	Alk.	1.0	Sand %	0.0	XS Lime lb/bbl	
Temp.	92	Gels 10sec	6	Cl ppm	1,900	Solids %	9.0	Salt bbls	
Visc	54	Gels 10min	18	Ca ppm	40	LGS %	6.0	LCM ppb	
PV	20	pH	10.4	pF	0.0	Oil %		API WL cc	6.8
YP	18	Filter Cake/32	1	Mf	2.0	Water %	91.0	HTHP WL cc	
O/W Ratio		ES		WPS					
Comments:	ANCO BAR 168,HI YIELD GEL 86,LIGNITE 3,MICA 13,LIME 8,PHPA 3,SAWDUST 100,WALNUT 16,MEGA CIDE 2ECO SEAL 6,,PAC LV 8,TRAILER-1, ENGINEERING-1.								

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,450	GPM	444	SPR	43	Slow PSI	465
Pump 2 Liner	6.5	Stroke Len	9.0	SPM		PSI		GPM		SPR		Slow PSI	
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR	60	Slow PSI	
BHA Makeup	DUMB IRON											Hours on BHA	3
Up Weight	140,000	Dn Weight	85,000	RT Weight	105,000			Length	857.2			Hours on Motor	3
								Torque	11,500				

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00			INSERT
2	BIT SUB	6.500	0.000	2.96			RIG
3	DRILL COLLARS	6.500	2.750	89.85		RIG	4.5 XH P x B
4	18JTS HWDP	4.500	2.750	548.77		RIG	4.5 XH P x B
5	DRILLING JARS	6.375	2.250	32.00		42259G	4.5 XH P x B(SMITH)HE JARS (RUN 2)
6	6JTS HWDP	4.500	2.750	182.64		RIG	4.5 XH P x B

DAILY COSTS

	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa		7,067	7,500
8100..320: Mud & Chemicals	6,846	38,260	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	20,145	188,310	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel		28,405	40,000	8100..410: Mob/Demob		22,607	17,000
8100..420: Bits & Reamers		14,438	15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling		4,772	10,000
8100..530: Equipment Rental	3,260	26,161	25,000	8100..531: Down Hole Motor Ren			1,500
8100..532: Solids Control Equi	425	3,400	7,000	8100..535: Directional Drillin	4,500	57,995	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work		18,931	25,000	8100..610: P & A			
8100..700: Logging - Openhole			15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	38,400	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	8,680	53,976		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing		105,215	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	48,656	674,563	717,000



ULTRA RESOURCES, INC.  
DAILY DRILLING REPORT DATE: 11/17/2014

WELL NAME	THREE RIVERS FED 35-34-720			AFE#	140979	SPUD DATE	11/10/2014	
WELL SITE CONSULTANT	JOHN FREITAS/ KING BROWN			PHONE#	713-948-9196	CONTRACTOR	Ensign 122	
TD AT REPORT	7,150'	FOOTAGE	0'	PRATE	CUM. DRLG. HRS	114.0	DRLG DAYS SINCE SPUD	7
ANTICIPATED TD	7,176'	PRESENT OPS	Rig release at 7,150'			GEOLOGIC SECT.		
DAILY MUD LOSS	SURF:	0	DH:	70	CUM. MUD LOSS	SURF:	0	DH: 670
MUD COMPANY:	ANCHOR			MUD ENGINEER:	SEAN LEHNEN			
LAST BOP TEST	11/10/2014	NEXT CASING SIZE	5 1/2	NEXT CASING DEPTH	7,136	SSE	0	SSED 0

TIME BREAKDOWN	CASING & CEMENT	12.00	NIPPLE DOWN B.O.P.	1.50	RIG SERVICE	0.50
	RIG UP / TEAR DOWN	6.00	WIRELINE	4.00		

DETAILS	Start	End	Hrs	
	06:00	10:00	04:00	RUN IN WIRELINE TOOLS,(LOGGERS DEPTH 7125') LINE SPEED DOWN 200 FPM. TOOLS- RELEASABLE WIRELINE CABLE HEAD,GAMMA TELEMTRY, DUEL SPACE NEUTRON, DNS DECENTRALIZER, SPECTRAL DENSITY TOOL,DENSITY INSITE PAD, ARRAY COMPENSATED TRUE RESISTIVITY INSTRUMENT SECTION, ARRAY COMPENSATED RESISTIVITY SONDE SECTION, ROLLER BOGIE.
	10:00	10:30	00:30	RIG SERVICE - GREASE WASH PIPE, PIPE ARM, ROUGHNECK, PILLAR BLOCKS, AND CATWALK - CHECK OIL LEVEL IN ALL PUMPS AND MOTORS
	10:30	19:00	08:30	RUN SHOE, FLOAT, 47 JOINTS OF 5.5" 17# N-80, MARKER N-80, 20 JOINTS OF 5.5" 17# J-55, MARKER J-55, RUN 115 JOINTS OF 5.5" 17# J-55, PUP JOINT, MANDRELL, LANDING JOINT, CASING SET AT 7135.31.CIRC AT 2000', CIRC AT 6000' BOTH CIRCULATIONS ARE TO GET THE THICK MUD THAT WE SPOTED FOR THE LOGGERS OUT OF THE HOLE BEFORE THE CEMENT JOB. CIRC AND R/U HALLIBURTON CEMENTERS.
	19:00	22:30	03:30	SAFETY MEETING, LOAD PLUG, AND TIE-IN LINES. TEST LINES T/5000 PSI. THAW MUD LINE IN TANK FARM, MIX AND PUMP TUNED SPACER(50 BBLs). MIX AND PUMP 235 SACKS LEAD CEMENT @11.0 PPG(146 BBL). MIX AND PUMP 490 SACKS TAIL CEMENT @14 PPG(118 BBL). DROP PLUG AND DISPLACE W/165 BBL FRESH WATER. BUMPED PLUG W/1560 PSI PRESSURE T/2080 PSI 5 MIN. BLEED BACK 1.5 BBLs FLOATS HELD. 35 BBL CEMENT TO SURFACE. R/D AND RELEASE.
	22:30	00:00	01:30	NIPPLE DOWN BOPE, CLEAN MUD TANKS.
	00:00	06:00	06:00	RIG DOWN AND CLEAN MUD TANKS. RELEASE RIG FROM THE FED 35-34-720 @ 0600 ON 11/17/2014
	05:55	05:55	00:00	SAFETY MEETING DAYS:PPE, SWA. RUNNING CASING. SAFETY MEETING NIGHTS: PPE,SWA. CEMENTING AND RIGGING DOWN. REGULATORY VISITS: NONE INCIDENTS: NONE. SAFETY DRILLS: NONE. REGULATORY NOTICES: NONE. DAYLIGHT: 5 CREW MEMBERS NIGHTS: 5 CREW MEMEBERS

AFE Days vs Depth:		AFE Cost Vs Depth:	
DWOP Days vs Depth:		# LL/BP Received Today:	

FUEL AND WATER USAGE	Used	Received	Transferred	On Hand	Cum.Used
Fluid					
Fuel	1,210.0	3,000.0	3,570.0	0.0	12,940.0
Gas					
Fresh Well Water					
Nano Water					
Frac Water					
Reserve Pit Water					
Boiler Hours	24.00				129.00
Air Heater Hours					
Urea				0.0	
Urea Sys 1 Hrs					
Urea Sys 2 Hrs					
Urea Sys 3 Hrs					

CEMENT JOB SUMMARY
SAFETY MEETING, LOAD PLUG, AND TIE-IN LINES. TEST LINES T/5000 PSI. THAW MUD LINE IN TANK FARM, MIX AND PUMP TUNED SPACER(50 BBLs). MIX AND PUMP 235 SACKS LEAD CEMENT W/1 LBM GRANULITE,.25 LBM POLY FLAKE,5LBM KOL SEAL @11.0 PPG(146 BBL). MIX AND PUMP 490 SACKS TAIL CEMENT W/2LBM KOL-SEAL,1LBM GRANULITE TR, .25 LBM POLY-FLAKE @14 PPG(118 BBL). DROP PLUG AND DISPLACE W/165 BBL FRESH WATER. BUMPED PLUG W/1560 PSI PRESSURE T/2080 PSI 5 MIN. BLEED BACK 1.5 BBLs FLOATS HELD. 35 BBL CEMENT TO SURFACE. R/D AND RELEASE.

RECENT CASINGS RUN:	Date Set	Size	Grade	Weight	Depth	FIT Depth	FIT ppg
Production	11/16/2014	5 1/2	N-80	17	7,135		
Production	11/16/2014	5 1/2	J-55	17	5,081		
Surface	09/03/2014	8 5/8	J-55	24	1,003		
Conductor	08/22/2014	16	ARJ-55	45	147		

RECENT BITS:	SIZE	MANUF	TYPE	SERIAL NO.	JETS	TFA	DEPTH IN	DEPTH OUT	I-O-D-L-B-G-O-R
BIT									
3	7.875		INSERT		20/20/20	0.920	7,150	7,150	-----
2	7.875	SMITH	MDI616	JH6360	12/12/12/12/12/12	0.663	6,818	7,150	0-0-BT-M-X-X-CT-TD
1	7.875	ULTERRA	U616S	26803	12/12/12/12/12/12	0.663	1,043	6,818	2-2-BT-M-X-X-CT-BC

BIT OPERATIONS:	BIT	WOB	RPM	GPM	PRESS	HHP	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
	3		70	445	1,519		2.00	0	0.00	2.00	0	0.00
	2		40/88	440	2,300	2.14	12.00	332	27.67	12.00	332	27.67
	1		60/146	445	2,301	2.17	15.00	418	27.87	84.50	5,775	68.34

RECENT MUD MOTORS:	#	SIZE	MANUF	TYPE	SERIAL NO.	LOBES	DEPTH IN	DEPTH OUT	DATE IN	DATE OUT
	2	6.500	HUNTING	ARROW	6275	7/8 3	6,818	7,150	11/14/2014	11/15/2014
	1	6.500	HUNTING	ARROW	6296	7/8	1,043	6,818	11/10/2014	11/14/2014

MUD MOTOR OPERATIONS:	#	WOB	REV/GAL	HRS	24hr DIST	24HR ROP	CUM HRS	CUM DIST	CUM ROP
	2	25	0.20	12.00	332	27.67	12.00	332	27.67
	1	28	0.33	15.00	418	27.87	86.50	5,775	66.76

SURVEYS	Date	TMD	Incl	Azimuth	TVD	VS	NS	EW	DLS	Tool Type
	11/15/2014	7,150	2.4	174.94	7,022	897.2	325.99	-838.75	0.0	Projected Survey Station
	11/15/2014	6,818	2.4	174.94	6,690	904.2	339.78	-839.97	0.0	Projected Survey Station
	11/15/2014	6,774	2.4	174.94	6,646	905.2	341.61	-840.14	0.2	MWD Survey Tool

MUD PROPERTIES

Type	LSND	Mud Wt	9.9	Alk.	0.5	Sand %	0.0	XS Lime lb/bbl	
Temp.	92	Gels 10sec	6	Cl ppm	1,900	Solids %	9.0	Salt bbls	
Visc	54	Gels 10min	18	Ca ppm	40	LGS %	6.0	LCM ppb	
PV	17	pH	10.4	pF	0.4	Oil %		API WL cc	6.8
YP	14	Filter Cake/32	1	Mf	1.7	Water %	91.0	HTHP WL cc	
O/W Ratio		ES		WPS					
Comments: BAR-40, SALT-1,DESCO-3,GEL-26,SAW DUST-50,MEGA CIDE-2,ECO SEAL-16,TRAILER-1, ENGINEERING-1.									

Flaring:	Flare Foot-Minutes	0	Flared MCF	0.0	Cum. Flared MCF	0.0
----------	--------------------	---	------------	-----	-----------------	-----

SURFACE PUMP/BHA INFORMATION

Pump 1 Liner	6.5	Stroke Len	9.0	SPM	125	PSI	2,450	GPM	444	SPR	43	Slow PSI	465
Pump 2 Liner	6.5	Stroke Len	9.0	SPM		PSI		GPM		SPR		Slow PSI	
Pump 32 Liner		Stroke Len		SPM		PSI		GPM		SPR	60	Slow PSI	
BHA Makeup	DUMB IRON							Length	857.2			Hours on BHA	3
Up Weight	140,000	Dn Weight	85,000	RT Weight	105,000			Torque	11,500			Hours on Motor	3

BHA MAKEUP:

#	Component	OD	ID	Length	Weight (ft/lb)	Serial Number	Description
1	DRILL BIT	7.875		1.00			INSERT
2	BIT SUB	6.500	0.000	2.96			RIG
3	DRILL COLLARS	6.500	2.750	89.85		RIG	4.5 XH P x B
4	18JTS HWDP	4.500	2.750	548.77		RIG	4.5 XH P x B
5	DRILLING JARS	6.375	2.250	32.00		42259G	4.5 XH P x B(SMITH)HE JARS
							(RUN 2)
6	6JTS HWDP	4.500	2.750	182.64		RIG	4.5 XH P x B

DAILY COSTS


	DAILY	CUM	AFE		DAILY	CUM	AFE
8100..100: Permits & Fees		14,117	4,500	8100..105: Insurance			2,000
8100..110: Staking & Surveying			1,500	8100..120: Surface Damages & R			
8100..200: Location Roads		32,524	50,000	8100..210: Reclamation			
8100..220: Secondary Reclamati				8100..230: Pit Solidification			5,000
8100..300: Water Well				8100..310: Water/Water Disposa	315	7,382	7,500
8100..320: Mud & Chemicals	2,475	40,735	45,000	8100..325: Oil Base Mud Diesel			
8100..400: Drilling Rig	20,145	208,455	127,000	8100..402: Drilling Rig Cleani			
8100..405: Rig Fuel	9,879	38,284	40,000	8100..410: Mob/Demob		22,607	17,000
8100..420: Bits & Reamers	6,000	20,438	15,500	8100..500: Roustabout Services			7,000
8100..510: Testing/Inspection/		2,900	5,000	8100..520: Trucking & Hauling		4,772	10,000
8100..530: Equipment Rental	3,260	29,421	25,000	8100..531: Down Hole Motor Ren	4,300	4,300	1,500
8100..532: Solids Control Equi	425	3,825	7,000	8100..535: Directional Drillin		57,995	76,000
8100..540: Fishing				8100..600: Surface Casing/Inte		17,086	20,000
8100..605: Cementing Work	39,287	58,218	25,000	8100..610: P & A			
8100..700: Logging - Openhole	29,270	29,270	15,000	8100..705: Logging - Mud			
8100..800: Supervision/Consult	4,800	43,200	25,000	8100..810: Engineering/Evaluat			
8100..900: Contingencies	12,499	66,475		8100..950: Administrative O/H			
8100..999: Non Operated IDC				8200..510: Testing/Inspection/			2,000
8200..520: Trucking & Hauling			7,000	8200..530: Equipment Rental			37,500
8200..605: Cementing Work			25,000	8210..600: Production Casing	3,780	108,995	94,000
8210..620: Wellhead/Casing Hea			20,000	Total Cost	136,435	810,998	717,000

43 047 53006  
35 78 20E

# WALKER INSPECTION, LLC

Inspector Dustin Richmond  
date 11-9-14  
rig Ensign 122  
well TR FED 35-34-720  
operator Ultra

TEST NO. \_\_\_\_\_  
TEST NO. \_\_\_\_\_  
TEST NO. \_\_\_\_\_  
TEST NO. \_\_\_\_\_



# WALKER INSPECTION, LLC

## Accumulator Function Test

Lease # TR FED 35-34-720 Operator Ultras  
Rig Name & # Ensign 122 Location W. 12th St. & 1st St. N. T. 20  
Inspector Dustin Redman Date 11-9-14

RECEIVED  
NOV 17 2014

DIV. OF OIL, GAS & MINING

TO CHECK THE USABLE FLUID STORED IN THE NITROGEN BOTTLES ON THE  
ACCUMULATOR (O.S.O. #2 section, III.A.2.c.i. or ii or iii)

1. Make sure all rams and annular are open and if applicable HCR is closed.
  2. Ensure accumulator is pumped up to working pressure! (Shut off all pumps)
  3. Open HCR Valve. (if applicable)
  4. Close annular.
  5. Close all pipe rams.
  6. Open one set of pipe rams to simulate closing the blind ram.
  7. If you have a 3 ram stack, open the annular to achieve the 50% safety factor for 5M and greater systems.
  8. Accumulator pressure should be 200 psi above the desired pre-charge pressure, (Accumulator working pressure {1500psi = 750 desired psi} { 2000 and 3000 psi = 1000 desired psi})
  9. Record the remaining pressure 1450 psi.
- If annular is closed, open it a this time and close the HCR.

TO CHECK THE PRECHARGE ON BOTTLES OR SPHERICAL (O.S.O. #2 section III.A.2.d)

1. The manifold pre-charge pressure should be above the desired pre-charge pressure, {1500 psi = 750 desired psi} {2000 and 3000 psi = 1000 desired psi} may need to use pumps to pressure back up.
2. With power to pump shut off open bleed line to the tank.
3. Watch and record where the pressure drops, (accumulator psi).

Record the pressure drop 900 psi.

If the pressure drops below the MINIMUM pre-charge, (Accumulator working pressure {1500 psi = 700 min.} {2000 and 3000psi = 1900psi min.}, each bottle shall be independently checked with a gauge and recharged with nitrogen to the desired pre-charge pressure. (Accumulator working pressure {1500psi = 750 desired psi} { 2000 and 3000 psi = 1000 desired psi}).

TO CHECK THE CAPACITY OF THE ACCUMULATOR PUMPS (O.S.O. #2 section III.A.2.f)


Shut the accumulator bottles or spherical, (isolate them from the pumps & manifold) open the bleed off valve to the tank, (manifold psi should go to 0 psi) close bleed valve.

1. Open the HCR valve, (if applicable).
2. Close annular.
3. With pumps only, time how long it takes to regain manifold pressure to 200 psi over desired pre-charge pressure! (Accumulator working pressure {1500psi = 750 desired psi} { 2000 and 3000 psi = 1000 desired psi}).
4. Record elapsed time 1 min 22 sec (2 minutes or less)  
Open bottles or spherical back up and turn pumps on.


8:37	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	1	Annular	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
9:04	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	2	Mud Saver, Pipe Rams, Inside Man. Kill & Choke	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
9:36	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	3	TIW, Dart, HCR, Check Valve	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
10:02	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	4	Inside Manifold Valves, Riser	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
10:30	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	5	Outside Manifold Valves	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
10:54	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	6	Super Choke	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
11:03	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	7	Blind Rams, Downstream Manifold Valves	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
11:43	AM <input checked="" type="checkbox"/> PM <input checked="" type="checkbox"/>	8	Casing	PASS <input checked="" type="checkbox"/> FAIL <input checked="" type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	9		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	10		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	11		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	12		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	13		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	14		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>
	AM <input type="checkbox"/> PM <input type="checkbox"/>	RETEST		PASS <input type="checkbox"/> FAIL <input type="checkbox"/>

Acc. Tank Size (inches) (                      W                      D                      L) 231=                      gal.

**WALKER INSPECTION, LLC**







1467

**WALKER INSPECTION, LLC.**  
**REBEL TESTING • EAGER BEAVER TESTERS**  
 WYOMING • COLORADO • NORTH DAKOTA

**Daily JSA/Observation Report**

OPERATOR: Ultra ResDATE: 11-9-2014LOCATION: TR F E D 35-34-720CONTRACTOR: Ensign 122EMPLOYEE NAME: Dustin Redmond☒ High Pressure TestingCOMMENTS: Safety procedures discussed  
and followed☒ Working Below Platform☒ Requires PPE☒ Overhead Work is Occurring☐ Fill in if: Confined Spaces are Involved☐ Fill in if: Set up of Containment☒ Using Rig Hoist to Lift Tools☐ Fill in if: Other: \_\_\_\_\_SIGNATURE: [Signature]DATE: 11-9-2014

WALKER INSPECTION, LLC. AND AFFILIATES

ATTENDANCE:

<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		
<u>[Signature]</u>		

**Observation Report**

EMPLOYEE REPORTING: Dustin Redmond SIGNATURE: [Signature]Was job set up and performed correctly and to best of companies ability? Y/NWas all safety equipment used correctly by all involved? Y/NAny incidents or near misses to report about WI? Y/NAny incidents or near misses to report in general? Y/NAny spills or environmental issues to report? Y/N

Basic Comments: \_\_\_\_\_

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> UTU-88623
<b>1. TYPE OF WELL</b> Oil Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> ULTRA RESOURCES INC		<b>7. UNIT or CA AGREEMENT NAME:</b>
<b>3. ADDRESS OF OPERATOR:</b> 304 Inverness Way South #295, Englewood, CO, 80112		<b>8. WELL NAME and NUMBER:</b> THREE RIVERS FED 35-34-720
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 1623 FSL 2492 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 35 Township: 07.0S Range: 20.0E Meridian: S		<b>9. API NUMBER:</b> 43047530060000
<b>PHONE NUMBER:</b> 303 645-9809 Ext		<b>9. FIELD and POOL or WILDCAT:</b> THREE RIVERS
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER	<input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION	<input type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: <b>12/20/2014</b>
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input checked="" type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION	OTHER: <input style="width: 100px;" type="text"/>		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.  
 First Production occurred on the TR35-34-720 on 12/20/2014.

Accepted by the  
 Utah Division of  
 Oil, Gas and Mining  
**FOR RECORD ONLY**  
 January 06, 2015

<b>NAME (PLEASE PRINT)</b> Jenna Anderson	<b>PHONE NUMBER</b> 303 645-9804	<b>TITLE</b> Permitting Assistant
<b>SIGNATURE</b> N/A	<b>DATE</b> 12/30/2014	

RECEIVED: Jan. 13, 2015

28b. Production - Interval C									
Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

28c. Production - Interval D									
Date First Produced	Test Date	Hours Tested	Test Production →	Oil BBL	Gas MCF	Water BBL	Oil Gravity Corr. API	Gas Gravity	Production Method
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate →	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio	Well Status	

29. Disposition of Gas(*Sold, used for fuel, vented, etc.*)  
USED ON LEASE

30. Summary of Porous Zones (Include Aquifers):				31. Formation (Log) Markers	
Show all important zones of porosity and contents thereof: Cored intervals and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures and recoveries.					
Formation	Top	Bottom	Descriptions, Contents, etc.	Name	Top Meas. Depth
				TOP GREEN RIVER MAHOGANY LOWER GREEN RIVER WASATCH	3126 4484 5325 7028

32. Additional remarks (include plugging procedure):  
Frac material used:27036 gal HC1 Acid , 572669 gal FR-66 Water,192100 gal DeltaFrac Fluid, 878834 lbs White Sand

33. Circle enclosed attachments:			
1. Electrical/Mechanical Logs (1 full set req'd.)	2. Geologic Report	3. DST Report	4. Directional Survey
5. Sundry Notice for plugging and cement verification	6. Core Analysis	7 Other:	

34. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records (see attached instructions):

**Electronic Submission #287884 Verified by the BLM Well Information System.  
For ULTRA PETROLEUM, sent to the Vernal**


Name(*please print*) MARIAH DAY Title SUBMITTING CONTACT

Signature \_\_\_\_\_ (Electronic Submission) Date 01/13/2015

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

**\*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\* ORIGINAL \*\***

**RECEIVED:** Jan. 13, 2015



THREE RIVERS FED 35-34-720

GL: 4,823.3, KB: 4,835.8

Sec 35, 7S, 20E

Uintah County, Utah

	Size	Weight	Grade	Depth	Sks/Cmt
Conductor	16	45	ARJ-55	147	
Surface	8 5/8	24	J-55	1003	675
Production	5 1/2	17	J-55	5081	725
Production	5 1/2	17	N-80	7135	725
Tubing	2.875	6.5	J-55	5375	
Cement Top				0	

STAGE	ZONE 1	ZONE 2	ZONE 3	ZONE 4	ZONE 5	ZONE 6	ZONE 7
1	7012-7014	6963-6964	6950-6951	6925-6926	6909-6910	6883-6884	6854-6855
2	6748-6750	6740-6741	6733-6734	6709-6710	6702-6703	6690-6691	6679-6680
3	6545-6546	6531-6533	6520-6521	6489-6490	6436-6437	6425-6426	6412-6413
4	6243-6244	6210-6211	6201-6202	6181-6182	6166-6167	6144-6145	6129-6130
5	5797-5799	5769-5770	5760-5761	5751-5752	5731-5732	5727-5728	5617-5618
6	5484-5485	5474-5475	5469-5470	5455-5456	5449-5450	5443-5444	5434-5435

Stage	Date	Av.Rate	Av.Press	Proppant	CleanFluid	Screenout
1	11/27/2014	58.7	2,104	141,600	3,040	N
2	12/12/2014	50.0	1,974	130,637	2,981	N
3	12/13/2014	49.0	2,906	169,217	3,438	N
4	12/13/2014	49.0	2,683	184,355	4,430	N
5	12/13/2014	51.0	2,690	123,457	2,562	N
6	12/13/2014	46.0	1,899	129,568	3,119	N
Totals:				878,834	19,570	

Actual Formation or Depth	Top	Sand Type	Amount
		Gross Sand Drilled	
		Gross Sand Logged	
		Net Sand	
		Net Pay	

Move In	Spud Date	TD Date	Rig Release	1st Prod	Full Sales	Workover	LOE
09/02/2014	11/10/2014	11/15/2014	11/17/2014	12/20/2014			

Tbg Date	Depth	OD	ID	Weight	Grade	Thread	# Joints	Coil
12/19/2014	5,371.000	2.875					176	N

Rod Num	Size	Grade	Length	Depth Set	Guided	Comments
1	30.000		0	30	N	POLISH ROD
4	0.500		25	55	N	PONY
1	0.250		25	80	N	PONY
51	0.875	MMS	1,275	1,355	Y	4 PER
25	0.875	MMS	625	1,980	Y	6 PER
106	0.750	MMS	2,650	4,630	Y	4 PER
29	1.000	MMS	725	5,355	Y	8 PER
1					N	PLUNGER
1					N	STANDING VALVE





# ULTRA RESOURCES, INC

Location: Three Rivers Slot: Three Rivers Fed 35-34-720 (1623' FSL &amp; 2492' FWL)

Field: UINTAH COUNTY Well: Three Rivers Fed 35-34-720

Facility: Sec.35-T7S-R20E Wellbore: Three Rivers Fed 35-34-720 PWB

Plot reference wellpath is Three Rivers Fed 35-34-720 PWB

True vertical depths are referenced to Ensign122 (RT)

Measured depths are referenced to Ensign122 (RT)

Ensign122 (RT) to Mean Sea Level: 4836.3 feet

Mean Sea Level to Mud line (At Slot: Three Rivers Fed 35-34-720 (1623' FSL &amp; 2492' FWL)): 0 feet

Coordinates are in feet referenced to Slot



Grid System: NAD83 / Lambert Utah SP, Central Zone (4302), US feet

North Reference: True north

Scale: True distance

Depths are in feet

Created by: aselliams on 10/20/15





## Actual Wellpath Report

Three Rivers Fed 35-34-720 AWP

Page 1 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 AWB
Facility	Sec.35-T7S-R20E		

### REPORT SETUP INFORMATION

Projection System	NAD83 / Lambert Utah SP, Central Zone (4302), US feet	Software System	WellArchitect® 3.0.0
North Reference	True	User	Ewilliams
Scale	0.999915	Report Generated	1/9/2015 at 10:30:48 AM
Convergence at slot	1.19° East	Database/Source file	WellArchitectDB/Three_Rivers_Fed_35-34-720_AWB.xml

### WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	309.74	2142.01	2161500.20	7233757.21	40°09'49.050"N	109°38'07.150"W
Facility Reference Pt			2159365.27	7233403.09	40°09'45.990"N	109°38'34.740"W
Field Reference Pt			2156630.96	7236613.42	40°10'18.270"N	109°39'09.100"W

### WELLPATH DATUM

Calculation method	Minimum curvature	Ensign122 (RT) to Facility Vertical Datum	4836.30ft
Horizontal Reference Pt	Slot	Ensign122 (RT) to Mean Sea Level	4836.30ft
Vertical Reference Pt	Ensign122 (RT)	Ensign122 (RT) to Mud Line at Slot (Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL))	4836.30ft
MD Reference Pt	Ensign122 (RT)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	291.24°



# Actual Wellpath Report

Three Rivers Fed 35-34-720 AWP

Page 2 of 5



## REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 AWB
Facility	Sec.35-T7S-R20E		

## WELLPATH DATA (75 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
0.00†	0.000	188.730	0.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
13.00	0.000	188.730	13.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
147.00	0.000	0.000	147.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1003.00	0.000	0.000	1003.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1043.00	0.000	0.000	1043.00	0.00	0.00	0.00	40°09'49.050"N	109°38'07.150"W	0.00	
1068.00	1.190	188.730	1068.00	-0.06	-0.26	-0.04	40°09'49.047"N	109°38'07.151"W	4.76	
1158.00	0.800	247.820	1157.99	0.20	-1.42	-0.76	40°09'49.036"N	109°38'07.160"W	1.15	
1249.00	2.210	290.740	1248.96	2.41	-1.04	-2.99	40°09'49.040"N	109°38'07.189"W	1.88	
1339.00	3.710	298.940	1338.83	7.03	0.99	-7.16	40°09'49.060"N	109°38'07.242"W	1.73	
1430.00	5.300	305.150	1429.55	14.03	4.83	-13.18	40°09'49.098"N	109°38'07.320"W	1.83	
1520.00	7.110	300.840	1519.02	23.56	10.08	-21.36	40°09'49.150"N	109°38'07.425"W	2.08	
1611.00	9.590	298.850	1609.05	36.63	16.63	-32.84	40°09'49.214"N	109°38'07.573"W	2.74	
1702.00	11.890	298.540	1698.45	53.44	24.76	-47.71	40°09'49.295"N	109°38'07.765"W	2.53	
1792.00	13.920	299.160	1786.17	73.36	34.47	-65.31	40°09'49.391"N	109°38'07.991"W	2.26	
1883.00	16.310	299.950	1874.01	96.84	46.18	-85.95	40°09'49.506"N	109°38'08.257"W	2.64	
1973.00	17.720	298.850	1960.07	122.91	59.10	-108.89	40°09'49.634"N	109°38'08.553"W	1.61	
2064.00	18.210	298.150	2046.64	150.75	72.49	-133.56	40°09'49.766"N	109°38'08.870"W	0.59	
2154.00	18.780	296.250	2131.99	179.14	85.54	-158.95	40°09'49.895"N	109°38'09.197"W	0.92	
2245.00	18.520	297.130	2218.21	208.11	98.60	-184.95	40°09'50.024"N	109°38'09.532"W	0.42	
2335.00	18.520	298.320	2303.55	236.51	111.90	-210.26	40°09'50.156"N	109°38'09.858"W	0.42	
2426.00	18.210	297.530	2389.92	264.99	125.33	-235.59	40°09'50.289"N	109°38'10.184"W	0.44	
2517.00	18.520	298.940	2476.28	293.44	138.90	-260.84	40°09'50.423"N	109°38'10.510"W	0.60	
2607.00	18.690	298.940	2561.58	321.90	152.79	-285.97	40°09'50.560"N	109°38'10.833"W	0.19	
2698.00	18.600	297.840	2647.80	350.76	166.62	-311.57	40°09'50.697"N	109°38'11.163"W	0.40	
2789.00	17.900	295.860	2734.22	379.12	179.50	-336.98	40°09'50.824"N	109°38'11.491"W	1.03	
2879.00	17.500	294.140	2819.96	406.42	191.07	-361.78	40°09'50.938"N	109°38'11.810"W	0.73	
2970.00	16.480	291.930	2906.99	432.99	201.49	-386.24	40°09'51.041"N	109°38'12.125"W	1.33	
3060.00	16.200	293.960	2993.36	458.30	211.35	-409.55	40°09'51.139"N	109°38'12.425"W	0.71	
3126.00†	16.110	292.078	3056.75	476.65	218.53	-426.45	40°09'51.210"N	109°38'12.643"W	0.81	Top Green River
3151.00	16.080	291.360	3080.77	483.58	221.10	-432.89	40°09'51.235"N	109°38'12.726"W	0.81	
3241.00	16.080	291.760	3167.25	508.51	230.26	-456.07	40°09'51.325"N	109°38'13.024"W	0.12	
3332.00	16.620	291.540	3254.57	534.13	239.71	-479.88	40°09'51.419"N	109°38'13.331"W	0.60	
3423.00	17.010	293.540	3341.68	560.44	249.80	-504.19	40°09'51.519"N	109°38'13.644"W	0.77	
3513.00	17.500	292.730	3427.63	587.12	260.29	-528.74	40°09'51.622"N	109°38'13.960"W	0.61	
3604.00	17.900	293.830	3514.32	614.77	271.23	-554.15	40°09'51.730"N	109°38'14.288"W	0.57	
3694.00	16.880	291.930	3600.21	641.65	281.69	-578.93	40°09'51.834"N	109°38'14.607"W	1.30	
3785.00	17.590	296.650	3687.13	668.55	292.80	-603.47	40°09'51.943"N	109°38'14.923"W	1.72	
3875.00	17.010	296.340	3773.05	695.20	304.74	-627.43	40°09'52.061"N	109°38'15.232"W	0.65	
3966.00	16.790	296.650	3860.12	721.55	316.54	-651.10	40°09'52.178"N	109°38'15.537"W	0.26	
4057.00	14.800	291.930	3947.69	746.26	326.78	-673.63	40°09'52.279"N	109°38'15.827"W	2.60	
4147.00	14.490	288.630	4034.76	769.00	334.67	-694.97	40°09'52.357"N	109°38'16.102"W	0.99	
4238.00	14.410	285.720	4122.89	791.64	341.37	-716.66	40°09'52.423"N	109°38'16.381"W	0.80	
4328.00	12.810	284.440	4210.36	812.70	346.89	-737.10	40°09'52.478"N	109°38'16.644"W	1.81	
4419.00	11.000	286.950	4299.40	831.38	351.94	-755.17	40°09'52.528"N	109°38'16.877"W	2.07	
4484.00†	10.678	294.900	4363.24	843.57	356.28	-766.57	40°09'52.571"N	109°38'17.024"W	2.35	Mahogany



# Actual Wellpath Report

Three Rivers Fed 35-34-720 AWP

Page 3 of 5



## REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 AWB
Facility	Sec.35-T7S-R20E		

## WELLPATH DATA (75 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Latitude	Longitude	DLS [°/100ft]	Comments
4509.00	10.610	298.060	4387.81	848.17	358.34	-770.70	40°09'52.591"N	109°38'17.077"W	2.35	
4600.00	9.010	302.730	4477.48	863.47	366.14	-784.09	40°09'52.668"N	109°38'17.250"W	1.96	
4691.00	8.400	308.240	4567.43	876.81	374.10	-795.31	40°09'52.747"N	109°38'17.394"W	1.13	
4781.00	7.600	303.920	4656.56	888.90	381.49	-805.41	40°09'52.820"N	109°38'17.524"W	1.11	
4872.00	7.510	308.020	4746.77	900.47	388.51	-815.09	40°09'52.889"N	109°38'17.649"W	0.60	
4962.00	6.100	298.000	4836.13	910.85	394.38	-823.94	40°09'52.947"N	109°38'17.763"W	2.04	
5053.00	4.290	294.230	4926.76	919.05	398.05	-831.32	40°09'52.983"N	109°38'17.858"W	2.02	
5144.00	3.180	276.640	5017.56	924.89	399.74	-836.93	40°09'53.000"N	109°38'17.930"W	1.74	
5234.00	2.300	263.820	5107.46	928.91	399.83	-841.20	40°09'53.001"N	109°38'17.985"W	1.19	
5325.00	1.680	229.840	5198.41	931.17	398.78	-844.04	40°09'52.991"N	109°38'18.022"W	1.43	Lower Green River
5342.00†	1.656	225.224	5215.40	931.39	398.44	-844.40	40°09'52.987"N	109°38'18.026"W	0.80	Top of Production
5416.00	1.680	204.720	5289.37	931.89	396.70	-845.61	40°09'52.970"N	109°38'18.042"W	0.80	
5506.00	1.810	182.820	5379.33	931.52	394.09	-846.24	40°09'52.944"N	109°38'18.050"W	0.75	
5597.00	2.120	173.260	5470.28	930.27	390.98	-846.11	40°09'52.914"N	109°38'18.048"W	0.49	
5687.00	2.300	180.360	5560.21	928.85	387.52	-845.92	40°09'52.879"N	109°38'18.046"W	0.36	
5778.00	2.780	181.150	5651.12	927.44	383.49	-845.98	40°09'52.839"N	109°38'18.047"W	0.53	
5868.00	2.500	174.450	5741.03	925.81	379.35	-845.83	40°09'52.799"N	109°38'18.045"W	0.46	
5959.00	2.300	180.050	5831.95	924.25	375.55	-845.64	40°09'52.761"N	109°38'18.042"W	0.34	
6041.00	2.210	169.430	5913.88	922.82	372.35	-845.36	40°09'52.729"N	109°38'18.039"W	0.52	
6049.00	2.520	170.750	5921.88	922.65	372.02	-845.30	40°09'52.726"N	109°38'18.038"W	3.93	
6230.00	2.520	170.350	6102.70	918.59	364.17	-843.99	40°09'52.649"N	109°38'18.021"W	0.01	
6321.00	2.390	166.250	6193.62	916.48	360.36	-843.21	40°09'52.611"N	109°38'18.011"W	0.24	
6412.00	2.520	168.630	6284.53	914.31	356.56	-842.36	40°09'52.573"N	109°38'18.000"W	0.18	
6502.00	2.300	169.430	6374.45	912.29	352.84	-841.64	40°09'52.537"N	109°38'17.991"W	0.25	
6593.00	2.520	174.760	6465.37	910.44	349.05	-841.12	40°09'52.499"N	109°38'17.984"W	0.34	
6683.00	2.300	170.040	6555.29	908.62	345.30	-840.63	40°09'52.462"N	109°38'17.978"W	0.33	
6774.00	2.390	174.940	6646.22	906.83	341.62	-840.15	40°09'52.426"N	109°38'17.972"W	0.24	
6818.00	2.390	174.940	6690.18	906.02	339.79	-839.98	40°09'52.408"N	109°38'17.969"W	0.00	End of Surveys
7028.00†	2.390	174.940	6900.00	902.14	331.06	-839.21	40°09'52.321"N	109°38'17.960"W	0.00	Wasatch
7150.00	2.390	174.940	7021.89	899.89	326.00	-838.76	40°09'52.271"N	109°38'17.954"W	0.00	Projection To Bit



# Actual Wellpath Report

Three Rivers Fed 35-34-720 AWP

Page 4 of 5



## REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 AWB
Facility	Sec.35-T7S-R20E		

## TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
Three Rivers Fed 35-34-720 Driller's Target Radius: 5' 2028' FNL & 1988' FWL		4968.00	403.20	-837.46	2160654.59	7234142.83	40°09'53.034"N	109°38'17.937"W	circle
Three Rivers Fed 35-34-720 Target On Plat Radius: 50' 1980' FSL & 1980' FWL		4968.00	355.20	-845.46	2160647.59	7234094.68	40°09'52.560"N	109°38'18.040"W	circle

WELLPATH COMPOSITION - Ref Wellbore: Three Rivers Fed 35-34-720 AWB					Ref Wellpath: Three Rivers Fed 35-34-720 AWP	
Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment		Wellbore	
13.00	147.00	Unknown Tool (Standard)	Conductor		Three Rivers Fed 35-34-720 AWB	
147.00	1003.00	Unknown Tool (Standard)	Surface		Three Rivers Fed 35-34-720 AWB	
1003.00	6818.00	MTC (Collar, post-2000) (Standard)	MWD		Three Rivers Fed 35-34-720 AWB	
6818.00	7150.00	Blind Drilling (std)	Projection to bit		Three Rivers Fed 35-34-720 AWB	



## Actual Wellpath Report

Three Rivers Fed 35-34-720 AWP

Page 5 of 5



### REFERENCE WELLPATH IDENTIFICATION

Operator	ULTRA RESOURCES, INC	Slot	Three Rivers Fed 35-34-720 (1623' FSL && 2492' FWL)
Area	Three Rivers	Well	Three Rivers Fed 35-34-720
Field	UINTAH COUNTY	Wellbore	Three Rivers Fed 35-34-720 AWB
Facility	Sec.35-T7S-R20E		

### WELLPATH COMMENTS

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Comment
3126.00	16.110	292.078	3056.75	Top Green River
4484.00	10.678	294.900	4363.24	Mahogany
5325.00	1.680	229.840	5198.41	Lower Green River
5342.00	1.656	225.224	5215.40	Top of Production
6818.00	2.390	174.940	6690.18	End of Surveys
7028.00	2.390	174.940	6900.00	Wasatch
7150.00	2.390	174.940	7021.89	Projeciton To Bit



ULTRA RESOURCES, INC.  
DAILY COMPLETION REPORT FOR 11/23/2014 TO 12/20/2014

Well Name	THREE RIVERS FED 35-34-720	Frac Planned	6
Location:	UINTAH County, UTAH(NWSE 35 7S 20E)	AFE#	140979
Total Depth Date:	11/15/2014 TD 7,150	Formation:	(Missing)
Production Casing:	Size 5 1/2 Wt 17 Grade J-55 Set At 5,081	GL:	KB: 4,836

Date: 11/23/2014			
Tubing:		OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD: 7,075
Supervisor:		Duncan	
Work Objective:		Logging	
Contractors:		CHS, R&R	
Completion Rig:		Casedhole Sol	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
0830-1200		MIRU CHS WLU, run 4.65" gauge ring fr/surface to 7075'. POH w/gauge ring. Run CBL/GR/CCL fr/7063' to surface. TOC @ 1910'. RDMO WLU.	
Costs (\$):		Daily: 4,400	Cum: 19,561
			AFE: 1,298,141

Date: 11/24/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Stringham/Duncan		
Work Objective:	Prep for frac work		
Contractors:	R&R, Cameron,Knight Oil Tools		
Completion Rig:	(Missing)	Supervisor Phone: 435-790-2326/435-828-1472	
Upcoming Activity:	Test casing & wellhead		
Activities			
0745-0800	HSM,JSA		
0800-0930	Cameron MIRU To Set Tubing Head		
0930-1430	HSM,JSA R&R, Knight Oil MIRU Set BOPE, Change Out Rams, Secure Well, And Rig Up Flow Lines To Flow Back Tanks.		
1430-1431	Run 8" Water Line & Set Live Load Manifold		
Costs (\$):	Daily: 9,887	Cum: 29,448	AFE: 1,298,141

Date: 11/25/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Duncan		
Work Objective:	Test casing & wellhead		
Contractors:	RBS, R&R		
Completion Rig:	(Missing)	Supervisor Phone: 435-828-1472	
Upcoming Activity:	Prep for frac work		
Activities			
0930-1030	MIRU RBS Test Unit, and test csg, WH, Flow back lines, and BOP to 4,250 psig, good test. RDMO Testers.		
Costs (\$):	Daily: 13,571	Cum: 43,018	AFE: 1,298,141

Date: 11/26/2014			
Tubing: OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075	
Supervisor: Duncan			
Work Objective: Perforating			
Contractors: Schlumberger, R&R			
Completion Rig: SLB		Supervisor Phone: 435-828-1472	
Upcoming Activity: Prep for frac work			
Activities			
0800-1600		Perforate stage 1 (6781'-7014').	
Costs (\$):	Daily: 631	Cum: 43,649	AFE: 1,298,141

Date: 11/27/2014				
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075	
Supervisor:	Stringham/Duncan			
Work Objective:	Perf, Frac, and Flowback		SSE: 2	
Contractors:	R&R,SLB-WL,HAL-FRAC			
Completion Rig:	HAL - Blue UT, SLB		Supervisor Phone: 435-790-2326/435-828-1472	
Upcoming Activity:	Perf, Frac, and Flowback			
Activities				
0600-0630	Pressure Test To 5100 PSI			
0630-0715	Safety Meeting-Review location hazards including ,WHD, WL crane operations, overhead objects, the use of land guides while backing. Review incident reporting of property damage, & personnel injuries. Slips trips and falls, Establish smoking area & Muster area.			
0730-0835	Frac Stage 1. SICP 1067 PSI			
0835-1030	Wait On TR_35-44-720			
1030-1245	Perforate Part Of Stage 2 (6702'-6750') Set 5.5" FTFP @ 6770'. Note: Shot Gun @ 6702' Lost All Weight But line Weight. POOH No Guns On.			
1245-0000	Call Denver Decision to Get Braided Line Truck To Fish Guns.Wait On Braided Line Truck.			
0000-1510	Wait On CTU To Fish Perforating Guns.			
Costs (\$):	Daily: 1,500	Cum: 45,149		AFE: 1,298,141

Date: 11/28/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD:	7,075
Supervisor:	Stringham/Duncan		
Work Objective:	Fishing	SSE:	2
Contractors:	R&R,SLB-WL,HAL-FRAC,IPS,ETS		
Completion Rig:	HAL - Blue UT, IPS CT 2", SLB	Supervisor Phone: 435-790-2326/435-828-1472	
Upcoming Activity:	Fishing		
Activities			
0000-1510	Wait On CTU To Fish Perforating Guns.		
1510-1530	CTU Arrive.Hold Safety Meeting-Review location hazards including ,WHD, WL crane operations, overhead objects, the use of land guides while backing. Review incident reporting of property damage, & personnel injuries. Slips trips and falls, Establish smoking area & Muster area.		
1530-1830	CTU Arrived with wrong size Lub. For Overshot to fit thru Call For Smaller Overshot.		
1830-1831	MIRU IPS CTU NU. lub. Fill coil with water. Install coil connect. Pull test to 25,000# & pressure test to 3000 psi. Break lubricator off 7-1/16" BOP. New ETS BHA as follows: Coil Connector, Bi-Directional jar, MHA Dual Check Valves, 3/4" Ball Seat (back pressure valve) Hydraulic Disconnect,2.875 OD Circulating Sub 2.375 PAC X 2.375 EUE, 2.875 OD Indexing Tool, 3.875 Overshot w/1 Extension,2.75 Basket Grapple, Flat Bottom Guide. Reconnect lubricator.		
2330-0000	Fill surface lines with water. Close valve to flowback tank and pressure test to 3000 psi. Bleed pressure back to 1000 psi. Open top ram, 200 psi.		
0000-0045	RIH with Jar,Indexing Tool, 3.875" Overshot,2.75" Basket Grapple And Flat Bottom Guide To Top Of Fish @ 6725'. (Coil depth 6735').		
Costs (\$):	Daily: 54,026	Cum: 99,175	AFE: 1,298,141

Date: 11/29/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Stringham/Duncan		
Work Objective:	Fishing		
Contractors:	R&R,IPS,ETS,Rheets		
Completion Rig:	IPS CT 2"	Supervisor Phone: 435-790-2326/435-828-1472	
Upcoming Activity:	Drill out plug		
Activities			
0000-0045	RIH with Jar,Indexing Tool, 3.875" Overshot,2.75" Basket Grapple And Flat Bottom Guide To Top Of Fish @ 6725'. (Coil depth 6735').		
0045-0050	Raise Pump Rate To 1.5 BPM Set Down Over Fish @ 6724' Seen A 150 PSI Increase Pull Up 10' Set Back Down to 6737' Pull Up 20' Set Back Down To 6737'.		
0050-0200	POOH Shut Bottom Rams SICP=(250 PSI). Bleed Off PSI. ND Stack. Have Fish On (Perforating Gun & Setting Tool).Secure Well Fill void in between rams with methanol.		
0200-0240	SLB Crew Break Perforating Guns Down.		
0240-0335	Rig Down Fishing BHA NU Stack Rig Down CTU, Move over to the TR_35-44-720.		
0335-1000	Wait On TR_35-44-720.		
1000-1100	Spot in and RU crane & coil tubing unit. NU. stack, and flow lines. Pick up injector head and NU. lub. Fill coil with water. Install coil connect. Pull test to 25,000# & pressure test to 3000 psi		
1100-1150	Using new BHA: (BI-Directional jar, MHA 3/4" Ball Seat(back pressure valve), motor and 5 blade 4.625" mill. Function test motor (1600 psi @ 1.5 bbl/min). NU lubricator to stack. Fill surface lines with water. Close valve to flowback tank and pressure test to 3000 psi. Bleed pressure back to 800 psi. Open top ram, 200 psi.		
1150-1235	RIH with mill and motor to plug @ 6770'. (Coil depth 6784').		
1235-1250	Drill plug. 120 psi.		
1250-1330	RIH to PBTD @ 7075'. Pump 20 bbl gel sweep, 10 bbl water spacer & 20 bbl gel sweep. (Coil PBTD @ 7113'). Make 500' short trip and retag PBTD. POOH @ 50 ft/min for 30 min and then continue POOH. Close Bottom ram, SICP 80 PSI.		
1330-1400	Swing over to the TR_35-44-720.		
1400-1430	Turn well over to flow testers, open well on 25/64 choke. IP 80 PSI. Fill void in between rams with methanol.		
Costs (\$):	Daily: 111,598	Cum: 210,773	AFE: 1,298,141

Date: 11/30/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Stringham/Duncan		
Work Objective:	Flow test well		SSE: 1
Contractors:	R&R,Rheets		
Completion Rig:	(Missing)		Supervisor Phone: 435-790-2326/435-828-1472
Upcoming Activity:	Turned over to Production Dept		
Costs (\$):	Daily: 18,008	Cum: 228,781	AFE: 1,298,141

Date: 12/01/2014			
Tubing: OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075	
Supervisor: Fletcher			
Work Objective: Waiting on crew			
Contractors: (Missing)			
Completion Rig: (Missing)		Supervisor Phone: 3036459812	
Upcoming Activity: Perf, Frac, and Flowback			
Costs (\$):	Daily: 857	Cum: 229,638	AFE: 1,298,141

Date: 12/09/2014			
Tubing:		OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD: 7,075
Supervisor:		(Missing)	
Work Objective:		(Nothing Recorded)	
Contractors:		(Missing)	
Completion Rig:		(Missing)	Supervisor Phone: (Missing)
Upcoming Activity:			
Costs (\$):	Daily:	3,600	Cum: 233,238 AFE: 1,298,141

Date: 12/10/2014			
Tubing:		OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD: 7,075
Supervisor:		Duncan	
Work Objective:		Perforating	
Contractors:		Willies, CHS	
Completion Rig:		Casedhole Sol	Supervisor Phone: 435-828-1472
Upcoming Activity:		Prep for frac work	
Activities			
1000-1115		MIRU Willies Hot Oil Serv., flush casing w/70 bbls of hot water.	
1115-1230		Perforate the remainder of Stage 2 (6702'-6750') Set 5.5" FTFP @ 6766'.	
Costs (\$):	Daily:	13,589	Cum: 246,827
			AFE: 1,298,141

Date: 12/12/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Hutchinson,Scott		
Work Objective:	Perf, Frac, and Flowback		SSE: 2
Contractors:	Hal-Frac,Hal-WL,R&R		
Completion Rig:	Hal, HAL RED T4	Supervisor Phone: 307-354-6007/307-350-8487	
Upcoming Activity:	Perf, Frac, and Flowback		
Activities			
0930-1300	Rig up HAL WL.		
1300-2000	Rig up frac equipment.		
2000-2010	Pressure test frac lines to 5000 psi.		
2010-2020	Review location hazards including production equipment & producing wells. Discuss slips, trips, & falls.		
	Review WHD operations, High Pressure pumping, FB, crane operations, chemical handling, MSDS sheets &		
	PPE requirements. Discuss traffic control & the use of land guides while backing. Review the reporting of		
	property damage, & personnel injuries. Establish smoking area & Muster area.		
2020-2045	Rig up chemical lines & jump start engine for accumulator.		
2045-2150	Frac stage 2.		
2150-2255	Perforate stage 3 (6293-6546) Set 5.5" FTFP @ 6566'.		
2255-0400	Wait to frac TR34-44-720.		
Costs (\$):	Daily: 19,217	Cum: 266,044	AFE: 1,298,141

Date: 12/13/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Hutchinson,Scott		
Work Objective:	Perf, Frac, and Flowback		SSE: 2
Contractors:	R&R,HAL-WL,HAL-FRAC		
Completion Rig:	Hal, HAL RED T4		Supervisor Phone: 307.354.6007/350.350.8487
Upcoming Activity:	Drill out plug		
Activities			
2255-0400	Wait to frac TR34-44-720.		
0400-0800	Wait on sand.		
0800-0920	Frac stage 3.		
0920-1020	Perforate stage 4 (6017-6244). Set 5.5" FTFP @ 6264'.		
1020-1120	Wait on TR_35-44-720.		
1120-1215	Change out chemical transport.		
1215-1340	Frac stage 4.		
1340-1425	Perforate stage 5 (5541-5799). Set 5.5" FTFP @ 5819'.		
1425-1530	Wait on TR_35-44-720.		
1530-1620	Wait on sand.		
1620-1710	Frac stage 5.		
1710-1800	Perforate stage 6 (5342-5485). Set 5.5" FTFP @ 5505'.		
1800-1850	Wait to off-load sand.		
1850-1955	Frac stage 6.		
1955-0100	SICP @ 1400 psi. - winterize rams & rig down vendors.		
Costs (\$):	Daily: 25,000	Cum: 291,044	AFE: 1,298,141

Date: 12/14/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"		PBTD: 7,075
Supervisor:	Stringham/Duncan		
Work Objective:	Drill out plug		SSE: 1
Contractors:	R&R,IPS,ETS,Rheets		
Completion Rig:	IPS CT 2"	Supervisor Phone: 435-790-2326/435-828-1472	
Upcoming Activity:	Flow test well		
Activities			
1955-0100	SICP @ 1400 psi. - winterize rams & rig down vendors.		
0100-0120	Safety Meeting-Review location hazards including ,WHD, WL crane operations, overhead objects, the use of land guides while backing. Review incident reporting of property damage, & personnel injuries. Slips trips and falls, Establish smoking area & Muster area.		
0120-0415	MIRU IPS CTU NU. lub. Fill coil with water. Install coil connector. Pull test to 25,000# & pressure test to 3000 psi. Break lubricator off 7-1/16" BOP. ETS BHA From TR_9-31-820 as follows: Coil Connector, Bi-Directional jar, MHA Dual Check Valves, 3/4" Ball Seat (back pressure valve) Hydraulic Disconnect, motor and New 5 blade 4.625" mill. Reconnect lubricator. Function test motor,(1600 psi @ 2.0 bbl/min). NU lubricator to stack. Fill surface lines with water. Close valve to flowback tank and pressure test to 3000 psi. Bleed pressure back to 1000 psi. Open top ram, 800 psi.		
0415-0500	RIH with mill and motor to plug @ 5505'. (Coil depth 5523').		
0500-0510	Drill plug. 750 PSI.		
0510-0515	Pump a 10 bbl gel sweep. RIH to plug @ 5189'. Tag sand at 5769', wash sand to plug. (Coil depth 5840').		
0515-0555	Drill plug. 700 psi.		
0555-0610	Pump a 10 bbl gel sweep. RIH to plug @ 6264'. Tag sand at 6234', wash sand to plug. (Coil depth 6275').		
0610-0620	Drill plug. 850 psi.		
0620-0650	Pump a 20 bbl gel sweep. RIH to plug @ 6566'. Tag sand at 6366', wash sand to plug. (Coil depth 6586').		
0650-0700	Drill plug. 850 psi.		
0700-0715	Pump a 10 bbl gel sweep. RIH to plug @ 6766'. (Coil depth 6788').		
0715-0725	Drill plug. 650 psi.		
0725-0910	RIH to PBTD @ 7075'. Pump 20 bbl gel sweep, 10 bbl water spacer & 20 bbl gel sweep. Coil PBTD @ 7120'. Make 500' short trip and retag PBTD. POOH @ 50 ft/min for 30 min and then continue POOH. Close Bottom ram, SICP 800#.		
0910-0930	ND swing over to the TR_35-44-720.		
0930-1020	Turn well over to flow testers, open well on 16/64 choke. IP 890 PSI. Note: Fill void in between rams with methanol.		
Costs (\$):	Daily: 55,960	Cum: 347,004	AFE: 1,298,141

Date: 12/15/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD:	7,075
Supervisor:	Stringham/Duncan		
Work Objective:	Flow test well		
Contractors:	R&R, Rhetts		
Completion Rig:	(Missing)	Supervisor Phone:	435-790-2326/435-828-1472
Upcoming Activity:	Flow test well		
Costs (\$):	Daily: 0	Cum: 347,004	AFE: 1,298,141

Date: 12/16/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD:	7,075
Supervisor:	Duncan		
Work Objective:	Flow test well		
Contractors:	R&R, Rhetts		
Completion Rig:	(Missing)	Supervisor Phone:	435-828-1472
Upcoming Activity:	Turned over to Production Dept		
Costs (\$):	Daily: 2,494	Cum: 349,499	AFE: 1,298,141

Date: 12/17/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD:	7,075
Supervisor:	Fletcher		
Work Objective:	Turned over to Production Dept		
Contractors:	(Missing)		
Completion Rig:	(Missing)	Supervisor Phone:	3036459812
Upcoming Activity:			
Costs (\$):	Daily: 19,797	Cum: 369,295	AFE: 1,298,141

Date: 12/18/2014			
Tubing:	OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD:	7,075
Supervisor:	(Missing)		
Work Objective:	(Nothing Recorded)		
Contractors:	(Missing)		
Completion Rig:	(Missing)	Supervisor Phone:	(Missing)
Upcoming Activity:			
Costs (\$):	Daily: 32,929	Cum: 402,225	AFE: 1,298,141

Date: 12/20/2014			
Tubing:		OD: 2.875" ID: Joints: 176" Depth Set: 5,375"	PBTD: 7,075
Supervisor:		JIM BURNS	
Work Objective:		TOH w/ tubing	
Contractors:		NONE LISTED	
Completion Rig:		Temple #3	Supervisor Phone: 4352992974
Upcoming Activity:		RDMO	
Activities			
0600-0700		CREW TRAVEL, SAFETY MEETING	
0700-1500		check pressures, 0 psi on tbg, 10 psi on csg.	
		pick up 1-4' tbg sub, hanger 1-6' tbg sub, land tbg. R/D floor N/D bop's, pull hanger set TAC W/ 10,000 lbs	
		stretch land tbg, N/U wellhead.	
		RIH W/ standing valve, plunger, 29-1" 8 per guided rods, 106-3/4" 4 per guided rods, 25-7/8" 6 per guided	
		rods, 50-7/8" 4 per guided rods, space out with 1-8' 1-6' 1-4' 1-2' ponys, pick up polish rod, fill tbg with 5 bbls	
		pressure up to 500 psi, long stroke pump to	
		800 psi (test good). Hang horses head, hang off rods. turn well to sales, rig down move off, shut down for	
		night.	
1500-1600		CREW TRAVEL	
Costs (\$):	Daily:	8,711	Cum: 410,936
			AFE: 1,298,141



ULTRA RESOURCES, INC.  
PERFORATION AND FRAC SUMMARY FOR THREE RIVERS FED 35-34-720

Well Name: THREE RIVERS FED 35-34-720			Fracs Planned: 6				
Location: UINTAH County, UTAH (NWSE 035 7S 20E)							
Stage 1		Frac Date: 11/27/2014		Avg Rate: 58.7 BPM		Avg Pressure: 2,104 PSI	
Initial Completion		Proppant: 141,600 lbs total		Max Rate: 62.5 BPM		Max Pressure: 3,583 PSI	
141600 lbs Ottawa							
Initial Annulus Pressure: 19		Final Annulus Pressure: 19		Pump Down Volume:			
PreFrac SICP:		ISIP: 1,067 PSI		Base BBLS to Recover: 3,040 BBLs			
Pseudo Frac Gradient: 0.585 PSI/FT		Pseudo Frac Gradient: 11.249 LB/GAL					
		Net Pressure: 201 psi		Total BBLS to Recover: 3,040 BBLs			
Breakdown Pressure: 2393		Breakdown Rate: 2393.0		Perfs Open:			
ScreenOut: No		Tracer: (None)					
Zones:	Perf Date	SPF	Perf Interval:		From	To	
12	11/26/2014	3			6,781	6,782	
11	11/26/2014	3			6,792	6,793	
10	11/26/2014	3			6,801	6,802	
9	11/26/2014	3			6,821	6,822	
8	11/26/2014	3			6,842	6,843	
7	11/26/2014	3			6,854	6,855	
6	11/26/2014	3			6,883	6,884	
5	11/26/2014	3			6,909	6,910	
4	11/26/2014	3			6,925	6,926	
3	11/26/2014	3			6,950	6,951	
2	11/26/2014	3			6,963	6,964	
1	11/26/2014	3			7,012	7,014	
Stage 2		Frac Date: 12/12/2014		Avg Rate: 50.0 BPM		Avg Pressure: 1,974 PSI	
Initial Completion		Proppant: 130,637 lbs total		Max Rate: 66.0 BPM		Max Pressure: 3,181 PSI	
130637 lbs Ottawa							
Initial Annulus Pressure: 0		Final Annulus Pressure: 0		Pump Down Volume:			
PreFrac SICP:		ISIP: 1,551 PSI		Base BBLS to Recover: 2,981 BBLs			
Pseudo Frac Gradient: 0.663 PSI/FT		Pseudo Frac Gradient: 12.742 LB/GAL					
		Net Pressure: 619 psi		Total BBLS to Recover: 2,981 BBLs			
Breakdown Pressure: 770		Breakdown Rate: 10.0		Perfs Open:			
ScreenOut: No		Tracer: (None)					
Zones:	Perf Date	SPF	Perf Interval:		From	To	
12	12/10/2014	3			6,598	6,599	
11	12/10/2014	3			6,608	6,609	
10	12/10/2014	3			6,628	6,629	
9	12/10/2014	3			6,645	6,646	
8	12/10/2014	3			6,663	6,664	
7	12/10/2014	3			6,679	6,680	
6	12/10/2014	3			6,690	6,691	
5	11/27/2014	3			6,702	6,703	
4	11/27/2014	3			6,709	6,710	
3	11/27/2014	3			6,733	6,734	
2	11/27/2014	3			6,740	6,741	
1	11/27/2014	3			6,748	6,750	
Stage 3		Frac Date: 12/13/2014		Avg Rate: 49.0 BPM		Avg Pressure: 2,906 PSI	
Initial Completion		Proppant: 169,217 lbs total		Max Rate: 61.0 BPM		Max Pressure: 4,388 PSI	
169217 lbs Ottawa							
Initial Annulus Pressure: 0		Final Annulus Pressure: 0		Pump Down Volume:			
PreFrac SICP:		ISIP: 1,606 PSI		Base BBLS to Recover: 3,438 BBLs			
Pseudo Frac Gradient: 0.678 PSI/FT		Pseudo Frac Gradient: 13.041 LB/GAL					
		Net Pressure: 537 psi		Total BBLS to Recover: 3,438 BBLs			
Breakdown Pressure: 1985		Breakdown Rate: 2.2		Perfs Open:			
ScreenOut: No		Tracer: (None)					
Zones:	Perf Date	SPF	Perf Interval:		From	To	
12	12/12/2014	3			6,293	6,294	
11	12/12/2014	3			6,301	6,302	
10	12/12/2014	3			6,330	6,331	
9	12/12/2014	3			6,388	6,389	
8	12/12/2014	3			6,400	6,401	
7	12/12/2014	3			6,412	6,413	
6	12/12/2014	3			6,425	6,426	
5	12/12/2014	3			6,436	6,437	
4	12/12/2014	3			6,489	6,490	
3	12/12/2014	3			6,520	6,521	
2	12/12/2014	3			6,531	6,533	
1	12/12/2014	3			6,545	6,546	



Stage 4	Frac Date: 12/13/2014	Avg Rate: 49.0 BPM	Avg Pressure: 2,683 PSI
Initial Completion	Proppant: 184,355 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,796 PSI
	184355 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,972 PSI	Base BBLS to Recover: 4,430 BBLs
	Pseudo Frac Gradient: 0.749 PSI/FT	Pseudo Frac Gradient: 14.396 LB/GAL	
		Net Pressure: 339 psi	Total BBLS to Recover: 4,430 BBLs
	Breakdown Pressure: 2918	Breakdown Rate: 4.0	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
13	12/13/2014	3	6,017 6,018
12	12/13/2014	3	6,046 6,047
11	12/13/2014	3	6,063 6,064
10	12/13/2014	3	6,076 6,077
9	12/13/2014	3	6,090 6,091
8	12/13/2014	3	6,111 6,112
7	12/13/2014	3	6,129 6,130
6	12/13/2014	3	6,144 6,145
5	12/13/2014	3	6,166 6,167
4	12/13/2014	3	6,181 6,182
3	12/13/2014	3	6,201 6,202
2	12/13/2014	3	6,210 6,211
1	12/13/2014	3	6,243 6,244
Stage 5	Frac Date: 12/13/2014	Avg Rate: 51.0 BPM	Avg Pressure: 2,690 PSI
Initial Completion	Proppant: 123,457 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,680 PSI
	123457 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,638 PSI	Base BBLS to Recover: 2,562 BBLs
	Pseudo Frac Gradient: 0.715 PSI/FT	Pseudo Frac Gradient: 13.755 LB/GAL	
		Net Pressure: -407 psi	Total BBLS to Recover: 2,562 BBLs
	Breakdown Pressure: 2649	Breakdown Rate: 3.6	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
11	12/13/2014	3	5,541 5,542
10	12/13/2014	3	5,572 5,573
9	12/13/2014	3	5,579 5,580
8	12/13/2014	3	5,606 5,607
7	12/13/2014	3	5,617 5,618
6	12/13/2014	3	5,727 5,728
5	12/13/2014	3	5,731 5,732
4	12/13/2014	3	5,751 5,752
3	12/13/2014	3	5,760 5,761
2	12/13/2014	3	5,769 5,770
1	12/13/2014	3	5,797 5,799
Stage 6	Frac Date: 12/13/2014	Avg Rate: 46.0 BPM	Avg Pressure: 1,899 PSI
Initial Completion	Proppant: 129,568 lbs total	Max Rate: 61.0 BPM	Max Pressure: 3,377 PSI
	129568 lbs Ottawa		
	Initial Annulus Pressure: 0	Final Annulus Pressure: 0	Pump Down Volume:
	PreFrac SICP:	ISIP: 1,423 PSI	Base BBLS to Recover: 3,119 BBLs
	Pseudo Frac Gradient: 0.692 PSI/FT	Pseudo Frac Gradient: 13.312 LB/GAL	
		Net Pressure: 126 psi	Total BBLS to Recover: 3,119 BBLs
	Breakdown Pressure: 1458	Breakdown Rate: 4.5	Perfs Open:
	ScreenOut: No	Tracer: (None)	
Zones:	Perf Date	SPF	Perf Interval: From To
13	12/13/2014	3	5,342 5,343
12	12/13/2014	3	5,349 5,350
11	12/13/2014	3	5,356 5,357
10	12/13/2014	3	5,381 5,382
9	12/13/2014	3	5,389 5,390
8	12/13/2014	3	5,408 5,409
7	12/13/2014	3	5,434 5,435
6	12/13/2014	3	5,443 5,444
5	12/13/2014	3	5,449 5,450
4	12/13/2014	3	5,455 5,456
3	12/13/2014	3	5,469 5,470
2	12/13/2014	3	5,474 5,475
1	12/13/2014	3	5,484 5,485

# Hydraulic Fracturing Fluid Product Component Information Disclosure

Job Start Date:	12/12/2014
Job End Date:	12/13/2014
State:	Utah
County:	Uintah
API Number:	43-047-53006-00-00
Operator Name:	Ultra Resources
Well Name and Number:	Three Rivers 35-34-720
Longitude:	-109.63531900
Latitude:	40.16362500
Datum:	NAD27
Federal/Tribal Well:	NO
True Vertical Depth:	7,500
Total Base Water Volume (gal):	694,074
Total Base Non Water Volume:	0



## Hydraulic Fracturing Fluid Composition:

Trade Name	Supplier	Purpose	Ingredients	Chemical Abstract Service Number (CAS #)	Maximum Ingredient Concentration in Additive (% by mass)**	Maximum Ingredient Concentration in HF Fluid (% by mass)**	Comments
Fresh Water	Operator	Base Fluid					
			Fresh Water	7732-18-5	100.00000	87.26807	Density = 8.330
SAND - PREMIUM WHITE	Halliburton	Proppant					
			Crystalline silica, quartz	14808-60-7	100.00000	11.52418	
HYDROCHLORIC ACID 10-30%	Halliburton	Solvent					
			Hydrochloric acid	7647-01-0	30.00000	0.16211	
LoSurf-300D	Halliburton	Non-ionic Surfactant					
			Ethanol	64-17-5	60.00000	0.04638	
			Heavy aromatic petroleum naphtha	64742-94-5	30.00000	0.02319	
			Poly(oxy-1,2-ethanediyl), alpha-(4-nonylphenyl)-omega-hydroxy-, branched	127087-87-0	5.00000	0.00386	
			Naphthalene	91-20-3	5.00000	0.00386	
			1,2,4 Trimethylbenzene	95-63-6	1.00000	0.00077	
WG-35 GELLING AGENT	Halliburton	Gelling Agent					
			Guar gum	9000-30-0	100.00000	0.06765	
BC-140	Halliburton	Crosslinker					
			Monoethanolamine borate	26038-87-9	60.00000	0.02980	

			Ethylene glycol	107-21-1	30.00000	0.01490	
SandWedge®	Halliburton	Conductivity Enhancer					
			Isopropanol	67-63-0	60.00000	0.02227	
			Heavy aromatic petroleum naphtha	64742-94-5	10.00000	0.00371	
			Methanol	67-56-1	5.00000	0.00186	
HYDROCHLORIC ACID 5-10%	Halliburton	Solvent					
			Hydrochloric acid	7647-01-0	10.00000	0.02702	
Cla-Web™	Halliburton	Additive					
			Ammonium salt	Confidential	60.00000	0.02671	Denise Tuck, Halliburton 3000 N. Sam Houston Pkwy E., Houston, TX 77032 281-871-6226
FE-1A ACIDIZING COMPOSITION	Halliburton	Additive					
			Acetic anhydride	108-24-7	100.00000	0.00812	
			Acetic acid	64-19-7	60.00000	0.00487	
FR-66	Halliburton	Friction Reducer					
			Hydrotreated light petroleum distillate	64742-47-8	30.00000	0.01140	
MC MX 2-2822	Multi-Chem	Scale Inhibitor					
			Methyl Alcohol	67-56-1	30.00000	0.00396	
			Phosphonate of a Diamine, Sodium Salt	Proprietary	30.00000	0.00396	
OPTIFLO-HTE	Halliburton	Breaker					
			Walnut hulls	Mixture	100.00000	0.00302	
			Crystalline silica, quartz	14808-60-7	30.00000	0.00091	
MC B-8614	Multi-Chem	Biocide					
			Acetone	67-64-1	40.00000	0.00222	
			Glutaraldehyde	111-30-8	30.00000	0.00167	
SP BREAKER	Halliburton	Breaker					
			Sodium persulfate	7775-27-1	100.00000	0.00225	
HAI-404M™	Halliburton	Corrosion Inhibitor					
			Isopropanol	67-63-0	30.00000	0.00045	
			Aldehyde	Confidential	30.00000	0.00045	
			Methanol	67-56-1	30.00000	0.00045	
			1-(Benzyl)quinolinium chloride	15619-48-4	10.00000	0.00015	
			Quaternary ammonium salt	Confidential	10.00000	0.00015	
Ingredients shown above are subject to 29 CFR 1910.1200(i) and appear on Material Safety Data Sheets (MSDS). Ingredients shown below are Non-MSDS.							
		Other Ingredient(s)					
			Water	7732-18-5		0.93544	
		Other Ingredient(s)					
			Oxyalkylated phenolic resin	Confidential		0.02319	
		Other Ingredient(s)					
			Fatty acid amine salt mixture	Confidential		0.02227	

		Other Ingredient(s)					
			Polyacrylamide copolymer	Confidential		0.01140	
		Other Ingredient(s)					
			Oxyalkylated phenolic resin	Confidential		0.00773	
		Other Ingredient(s)					
			Sodium chloride	7647-14-5		0.00413	
		Other Ingredient(s)					
			Quaternary ammonium compound	Confidential		0.00371	
		Other Ingredient(s)					
			Modified bentonite	Confidential		0.00338	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00223	
		Other Ingredient(s)					
			Alcohols, C12-16, ethoxylated	68551-12-2		0.00205	
		Other Ingredient(s)					
			Ammonium chloride	12125-02-9		0.00190	
		Other Ingredient(s)					
			Fatty acid tall oil amide	Confidential		0.00190	
		Other Ingredient(s)					
			Cured acrylic resin	Confidential		0.00091	
		Other Ingredient(s)					
			Ethoxylated nonylphenol	Confidential		0.00068	
		Other Ingredient(s)					
			Silica, amorphous - fumed	7631-86-9		0.00068	
		Other Ingredient(s)					
			Naphthenic acid ethoxylate	68410-62-8		0.00045	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00045	
		Other Ingredient(s)					
			Sorbitan monooleate polyoxyethylene derivative	9005-65-6		0.00038	
		Other Ingredient(s)					
			Sorbitan, mono-9-octadecenoate, (Z)	1338-43-8		0.00038	
		Other Ingredient(s)					
			Enzyme	Confidential		0.00015	
		Other Ingredient(s)					
			Fatty acids, tall oil	Confidential		0.00015	
		Other Ingredient(s)					
			Polyethoxylated fatty amine salt	61791-26-2		0.00015	
		Other Ingredient(s)					
			Ethoxylated amine	Confidential		0.00007	
		Other Ingredient(s)					
			Crystalline silica, quartz	14808-60-7		0.00007	
		Other Ingredient(s)					
			Quaternary amine	Confidential		0.00004	

		Other Ingredient(s)					
			Amine salts	Confidential		0.00004	
		Other Ingredient(s)					
			Amine salts	Confidential		0.00004	
		Other Ingredient(s)					
			Cured acrylic resin	Confidential		0.00003	
		Other Ingredient(s)					
			C.I. Pigment Red 5	6410-41-9		0.00003	
		Other Ingredient(s)					
			Methanol	67-56-1		0.00003	
		Other Ingredient(s)					
			Sodium iodide	7681-82-5		0.00001	
		Other Ingredient(s)					
			Ammonium phosphate	7722-76-1		0.00001	
		Other Ingredient(s)					
			Phosphoric Acid	7664-38-2		0.00000	
		Other Ingredient(s)					
			Sodium sulfate	7757-82-6		0.00000	

\* Total Water Volume sources may include fresh water, produced water, and/or recycled water

\*\* Information is based on the maximum potential for concentration and thus the total may be over 100%

Note: For Field Development Products (products that begin with FDP), MSDS level only information has been provided.

Ingredient information for chemicals subject to 29 CFR 1910.1200(i) and Appendix D are obtained from suppliers Material Safety Data Sheets (MSDS)

Company Ultra Petro Three Rivers 35-34-72 API 3-047-53006  
Formation 0 Zone #1 Temperature 174 °F  
Perfs 6781 - 70 Fluid System Frac 140 (13) Hybrid

Liquid Additives -----

Stage	Fluid	Fluid	Prop Conc	Prop	Slurry Vol	Slurry	Treating	Stage	Exposure	WG-36	LoSurf-300D	CLA-Web	B-8614	MX 2-2822	BC-140	Optiflo-HTE	SP Breaker	FR-76	SandWedge N	0	
		(gal)	(ppg)	(lbs)	(bbls)	(bpm)	(psi)	Pump Time	Time	Gel	Surfactant	Clay Control	Biocide	Scale Inh.	Crosslinker	Breaker	Breaker	Frict. Red.	Cond. Enh.	0	
1	oad & Brea	227			5.4	6.0	938	0:00:55	1:06:04	0.00	1.00	0.50	0.20	0.00	0.00	0.00	0.00	0.50	0	0.00	
2	5% HCl Ac	1000			23.8	8.3	1387	0:02:51	1:05:09	0.00	0.00	0.00	0.00	0.00	0.0	0.00	0.00	0.00	0	0.00	
3	Pad	6897			164.2	37.6	2635	0:04:22	1:02:18	0.00	1.00	0.50	0.20	0.83	0.00	0.00	0.00	0.50	0	0.00	
4	/gal 20/40 V	20357	0.50	10160	495.6	60.9	2506	0:08:09	0:57:56	0.00	1.00	0.50	0.20	0.83	0.00	0.00	0.00	0.50	0	0.00	
5	Pad	9574	0.00		228.0	57.1	2250	0:04:00	0:49:47	0.00	1.00	0.50	0.20	0.83	0.00	0.00	0.00	0.50	0	0.00	
6	/gal 20/40 V	20372	0.51	10480	496.3	57.4	2261	0:08:39	0:45:48	0.00	1.00	0.50	0.20	0.83	0.00	0.00	0.00	0.50	0	0.00	
7	Pad	7323			174.4	56.5	2193	0:03:05	0:37:08	0.00	1.00	0.50	0.20	0.83	0.00	0.00	0.00	0.50	0	0.00	
8	/gal 20/40 V	10667	0.50	5290	259.7	57.4	2176	0:04:31	0:34:03	0.00	1.00	0.50	0.20	0.83	0.00	0.00	0.00	0.50	0	0.00	
9	/gal 20/40 V	4981	0.50	2500	121.3	57.4	2118	0:02:07	0:29:32	0.00	1.00	0.50	0.20	2.00	0.00	0.00	0.00	0.50	0	0.00	
10	/gal 20/40 V	5010	0.51	2550	122.0	57.4	2105	0:02:08	0:27:25	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.00		0	0.00	
11	Pad							0:00:00	0:25:18	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	0.00	0	0.00	
12	gal 20/40 W	16947	1.99	33680	439.8	59.8	1881	0:07:21	0:25:18	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	0.00	0	0.00	
13	gal 20/40 W	9646	3.99	38440	271.1	60.1	1718	0:04:31	0:17:56	18.00	1.00	0.50	0.20	0.25	1.80	1.00	0.50	0.00	0		
14	gal 20/40 W	7924	4.86	38500	230.1	59.9	1506	0:03:50	0:13:26	18.00	1.00	0.50	0.20	0.00	1.80	1.00	0.50	0.00	1.80		
15	(top perf+3	6743			160.5	16.8		0:09:35	0:09:35	0.00	1.00	0.50	0.20	0.00	0.00	0.00	0.0	0.50	0		
16	ler Tub Variance				0.0			0:00:00	0:00:00	50.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
17	0				0.0			0:00:00	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
18	0				0.0			0:00:00	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
19	0							0:00:00	0:00:00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
										711.5	126.7	63.3	25.3	80.0	71.1	39.5	17.3	43.6	69.3	0	
										Used	740	135	67	27	85	73	40		41	71	5
										% diff	4%	7%	6%	7%	6%	3%	0%	-100%	-6%	2%	#DIV/0!
										Prime											
										Total	740	135	67	27	85	73	40	0	41	71	5

bbls	0	0	141,600	3192.3
35.71429	5% HCl Ac	1,500	gal	
2062.881	Slickwater	86,641	gal	Average Rate 46.6
941.119	eltaFrac 14	39,527	gal	
3039.714	Total Fluid	127,668	gal	
3192.268	Total Slurry	134,075	gal	

0	0
20/40 White	141,600
Total Proppa	141,600

TOP PERF	6,781	0
BOTTOM PERF	7,014	0
MID PERF	6,898	0
BHT	174	

BHT GRAD [°F/100-ft (+60°)]

API #	43-047-53006
AFE#	0
Sec. / Twp. / Rng.	S:35 / T:7S / R:20E
Well Name	Three Rivers 35-34-720
Company	Ultra Petroleum
Formation	0
Fluid Systems	18# DeltaFrac 140 (13) Hybrid
Date	November 27, 2014
Base Fluid, lb/gal	8.33
Sales Order #	0
County and State	Uintah, UT
Zone #1	

Total Perfs: 39			
Top Perf	Bottom Perf	SPF	# of shots
6781	6782	3	3
6792	6793	3	3
6801	6802	3	3
6821	6822	3	3
6842	6843	3	3
6854	6855	3	3
6883	6884	3	3
6909	6910	3	3
6925	6926	3	3
6950	6951	3	3
6963	6964	3	3
7012	7014	3	6
0	0	0	0
0	0	0	0

Start Time:	7:34 AM
End Time:	8:34 AM
Customer:	Joe Duncan



Well Name: Three Rivers 35-34-720 2 Green River

Date, Time & SO: 12/12/14 8:46 PM 901914971  
Top & Bottom Perfs: 6598 TO 6750.0  
Mid-Perf: 6674 9:44 PM

BHST: 148 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol  (bbl)	Pump Time	Fluid Name	Fluid Volume  (gal)	Proppant  Mass (lb)	Slurry  Rate (bpm)	Max Slurry  Rate (bpm)	Pressure  Ave (psi)	Pressure  Max (psi)	Pressure  Min (psi)	Prop Conc  Avg (PPG)	Prop Conc  Max (PPG)	Liquid Additives						Liquid Additives					
														WG-35  (Gel) (ppt)	CL-22UC  (Xlinker) (gpt)	BC 140  (Xlinker) (gpt)	Lo-Surf3000  (Surfactant) (gpt)	MC MX 2-282  (Scale) (gpt)	MC B 8614  (Biocide) gpt	CLAWeb  (Clay Cont.) (gpt)	FR-76  (Fric Red) (gpt)	andWedgeN  Conduct. Enh (gpt)	SP  (Breaker) (ppt)	OptiHTE  (Breaker) (gpt)	
2-1	Pad	18	0:02:14	FR Water	748		8.0	11.0	422	919	2						1.00		0.20	0.50	0.50				
2-2	Acid	17	0:01:35	Acid	1000		11.0	18.0	1014	1083	919														
2-3	Pad	120	0:03:31	FR Water	5022		34.0	51.0	2494	2833	1083						1.00	0.82	0.20	0.50	0.50				
2-4	Proppant Laden Fluid	471	0:08:08	FR Water	19432	7851	58.0	61.0	2160	2862	1903	0.40	0.46				1.00	0.82	0.20	0.50	0.50				
2-5	Pad	238	0:03:58	FR Water	9983		60.0	61.0	1982	2111	1831						1.00	0.82	0.20	0.50	0.50				
2-6	Proppant Laden Fluid	474	0:07:46	FR Water	19458	9710	61.0	64.0	2030	2149	1964	0.50	0.46				1.00	0.82	0.20	0.50	0.50				
2-7	Pad	238	0:03:54	FR Water	9991		61.0	61.0	2111	2173	2049						1.00	0.82	0.20	0.50	0.50				
2-8	Proppant Laden Fluid	238	0:03:54	FR Water	9762	4813	61.0	61.0	2032	2107	1963	0.49	0.54				1.00	0.82	0.20	0.50	0.50				
2-9	Proppant Laden Fluid	123	0:02:01	FR Water	5034	2658	61.0	61.0	1986	2008	1969	0.53	0.54				1.00	2.00	0.20	0.50	0.50				
2-10	Proppant Laden Fluid	124	0:02:02	FR Water	5075	2700	61.0	61.0	2010	2033	1994	0.53	0.57				1.00	0.25	0.20	0.50	0.50				
2-11	Pad			18# Delta 140										18.00		1.80	1.00	0.25	0.20	0.50			0.50	1.00	
2-12	Proppant Laden Fluid	423	0:07:03	18# Delta 140	16218	33458	60.0	64.0	2152	2400	1794	2.06	2.45	18.00		1.80	1.00	0.25	0.20	0.50			0.50	1.00	
2-13	Proppant Laden Fluid	260	0:04:08	18# Delta 140	9208	36749	63.0	64.0	2349	2434	2259	3.99	4.21	18.00		1.80	1.00	0.25	0.20	0.50			0.50	1.00	
2-14	Proppant Laden Fluid	185	0:02:56	18# Delta 140	6147	34718	63.0	64.0	2276	2308	2227	5.65	5.92	18.00		1.80	1.00		0.20	0.50		1.80	0.50	1.00	
2-15	Pre-Flush	161	0:03:40	PreFlush	2644		44.0	66.0	2293	3181	558						1.00		0.20	0.50	0.50				
2-16	Acid	48	0:01:05	Acid	2000		44.0	66.0	2293	3181	558														
2-17	Flush			Flush	4132												1.00		0.20	0.50	0.50				
					125582.0									Calculated Amt	568.31	0.00	56.83	122.85	77.82	24.57	61.43	45.64	66.15	15.79	31.57
														Actual Amt	640.00		61.00	115.10	77.90	10.00	59.10	50.90	49.20	26.30	34.10
														Percent Variance	12.6%	0.0%	7.3%	-6.3%	0.0%	-59.3%	-3.8%	11.5%	-25.6%	66.6%	8.0%
														Strap Amt	640.00		73.00	133.50	89.00	20.00	79.00	56.50	32.00	27.00	35.00
														Percent Variance	12.6%	0.0%	28.5%	8.7%	14.4%	-18.6%	28.6%	23.8%	-51.6%	71.0%	10.9%
	Slurry (bbl)	3137																							

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 3137  
Pump Time (Min) 0:57:53  
Clean Fluid (gal) 125582  
Proppant MB (lb) 132656  
Proppant Denso (lb) 130637

Avg Rate 50.0 BPM  
Avg Corrected Rate 53.0 BPM  
Max Rate 66.0 BPM  
Average Prop Con 1.8  
Average Pressure 1973.6 PSI  
Maximum Pressure 3181.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.34  
Wellhead Pressure: 66  
Broke Back: 770  
Pressure (Prop at Perfs): 1961  
ISDP: 1551

PPG  
PSI  
PSI  
PSI  
PSI

@ 10.0 BPM  
@ 61.0 BPM  
@ 0.666 PSUFT

TOTAL PROPPANT PUMPED:				Lbs
% of Job	Prop	Mesh	Quantity	Units
100%	20/40 White	20/40	135,275	Lbs
0%	0	20/40	0	Lbs
0%	0	20/40	0	Lbs

Initial Annulus Pressure 0.0 PSI  
Final Annulus Pressure 0.0 PSI

Variance 0.0%  
MB Vari -1.9%  
SS Vari -0.2%  
Dens Vari -3.4%  
SC Vari -100.0%  
Average Annulus Pressure 0.0 PSI  
Change in Annulus Pressure 0.0 PSI

CLEAN STREAM:

UV1 HRs	UV2 HRs	Transm.%
630	630	56

COMMENTS:

HES Engineer: Sabrina Dona  
Co\_Rep: Andy Hutchinson  
Crew: Red C

Xlink samples look good  
Good job by Crew  
3bbl overflush per Co Rep

Per co rep stages 2 and 3 were redesigned to pump acid in flush on S2 and no acid in S3 Skipped S11 and went straight to S12 Cut the flush stage. Original design after the redesign auto populated a setpoint of 2.5 of the sp, this was fixed when noticed before starting job but there was a miscommunication with treater and engineer and the set point started out as a 2.5 but was changed immediately when noticed. Treater accidentally auto staged in S14 co rep told him to just go to preflush.

RECEIVED: Jan. 13, 2015

Well Name: Three Rivers 35-34-720 4 Green River

Date, Time & SO: 12/13/14 12:13 PM 901914971  
Top & Bottom Perfs: 6017 TO 6244.0  
Mid-Perf: 6131 1:38 PM

BHST: 140 °F

HALLIBURTON

Stage	Stage Name	Slurry Vol (bbl)	Pump Time	Fluid Name	Fluid Volume (gal)	Proppant Mass (lb)	Slurry Rate (bpm)	Max Slurry Rate (bpm)	Pressure Ave (psi)	Pressure Max (psi)	Pressure Min (psi)	Prop Conc Avg (PPG)	Prop Conc Max (PPG)	Liquid Additives					Liquid Additives					andWedgeN Conduct. Ent (gpt)	SP (Breaker) (ppt)	OptiHTE (Breaker) (gpt)
														WG-35 (Gel) (ppt)	CL-22UC (Xlinker) (gpt)	BC 140 (Xlinker) (gpt)	Lo-Surf300 (Surfactant) (gpt)	MC MX 2-282 (Scale) (gpt)	MC B 8614 (Biocide) gpt	CLAWeb (Clay Cont.) (gpt)	FR-76 (Fric Red) (gpt)					
4-1	Pad	11	0:02:28	FR Water	471		4.6	10.7	2118	2920	1046								0.20	0.50	0.50					
4-2	Acid	24	0:02:42	Acid	1000		8.8	27.7	1940	2854	1740															
4-3	Pad	136	0:03:27	FR Water	5709		39.4	52.3	3229	3435	2854						1.00	0.48	0.20	0.50	0.50					
4-4	Proppant Laden Fluid	832	0:13:53	FR Water	34236	15475	59.9	60.2	2524	3396	2412	0.45	0.49				1.00	0.48	0.20	0.50	0.50					
4-5	Pad	317	0:05:17	FR Water	13333		60.1	60.1	2535	2607	2441						1.00	0.48	0.20	0.50	0.50					
4-6	Proppant Laden Fluid	834	0:13:53	FR Water	34289	16184	60.1	60.2	2537	2663	2467	0.47	0.48				1.00	0.48	0.20	0.50	0.50					
4-7	Pad	318	0:05:18	FR Water	13361		60.0	60.1	2738	2779	2656						1.00	0.48	0.20	0.50	0.50					
4-8	Proppant Laden Fluid	599	0:09:58	FR Water	24620	11374	60.0	60.3	2718	2778	2734	0.46	0.49				1.00	0.48	0.20	0.50	0.50					
4-9	Proppant Laden Fluid	122	0:02:01	FR Water	5014	2342	60.3	60.3	2751	2756	2734	0.47	0.51				1.00	2.00	0.20	0.50	0.50					
4-10	Proppant Laden Fluid	122	0:02:02	FR Water	5027	2423	60.4	60.6	2816	2961	2737	0.48	0.52	10.00			1.00	0.25	0.20	0.50	0.50		0.30	0.30		
4-11	Pad			16# Delta 140										16.00		1.60	1.00	0.25	0.20	0.50			1.00	1.00		
4-12	Proppant Laden Fluid	527	0:08:47	16# Delta 140	20260	40419	60.1	60.6	3122	3239	2961	2.00	2.18	16.00		1.60	1.00		0.20	0.50			1.00	1.00		
4-13	Proppant Laden Fluid	324	0:05:26	16# Delta 140	11532	44733	59.7	60.1	2898	3055	2797	3.88	4.05	16.00		1.70	1.00	0.25	0.20	0.50			1.00	1.00		
4-14	Proppant Laden Fluid	337	0:05:37	16# Delta 140	11316	60790	60.0	61.3	2762	2873	2699	5.37	6.10	16.00		1.80	0.80		0.20	0.50		1.80	1.00	1.00		
4-15	Flush	141	0:03:38	FR Water	5902		38.6	30.7	2878	3796	1839						0.50		0.10	0.30	0.50					
					186070.3									Calculated Amt	740.00	0.00	72.39	179.38	74.60	36.42	91.35	70.98	80.52	44.62	44.62	
														Actual Amt	772.00		71.10	171.00	73.70	36.90	92.20	72.20	105.10	44.60	44.60	
														Percent Variance	4.3%	0.0%	-1.8%	-4.7%	0.0%	0.0%	0.0%	1.7%	30.5%	0.0%	0.0%	
														Strap Amt	726.00		79.00	168.00	81.00	43.00	49.00	63.00	95.00	45.00	45.00	
														Percent Variance	-1.9%	0.0%	9.1%	-6.3%	8.6%	18.1%	-46.4%	-11.2%	18.0%	0.0%	0.0%	
	Slurry (bbl)	4645																								

Percent Variance is reported as 0% if variance is within 1 gallon.

Slurry (bbl) 4645  
Pump Time (Min) 1:24:27  
Clean Fluid (gal) 186070  
Proppant MB (lb) 193739  
Proppant Denso (lb) 184355

Avg Rate 49.4 BPM  
Avg Corrected Rate 52.9 BPM  
Max Rate 61.3 BPM  
Average Prop Con 1.7  
Average Pressure 2683.3 PSI  
Maximum Pressure 3796.0 PSI

BREAKDOWN INFORMATION:

Base Fluid: 8.34 PPG  
Wellhead Pressure: 1053 PSI  
Broke Back: 2918 PSI  
Pressure (Prop at Perfs) 2496 PSI  
ISDP: 1972 PSI

(Use weight slips for below amounts)			
TOTAL PROPPANT PUMPED:			
	184,002	Lbs	
% of Job	Prop	Mesh	Quantity
100%	20/40 White	20/40	184,002
0%	0	20/40	0
0%	0	20/40	0

Initial Annulus Pressure 0.0 PSI  
Final Annulus Pressure 0.0 PSI

Variance			
0.0%			
MB Vari	SS Vari	Dens Vari	SC Vari
5.3%	8.2%	0.2%	-100.0%

Average Annulus Pressure 0.0 PSI  
Change in Annulus Pressure 0.0 PSI

CLEAN STREAM:		
UV1 HRs	UV2 HRs	Transm. %
634	634	72

@ 4.0 BPM  
@ 60.2 BPM  
@ 0.755 PSI/FT

COMMENTS:

HES Engineer: Alvaro Meza Ligarda  
Co. Rep: Jeff Scott  
Crew: RED B

Xlink samples look good  
Good job by Crew  
3bbl overflush per Co Rep

0

# HALLIBURTON

**BHST:** 134 °F

Percent Variance is reported as 0% if variance is within 1 gallon.

Took a couple minutes to obtain crosslink but was able to obtain crosslink and continue on with crosslink stage.

RECEIVED: Jan. 13, 2015

RECEIVED: Jan. 13, 2015